

Fri 3d

**CALIFORNIA COASTAL COMMISSION**

SOUTH CENTRAL COAST AREA  
 89 SOUTH CALIFORNIA ST., SUITE 200  
 VENTURA, CA 93001  
 (805) 641-0142

**RECORD PACKET COPY**

Filed: 7/31/00  
 49<sup>th</sup> Day: 10/4/00  
 180<sup>th</sup> Day: 12/14/00  
 Staff: MEB-V *jk*  
 Staff Report: 9/20/00  
 Hearing Date: 10/10-13/00  
 Commission Action:

**STAFF REPORT: CONSENT CALENDAR**

**APPLICATION NO.** 4-00-171

**APPLICANT:** Malibu Investors **AGENT:** John Kilbane

**PROJECT LOCATION:** 27465 Latigo Bay View Drive, City of Malibu, Los Angeles County

**PROJECT DESCRIPTION:** Construct a 4,295 sq. ft., two story, 24-foot high, single family residence, with three car attached garage, swimming pool, septic system, and 65 cu. yds. of grading (65 cu. yds. cut) to be disposed of outside the coastal zone.

<b>Lot Area:</b>	73,120 sq. ft.
<b>Building Coverage:</b>	2,678 sq. ft.
<b>Pavement Coverage:</b>	5,543 sq. ft.
<b>Landscaped Area:</b>	67,577 sq. ft.
<b>Parking Spaces:</b>	3 covered
<b>Plan Designation:</b>	Residential I, One du/1 acre
<b>Project Density:</b>	One du/1.7 acre
<b>Height above existing grade:</b>	24 feet

**LOCAL APPROVALS RECEIVED:** Approval in Concept, City of Malibu Planning Department, dated 7/5/00; In Concept Approval (Septic System), City of Malibu Environmental Health Department, dated February 7, 2000; Los Angeles County Fire Department, Fuel Modification Plan, dated 5/2/00.

**SUMMARY OF STAFF RECOMMENDATION:**

The subject parcel is Lot 13, Tract 46851, of the 19-lot "Malibu Pacifica" subdivision located west of Latigo Canyon Road, in Malibu, approximately one mile north of Pacific Coast Highway. Lot 13 contains an approximate 6,000 square foot level pad previously graded pursuant to the underlying permit for the subdivision (CDP 5-89-1149 (Thorne)). Staff recommends approval of the project with special conditions addressing Plans Conforming to Geologic Recommendations, Landscape and Erosion Control Plan, Removal of Natural Vegetation, Wildfire Waiver of Liability, Drainage and Polluted Runoff, Color Restriction, and Deed Restriction on Future Development.

**SUBSTANTIVE FILE DOCUMENTS:** Malibu/Santa Monica Mountains Land Use Plan, Coastal Development Permits 89-1149 (Thorne) and 4-98-275 through 277 and 4-00-058, -069, -080, and -141 (Malibu Investors); Geosystems, Building Plan Review, 27465 Latigo Bay View Drive, November 29, 1999, Response to City of Malibu Geology and Geotechnical Engineering Review Sheets, February 9 & 24, 2000.

## **I. STAFF RECOMMENDATION**

**MOTION:** I move that the Commission approve Coastal Development Permit No. 4-00-171 pursuant to the staff recommendation.

### **STAFF RECOMMENDATION OF APPROVAL:**

Staff recommends a **YES** vote. Passage of this motion will result in approval of the permit as conditioned and adoption of the following resolution and findings. The motion passes only by affirmative vote of a majority of the Commissioners present.

### **RESOLUTION TO APPROVE THE PERMIT:**

The Commission hereby approves a coastal development permit for the proposed development and adopts the findings set forth below on grounds that the development as conditioned will be in conformity with the policies of Chapter 3 of the Coastal Act and will not prejudice the ability of the local government having jurisdiction over the area to prepare a Local Coastal Program conforming to the provisions of Chapter 3. Approval of the permit complies with the California Environmental Quality Act because either 1) feasible mitigation measures and/or alternatives have been incorporated to substantially lessen any significant adverse effects of the development on the environment, or 2) there are no further feasible mitigation measures or alternatives that would substantially lessen any significant adverse impacts of the development on the environment.

## **II. STANDARD CONDITIONS**

1. **Notice of Receipt and Acknowledgment.** The permit is not valid and development shall not commence until a copy of the permit, signed by the permittee or authorized agent, acknowledging receipt of the permit and acceptance of the terms and conditions, is returned to the Commission office.
2. **Expiration.** If development has not commenced, the permit will expire two years from the date on which the Commission voted on the application. Development shall be pursued in a diligent manner and completed in a reasonable period of time. Application for extension of the permit must be made prior to the expiration date.

3. Interpretation. Any questions of intent or interpretation of any condition will be resolved by the Executive Director or the Commission.
4. Assignment. The permit may be assigned to any qualified person, provided assignee files with the Commission an affidavit accepting all terms and conditions of the permit.
5. Terms and Conditions Run with the Land. These terms and conditions shall be perpetual, and it is the intention of the Commission and the permittee to bind all future owners and possessors of the subject property to the terms and conditions.

### III. Special Conditions

#### 1. Plans Conforming to Geologic Recommendations

- (a) All recommendations contained in the Geosystems, Building Plan Review, Dated November 29, 1999 shall be incorporated into all final design and construction including recommendations concerning foundations, grading, drainage, erosion control, retaining walls (new and existing), site preparation, friction piles, general construction specifications and precautions, floor slabs, pavement, swimming pool subdrainage, and sewage disposal. All plans must be reviewed and approved by the geotechnical consultants. Prior to the issuance of the coastal development permit, the applicant shall submit, for review and approval of the Executive Director, evidence of the consultants' review and approval of all project plans. Such evidence shall include affixation of the consulting geologists' stamp and signature to the final project plans and designs.
- (b) The final plans approved by the consultants shall be in substantial conformance with the plans approved by the Commission relative to construction, grading and drainage. Any substantial changes in the proposed development approved by the Commission which may be required by the consultants shall require an amendment to the permit or a new coastal permit. The Executive Director shall determine whether required changes are "substantial."

#### 2. Landscape and Erosion Control Plan and Fuel Modification

- A. Prior to the issuance of the coastal development permit, the applicant shall submit landscaping and fuel modification plans prepared by a licensed landscape architect for review and approval by the Executive Director. The plans shall incorporate the following criteria:
  - (1) All disturbed areas on the subject site shall be planted and maintained for erosion control and visual enhancement purposes within sixty (60) days of receipt of the Certificate of Occupancy from Los Angeles County. To minimize the need for irrigation and to screen or soften the visual impact

of development, all landscaping shall consist primarily of native/drought resistant plants as listed by the California Native Plant Society, Santa Monica Mountains Chapter, in their document entitled Recommended List of Plants for Landscaping in the Santa Monica Mountains, dated February 5, 1996. Invasive, non-indigenous plant species that tend to supplant native species shall not be used. Such planting shall be adequate to provide ninety (90) percent coverage within two (2) years, shall be repeated, if necessary, to provide the required coverage. This requirement shall apply to all disturbed soils including the existing graded pad and slopes. Plantings shall include vertical elements to screen and soften the visual impact of the residence as seen from Escondido Canyon.

- (2) Vegetation within 50 feet of the proposed house may be removed to mineral earth or planted in a zone of irrigated lawn or similar ground cover. Selective thinning, for purposes of fire hazard reduction shall be allowed in accordance with an approved long-term fuel modification plan submitted pursuant to this special condition. The applicant shall submit evidence to the satisfaction of the Executive Director that the fuel modification plan required herein has been approved by the Los Angeles County Forestry Department.
- (3) All plantings shall be maintained in good growing condition throughout the life of the project and, whenever necessary, shall be replaced with new plant materials to ensure continued compliance with applicable landscape requirements.
- (4) All development approved herein shall be undertaken in accordance with the final approved plans. Any proposed changes to the approved final landscape or fuel modification plans shall be reported to the Executive Director. No changes to said plans shall occur without a Coastal-Commission approved amendment to the coastal development permit, unless the Executive Director determines that no amendment is required.
- (5) Should grading take place during the rainy season (November 1 – March 31), sediment basins (including debris basins, desilting basins, or silt traps) shall be required on the project site prior to or concurrent with the initial grading operations and maintained through the development process to minimize sediment from runoff waters during construction. All sediment should be retained on-site unless removed to an approved dumping location.

**B. Monitoring Plan**

- (1) Five years from the date of the receipt of the Certificate of Occupancy for the residence the applicant shall submit, for the review and approval of the Executive Director, a landscape monitoring report, prepared by a licensed

Landscape Architect or qualified Resource Specialist, that certifies the on-site landscaping is in conformance with the landscape plan approved pursuant to this Special Condition. The monitoring report shall include photographic documentation of plant species and plant coverage.

- (2) If the landscape monitoring report indicates the landscaping is not in conformance with or has failed to meet the performance standards specified in the landscaping plan approved pursuant to this permit, the applicant, or successors in interest, shall submit a revised or supplemental landscape plan for the review and approval of the Executive Director. The revised landscaping plan must be prepared by a licensed Landscape Architect or a qualified Resource Specialist and shall specify measures to remediate those portions of the original plan that have failed or are not in conformance with the original approved plan.

**3. Removal of Natural Vegetation**

Removal of natural vegetation for the purpose of fuel modification within the 50 foot zone surrounding the proposed structure(s) shall not commence until the local government has issued a building or grading permit for the development approved pursuant to this permit. Vegetation thinning within the 50-200 foot fuel modification zone shall not occur until commencement of construction of the structure(s) approved pursuant to this permit.

**4. Wild Fire Waiver of Liability**

Prior to the issuance of the coastal development permit, the applicant shall submit a signed document which shall indemnify and hold harmless the California Coastal Commission, its officers, agents and employees against any and all claims, demands, damages, costs, expenses of liability arising out of the acquisition, design, construction, operation, maintenance, existence, or failure of the permitted project in an area where an extraordinary potential for damage or destruction from wild fire exists as an inherent risk to life and property.

**5. Drainage and Polluted Runoff**

Prior to the issuance of the coastal development permit, the applicant shall submit for the review and approval of the Executive Director, a drainage and polluted runoff control plan designed by a licensed engineer which minimizes the volume, velocity, and pollutant load of storm water leaving the developed site. The plan shall be reviewed and approved by the consulting geotechnical engineer and engineering geologist to ensure the plan is in conformance with the consultants' recommendations. The plan shall include but not be limited to the following criteria:

- (a) Post-development peak runoff rates and average volumes shall not exceed pre-development conditions.

- (b) Runoff from all roofs, parking areas, driveways and other impervious surfaces shall be collected and directed through a system of vegetated and/or gravel filter strips or other media filter devices. The filter elements shall be designed to 1) trap sediment, particulates, and other solids and 2) remove or mitigate contaminants through infiltration and/or biological uptake. The drainage system shall also be designed to convey and discharge runoff from the building site in a non-erosive manner.
- (c) The plan shall include provisions for maintaining the drainage and filtration systems so that they are functional throughout the life of the approved development. Such maintenance shall include the following: (1) the drainage and filtration system shall be inspected, cleaned and repaired prior to the onset of the storm season, no later than September 30<sup>th</sup> each year and (2) should any of the project's surface or subsurface drainage/filtration structures fail or result in increased erosion, the applicant/landowner or successor-in-interest shall be responsible for any necessary repairs to the drainage/filtration system and restoration of the eroded area. Should repairs or restoration become necessary, prior to the commencement of such repair or restoration work, the applicant shall submit a repair and restoration plan to the Executive Director to determine if an amendment or new coastal development permit is required to authorize such work.
- (d) The plan shall include, for the review and approval of the Executive Director, a swimming pool drainage plan prepared by a licensed engineer that is adequate to drain the subject pool's volume of stored water at full capacity and shall specify that swimming pool drainage shall not be accomplished by pumping the drained effluent onto adjacent open areas or slopes.

**6. Color Restriction**

The color of the structures, roofs, and driveway permitted hereby shall be restricted to a color compatible with the surrounding environment (white tones shall not be acceptable). All windows shall be comprised of non-glare glass.

PRIOR TO ISSUANCE OF THE COASTAL DEVELOPMENT PERMIT, the applicant shall execute and record a deed restriction, in a form and content acceptable to the Executive Director, which reflects the restrictions stated above on the proposed development. The document shall run with the land for the life of the structures approved in this permit, binding all successors and assigns, and shall be recorded free of prior liens and encumbrances that the Executive Director determines may affect the enforceability of the restriction. This deed restriction shall not be removed or changed without a Commission amendment to this coastal development permit.

**7. Future Improvements**

This permit is only for the development described in coastal development permit No. 4-00-171. Pursuant to Title 14 California Code of Regulations Sections 13250 (b)(6), the

exemptions otherwise provided in Public Resources Code Section 30610 (a) and (b) shall not apply to the entire parcel. Accordingly, any future improvements to the permitted structures, including but not limited to clearing of vegetation or grading, other than as provided for in the approved fuel modification, landscape and erosion control plan prepared pursuant to Special Condition 2, shall require an amendment to Permit No. 4-00-171 from the Commission or shall require an additional coastal development.

PRIOR TO THE ISSUANCE OF THE COASTAL DEVELOPMENT PERMIT, the applicant shall execute and record a deed restriction in a form and content acceptable to the Executive Director, reflecting the above restrictions on development in the restricted area. The deed restriction shall include legal descriptions of both the applicant's entire parcel and the restricted area. The deed restriction shall run with the land, binding all successors and assigns, and shall be recorded free of prior liens that the Executive Director determines may affect the enforceability of the restriction. This deed restriction shall not be removed or changed without a Commission amendment to this coastal development permit.

**8. Removal of Excavated Material**

Prior to the issuance of the coastal development permit, the applicant shall provide evidence to the Executive Director of the location of the disposal site for all excess excavated material from the site. Should the dumpsite be located in the Coastal Zone, a coastal development permit shall be required.

**IV. Findings and Declarations.**

The Commission hereby finds and declares:

**A. Project Description and Background**

The applicant proposes to construct a 4,295 sq. ft., two story, 24-foot high, single family residence, with three car attached garage, swimming pool, septic system, and 65 cu. yds. of grading (65 cu. yds. cut) to be disposed of outside the coastal zone. The subject parcel is Lot 13 of Tract 46851, of the 19-lot "Malibu Pacifica" subdivision located west of Latigo Canyon Road, in Malibu, approximately one mile north of Pacific Coast Highway (Exhibits 1-3)

The proposed project site is located at 27465 Latigo Bay View Drive (APN 4460-034-003). The building site on the subject 73,120 ft. parcel is an approximate 6,000 square foot graded pad. The subject parcel is one of nineteen lots created by this subdivision approved by the Commission in 1990 (CDP 89-1149 (Thorne)). Many of the parcels in the subdivision now known as "Malibu Pacifica" are subject to extensive open space deed restrictions. Approximately one-third of the western portion of lot 13 is within a open space easement (Exhibit 3). There is no visual setback limiting height of buildings and structures for subject Lot 13 specified by the underlying permit, as is true for the adjacent Lot 12 to the south. Lot 13 has a long narrow approximate 6,000 square foot

flat pad. The previously approved building site included the flat pad as well as an area to the west or just downslope of the pad (Exhibit 4).

There are no United States Geological Survey (U.S.G.S.) designated "blue line" drainage courses within the subdivision. Escondido Canyon Creek, a U.S.G.S. blue line stream and Environmentally Sensitive Habitat Area (ESHA), flows roughly parallel to the western and southern site boundaries of the subdivision at distances from 300-700 lineal feet to the west. The subject parcel drains in this direction. Escondido Canyon Creek contains environmentally sensitive habitats including a significant oak woodland, as well as the blue line stream and associated riparian area. Escondido Canyon/Falls Trail is located within and adjacent to the riparian corridor of the blue line stream.

The Commission has approved development of a number of single family residences in this subdivision including coastal development permit 4-98-275 (Malibu Investors) and applications 4-00-058, 4-00-069, -080, and -141 (Malibu Investors) approved during the year 2000. Previous applications reviewed by the Commission include: Lot 3, CDP 4-97-120 at 4765 Latigo Canyon Road; Lot 4, CDP 4-97-121 at 4767 Latigo Canyon Road; Lot 7, CDP 4-97-157 at 4775 Latigo Canyon Road; Lot 11, CDP 4-97-189 at 4771 Latigo Canyon Road; Lot 14, CDP 4-98-274 at 27457 Latigo Bay View Drive; Lot 16, CDP 4-98-275 at 27425 Calicut Road; Lot 18, CDP 4-98-277 at 27467 Calicut Road; Lot 17, CDP 4-98-276 at 27453 Calicut Road; and Lot 1, CDP 4-98-318 at 27460 Latigo Bay View Drive.

## B. Geology and Fire Hazards

Coastal Act Section 30253 provides that:

### Section 30253.

#### ***New development shall:***

***(1) Minimize risks to life and property in areas of high geologic, flood, and fire hazard.***

***(2) Assure stability and structural integrity, and neither create nor contribute significantly to erosion, geologic instability, or destruction of the site or surrounding area or in any way require the construction of protective devices that would substantially alter natural landforms along bluffs and cliffs. ...***

In addition, the Malibu/Santa Monica Mountains LUP, which the Commission has certified and utilized as guidance in past permit decisions, contains policies applicable to the proposed project:



***P 147 Continue to evaluate all new development for impact on, and from, geologic hazard.***

***P 149 Continue to require a geologic report, prepared by a registered engineer...***

***P 156 Continue to evaluate all new development for impact on, and from, fire hazard.***

The proposed development is located in the Santa Monica Mountains, an area that is generally considered to be subject to an unusually high amount of natural hazards. Geologic hazards common to the Santa Monica Mountains include landslides, erosion, and flooding. In addition, fire is an inherent threat to the indigenous chaparral community of the coastal mountains. Wild fires often denude hillsides in the Santa Monica Mountains of all existing vegetation, thereby contributing to an increased potential for erosion and landslides on property.

## **1. Geology**

Section 30253 of the Coastal Act requires that new development assure stability and structural integrity, and neither create nor contribute significantly to erosion, geologic instability, or destruction of the site or surrounding area. The applicant has submitted geology reports by Geosystems, Building Plan Review, 27465 Latigo Bay View Drive, November 29, 1999, Responses to City of Malibu Geology and Geotechnical Engineering Review Sheets, February 9 & 24, 2000.

As stated previously, the applicant proposes to construct a 4,295 sq. ft., two story, 24-foot high, single family residence, with three car attached garage, swimming pool, septic system, and 65 cu. yds. of grading (65 cu. yds. cut) to be disposed of outside the coastal zone. The proposed project would be sited on a previously constructed and graded approximate 6,000 square foot level pad created under a prior permit (5-89-1149, Thorne). A portion of the residence and deck extend a maximum of 16 feet beyond the western limit of the flat pad. This area is within the previously approved building site designated in the coastal development permit for the underlying subdivision. In the permit for the underlying subdivision the Commission previously addressed the geologic stability and mitigation measures necessary to undertake development of the subdivision. However, as addressed below, the consulting geologist has conducted an additional geologic investigation of the as-built pad and has recommended additional measures to ensure the proposed home is safe from geologic hazard.

The building pad is constructed on a south trending ridge that descends toward the west at a 2:1 gradient from the building pad toward Escondio Canyon on compacted fill slopes. The applicant proposes to excavate 65 cubic yards of material predominantly to construct a swimming pool. The applicant states that the resultant debris will be disposed of at the Calabasas Landfill.

The Geosystems report makes numerous recommendations regarding site preparation, foundation and building setbacks, swimming pool drainage, sewage disposal, and other considerations potentially affecting site stability. The consultant recommends that due to the proximity of the structure to the descending 2:1 slope that a deepened friction pile foundation system must be utilized for the residence and the swimming pool. The report concludes that:

It is the finding of this firm that the proposed building and or grading will be safe and that the site will not be affected by any hazard from landslide, settlement or slippage and the completed work will not adversely affect adjacent property in compliance with the County Code, provided our recommendations are followed.

Based on the recommendations of the consulting geologists, therefore, the Commission finds that the proposed development, as conditioned herein, minimizes risks to life and property from geologic hazards and assures stability and structural integrity, as required by Section 30253 of the Coastal Act, so long as the recommendations set forth in the Geosystems report are incorporated into the project plans. Therefore, the Commission finds it necessary to require the applicant to submit project plans that have been certified in writing by the consulting geologist and soils engineer as conforming to their recommendations (Special Condition 1).

Section 30253 of the Coastal Act states that new development shall not create or contribute significantly to erosion, in addition to other site stability issues addressed above. Special Condition 2 requires the applicant to submit for the Executive Director's approval landscape and fuel modification plans incorporating erosion control measures and providing for landscaping with suitable, locally native plant species. Established native plants, particularly chaparral shrub species, have deep root systems that hold soil in place and inhibit erosion. Use of the materials and methods required by that special condition will therefore stabilize the site immediately after disturbance and additionally protect against long-term site erosion. Temporary erosion control measures for implementation during the rainy season must also be incorporated into the landscape plan to protect excavated soils from erosion while construction is in progress.

The Commission notes that the use of native plants to landscape disturbed areas of the site (in addition to the use of native plants for overall landscape design), provides superior erosion control to that provided by more common applications, such as hydroseeding with non-native annual grasses as employed along roadcuts or burned areas. For these reasons, the Commission also finds it necessary to impose Special Condition 2 as a condition of approval of the proposed development, thereby ensuring that erosion is controlled and that native plants are appropriately utilized for slope stabilization and landscaping.

The slope below and to the west of the designated building sites extending into Escondido Canyon contains an open space area designated by the underlying subdivision. Exhibit 3 illustrates this open space area. This area and portions of lots 12, 14, 15 and the property to the north at 27480 Calicut Road will be affected by fire

clearance. The fuel modification area required for the proposed residence will overlap with fuel modification zones from the approved residence on lot 12, the existing residence on lot 14 and a future residence on lot 15. The property to the north at 27480 Calicut Road is developed with a single family residence located approximately 240 feet north of the proposed residence. As a result of the construction of the proposed residence approximately 100 feet of brush removal will be required on this lot. Special condition number 3 is necessary to ensure that removal of natural vegetation for the purpose of fuel modification does not take place without the proposed development being implemented. This will avoid unnecessary fuel modification without an underlying permitted development. Such fuel modification would be inconsistent with PRC Section 30253 provisions to ensure site stability and avoid potentially adverse impacts of erosion and sedimentation.

Therefore, for all of the reasons cited above, the Commission finds that the proposed project as conditioned by Special Conditions 1, 2 and 3 will be consistent with the requirements of Coastal Act Section 30253 applicable to geology and site stability.

## **2. Wild Fire**

Section 30253 of the Coastal Act also requires that new development minimize the risk to life and property in areas of high fire hazard. The Coastal Act recognizes that new development may involve the taking of some risk. Coastal Act policies require the Commission to establish the appropriate degree of risk acceptable for the proposed development and to establish who should assume the risk. When development in areas of identified hazards is proposed, the Commission considers the hazard associated with the project site and the potential cost to the public, as well as the individual's right to use his property.

Vegetation in the coastal areas of the Santa Monica Mountains consists mostly of coastal sage scrub and chaparral. Many plant species common to these communities produce and store terpenes, which are highly flammable substances (Mooney in Barbour, Terrestrial Vegetation of California, 1988). Chaparral and sage scrub communities have evolved in concert with, and continue to produce the potential for, frequent wild fires. The typical warm, dry summer conditions of the Mediterranean climate combine with the natural characteristics of the native vegetation to pose a risk of wild fire damage to development that cannot be completely avoided or mitigated.

Much of the Malibu Pacifica subdivision, including the applicant's parcel, burned during the 1993 Malibu Fire. Due to the fact that the proposed project is located in an area subject to an extraordinary potential for damage or destruction from wild fire, the Commission can only approve the project if the applicant assumes the liability from these associated risks. Through Special Condition 4, the wild fire waiver of liability, the applicant acknowledges the nature of the fire hazard which exists on the site and which may affect the safety of the proposed development. Moreover, through acceptance of Special Condition 4, the applicant agrees to indemnify the Commission, its officers, agents and employees against any and all claims, demands, damages, costs, expenses

or liability arising out of the acquisition, design, construction, operation, maintenance, existence, or failure of the permitted project in an area where an extraordinary potential for damage or destruction from wild fire exists as an inherent risk. The Commission finds that only as conditioned by Special Condition 4 is the proposed project consistent with Section 30253 of the Coastal Act applicable to hazards from wildfire.

C. Water Quality

The Commission recognizes that new development in the Santa Monica Mountains has the potential to adversely impact coastal water quality through the removal of native vegetation, increase of impervious surfaces, runoff, erosion, and sedimentation, and introduction of pollutants such as petroleum, cleaning products, pesticides, and other pollutant sources, as well as effluent from septic systems. Section 30231 of the Coastal Act states:

***The biological productivity and the quality of coastal waters, streams, wetlands, estuaries, and lakes appropriate to maintain optimum populations of marine organisms and for the protection of human health shall be maintained and, where feasible, restored through, among other means, minimizing adverse effects of waste water discharges and entrainment, controlling runoff, preventing depletion of ground water supplies and substantial interference with surface water flow, encouraging waste water reclamation, maintaining natural vegetation buffer areas that protect riparian habitats, minimizing alteration of natural streams.***

As stated previously, the applicant proposes to construct a 4,295 sq. ft., two story, 24-foot high, single family residence, with three car attached garage, swimming pool, septic system, and 65 cu. yds. of grading (65 cu. yds. cut) to be disposed of outside the coastal zone. The use of the site for residential purposes will introduce potential sources of pollutants such as petroleum, household cleaners, and pesticides, as well as other accumulated pollutants from rooftops and other impervious surfaces. As previously stated, the subject site drains toward Escondido Canyon and Creek, which is a designated ESHA.

The project plans include a surface drainage system designed by a civil engineer including rip rap water flow restrictors to accommodate anticipated runoff. However, the plans must address the Commission's concerns relative to water quality and polluted runoff. The removal of natural vegetation and placement of impervious surfaces associated with new residential development reduces infiltration of rainwater into the soil thereby increasing the rate and volume of runoff, which in turn causes increased erosion and sedimentation. Infiltration of precipitation into the soil reduces runoff and provides for the natural filtration of pollutants. When infiltration is prevented by impervious surfaces, pollutants in runoff are quickly conveyed to coastal streams and to the ocean. Thus, new development can cause cumulative impacts to the hydrologic cycle of an area and coastal waters by increasing and concentrating runoff leading to

stream channel destabilization, increased flood potential, increased concentration of pollutants, and reduced groundwater levels.

Such cumulative impacts can be minimized through the implementation of drainage and polluted runoff control measures. In addition to ensuring that runoff is conveyed from the site in a non-erosive manner, drainage and water pollution control measures should also include opportunities for runoff to infiltrate into the ground. Methods such as vegetated filter strips, gravel filters, and other media filter devices allow for infiltration. Because much of the runoff from the site is returned to the soil, overall runoff volume is reduced and more water is available to replenish groundwater and maintain stream flow. Slow surface flow of runoff allows sediment and other pollutants to settle into the soil where they can be filtered. The reduced volume of runoff takes longer to reach streams and its pollutant load is greatly reduced.

The project is conditioned to implement and maintain a drainage plan designed to ensure that runoff rates and volumes after development do not exceed pre-development levels and that drainage is conveyed in a non-erosive manner. This drainage plan is required in order to ensure that risks from geologic hazard are minimized and that erosion, sedimentation, and polluted runoff are minimized to reduce potential impacts to coastal streams, natural drainages, and environmentally sensitive habitat areas on or near the site. In order to further ensure that adverse impacts to coastal water quality do not result from the proposed project, the Commission finds it necessary to require the applicant to incorporate filter elements that intercept and infiltrate or treat the runoff from the site, as specified in Special Condition 5. Such a plan will allow for the infiltration and filtering of runoff from the developed areas of the site, most importantly capturing the initial "first flush" flows that occur as a result of the first storms of the season. This flow carries with it the highest concentration of pollutants that have been deposited on impervious surfaces during the dry season. Additionally, the applicant must monitor and maintain the drainage and polluted runoff control system to ensure that it continues to function as intended throughout the life of the development.

The Geosystems report states that the proposed pool will be provided with a subdrain system consisting of sand, a geomembrane, gravel, and a PVC drain outletted to the descending slope. This system is included in the application materials. However, the geotechnical report does not state how maintenance drainage of the swimming pool would be managed. Drainage of the swimming pool's full storage capacity onto the adjacent slope could saturate or erode the slope, resulting in destabilization and the potential failure of the slope. Consequently, the drainage and polluted runoff plan requirement must be augmented to require that the applicant ensure that maintenance or emergency drainage of the pool is directed to the paved streets and ultimately into the storm drain system through Executive Director's approval a swimming pool drainage plan prepared by a licensed engineer. The plan must specify, and show the means by which, all swimming pool drainage will be conducted to the street and storm drain system. Swimming pool drainage to open areas, or onto or within slope areas, is unacceptable.

The proposed development includes installation of an on-site septic system with a 2500 gallon tank to serve the residence. The 2500 gallon septic tank will be located on the southeast side of the building pad, from which effluent from the septic system will be pumped and disposed of through a septic pit. The applicants' engineering geologic consultants have evaluated the site relative to a potential septic system and conclude that the site is suitable for the septic system and that there will be no adverse impact to the site or surrounding area from use of the proposed septic system. Finally, the City of Malibu Department of Health Services has approved the design of the proposed sewage disposal system, determining that the system meets the requirements of the plumbing code. The Commission has found that conformance with the provisions of the plumbing code is protective of resources. Therefore, the Commission finds that the proposed project, as conditioned to incorporate and maintain a drainage and polluted runoff control plan, is consistent with Section 30231 of the Coastal Act.

**D. Visual Resources**

Section 30251 of the Coastal Act states that:

***The scenic and visual qualities of coastal areas shall be considered and protected as a resource of public importance. Permitted development shall be sited and designed to protect views to and along the ocean and scenic coastal areas, to minimize the alteration of natural land forms, to be visually compatible with the character of surrounding areas, and, where feasible, to restore and enhance visual quality in visually degraded areas. ...***

In addition, the certified Malibu/Santa Monica Mountains LUP provides policies regarding protection of visual resources, which are used as guidance and are applicable to the proposed development. These policies have been applied by the Commission as guidance, in the review of development proposals in the Santa Monica Mountains and include: ***P 125 sited and designed relative to LCP-designated scenic highways, views to and along the shoreline, and scenic coastal areas; P129 designed and located for attractive appearance and harmonious relationship with the surroundings; P130 In highly scenic areas and along scenic highways, sited and designed to protect views to and along the ocean and to and along other scenic features, minimize the alteration of natural land forms, conceal raw-cut slopes, compatible with and subordinate to the character the setting, and not intrude into the skyline as seen from public viewing places; P134 sited to conform to the natural topography.***

As described, the applicant proposes to construct a 4,295 sq. ft., two story, 24-foot high, single family residence, with three car attached garage, swimming pool, septic system, and 65 cu. yds. of grading (65 cu. yds. cut) to be disposed of outside the coastal zone. To assess any potential visual impacts of this project to the public, the Commission reviews the publicly accessible locations from which the proposed development is

visible, such as beaches, parks and trails. The Commission typically also examines the building site and the size of the structure.

The proposed development will be visible from portions of the Escondido Falls Trail, a popular hiking trail, stream and waterfall. Past Commission actions have considered that development of single family residences in the subject subdivision creates a visual impact which must be mitigated appropriately.

In its approval of the previous subdivision the Commission designated a building site on lot 13 which include the graded 6,000 sq. ft. pad as well as a designated building area below this pad (Exhibit 4). Parcel 13 was not subject to a requirement for a deed restriction providing a visual setback limiting height of buildings and structures as was required on lots 9, 10, 11 and 12. Parcel 13 due to the orientation of the building site is not as visible of a location from the trail as lots 9, 10 11 and 12 are. However, the building site and proposed structure will be visible from the trail.

The applicant has sited and designed the proposed structure on the existing pad with approximately 16 feet (maximum) of several portions of the structure and deck extending over the western edge of the pad (Exhibit 5). As noted above, the underlying subdivision designated specific building areas and building pads. The area just west and below the subject building pad is designated as a building site. The proposed design is well within the designated building site for this lot and is located for the most part on the flat pad. The proposed structure is a flat roof design and ranges in height from 22 to 24 feet from existing grade. The proposed design is consistent with the requirements of the previously approved subdivision and is not excessive in height or bulk.

The impact on public views from the trail can be mitigated by requiring that; the residence to be finished in a color consistent with the surrounding natural landscape; the windows of the proposed structure be of a non-reflective nature; and the driveway be colored in a manner that blends into the surrounding area. There is need to ensure any visual impacts associated with the colors of the structure and the potential glare of the window glass are minimized. Therefore, the Commission finds it necessary to require the applicant to use colors compatible with the surrounding environment, non-glare glass, and a natural colored driveway as required by Special Condition number six.

In addition, future developments or improvements to the property have the potential to create significant adverse visual impacts as seen from the surrounding area. It is necessary to ensure that future developments or improvements normally associated with a single family residence, which might otherwise be exempt, be reviewed by the Commission for compliance with the visual resource protection policies of the Coastal Act. Special Condition number seven, the future improvements deed restriction, will ensure the Commission will have the opportunity to review future projects for compliance with the Coastal Act.

Furthermore, visual impacts can be mitigated by requiring that the southwest facing slopes, i.e. those facing Escondido Canyon, be adequately landscaped. The landscaping plan, discussed above, will include native, drought resistant plants and partially screen and soften the visual impact of the structure, as required by Special Condition number two. Plantings will also include vertical elements to screen and soften the visual impact of the residence and garage as seen from Escondido Canyon.

In summary, the proposed project as conditioned will not result in a significant adverse impact to the scenic public views or character of the surrounding area in this portion of the Santa Monica Mountains. Thus, the Commission finds that the proposed project is consistent, as conditioned, with Section 30251 of the Coastal Act.

**E. Local Coastal Program**

Section 30604(a) of the Coastal Act states that:

Prior to certification of the local coastal program, a coastal development permit shall be issued if the issuing agency, or the commission on appeal, finds that the proposed development is in conformity with the provisions of Chapter 3 (commencing with Section 30200) of this division and that the permitted development will not prejudice the ability of the local government to prepare a local program that is in conformity with the provisions of Chapter 3 (commencing with Section 30200).

Section 30604(a) of the Coastal Act provides that the Commission shall issue a coastal development permit only if the project will not prejudice the ability of the local government having jurisdiction to prepare a Local Coastal Program which conforms with Chapter 3 policies of the Coastal Act. The preceding sections provide findings that the proposed project will be in conformity with the provisions of Chapter 3 if certain conditions are incorporated into the project and accepted by the applicant. As conditioned, the proposed development will not create adverse impacts and is found to be consistent with the applicable policies contained in Chapter 3. Therefore, the Commission finds that approval of the proposed development, as conditioned, will not prejudice the City's ability to prepare a Local Coastal Program for Malibu which is also consistent with the policies of Chapter 3 of the Coastal Act as required by Section 30604(a).

**F. California Environmental Quality Act**

Section 13096(a) of the Commission's administrative regulations requires Commission approval of a Coastal Development Permit application to be supported by a finding showing the application, as conditioned, to be consistent with any applicable requirements of the California Environmental Quality Act (CEQA). Section 21080.5(d)(2)(A) of CEQA prohibits a proposed development from being approved if there are feasible alternatives or feasible mitigation measures available which would substantially lessen any significant adverse effect which the activity would have on the environment.



The Commission finds that the proposed project, as conditioned, will not have significant adverse effects on the environment, within the meaning of the California Environmental Quality Act of 1970. Therefore, the Commission finds that the proposed project, as conditioned to mitigate the identified effects, is consistent with the requirements of CEQA and the policies of the Coastal Act.

LOS ANGELES CO.




EXHIBIT NO. 1
APPLICATION NO.
4-00-171
PROJECT LOCATION

SEE MAP 526

SEE MAP 628

Copyright 1998 Thomas Data Mapper

SFF MAP

RECEIVED

JUL 3 1 2000

CALIFORNIA  
COASTAL COMMISSION  
SOUTH CENTRAL COAST DISTRICT




EXHIBIT NO. 2
APPLICATION NO.
4-00-171
PLOT PLAN

SCALE: HORIZ. 1" = 40' VERT. 1" = 20'

DATE: OCTOBER 1998

SCALE: 1" = 40'

RECORDED BY: [Signature]

RECORDED: OCTOBER 1998

RETRACT PLAN - LOT 13

**LDC** LAND DESIGN CONSULTANTS INC.  
2500 S. GARDEN AVENUE, SUITE 200, ANAHEIM, CA 92805  
TEL: (714) 771-1111 FAX: (714) 771-1112

PLOT PLAN (LOTS 2, 5, 6, 11, 14 AND 15)  
TRACT 48851  
IN THE UNINCORPORATED COMMUNITY OF SANDGILES

DATE: OCTOBER 1998

SCALE: 1" = 40'

RETRACT PLAN - LOT 13

DATE: OCTOBER 1998

SCALE: 1" = 40'


RETRACT PLAN - LOT 13











SECOND FLOOR PLAN

JUL 31 2000

CALIFORNIA  
COASTAL COMMISSION  
SOUTH CENTRAL COAST

DEVELOPI

<b>EXHIBIT NO. 7</b>
<b>APPLICATION NO.</b>
4-00-171
<b>FLOOR PLAN</b>

**PROJECT:**  
MALIBU PACIFICA, LOT 13  
27463 LATIGO BAY VIEW DRIVE MALIBU, CA 90265

**PROJECT OWNER:**  
MALIBU INVESTORS, LLC  
2718 OCEAN PARK BLVD., SUITE 1048 SANTA MONICA, CA 90405  
TELEPHONE: (310) 398-4118 FAX: (310) 392-2117

**ARCHITECT:**  
ARCHWEST DEVELOPI  
2718 OCEAN PARK BLVD., SUITE 1048 SAN  
TELEPHONE: (310) 398-4118

1	2	3	4	5	6	7	8	9	10
---	---	---	---	---	---	---	---	---	----




RECEIVE

JUL 3 1 2000


CALIFORNIA  
COASTAL COMMISSIO  
SOUTH CENTRAL COAST DI

EXHIBIT NO. 8  
APPLICATION NO.

4-00-171  
FLOOR PLAN



FRONT ELEVATION 1/4" = 1'-0" SCALE




RIGHT SIDE ELEVATION 1/4" = 1'-0" SCALE

<p>PROJECT: <b>MALIBU PACIFICA, LOT 13</b> 27465 LATIGO BAY VIEW DRIVE, MALIBU, CA 90265</p>	<p>PROJECT OWNER: <b>MALIBU INVESTORS, LLC</b> 2716 OCEAN PARK BLVD., SUITE 1048, SANTA MONICA, CA 90405 TELEPHONE: (310) 399-4118</p>	<p>ARCHITECT: <b>ARCHW</b> 2716 OCEAN PARK TELEPHONE: (310) 399-4118</p>
--	--	--


RECEIVED

JUL 3 1 2000

CALIFORNIA  
COASTAL COMMISSION  
SOUTH CENTRAL COAST DISTRICT



Left side elevation 1/4" = 1'-0" scales



Rear elevation 1/4" = 1'-0" scales


EXHIBIT NO.  
APPLICATION NO. 9  
4-00-171  
ELEVATIONS

PROJECT:  
MALIBU PACIFICA, LOT 13  
2748 LATIGO BAY VIEW DRIVE, MALIBU, CA 90263


PROJECT OWNER:  
MALIBU INVESTORS, LLC  
2718 OCEAN PARK BLVD., SUITE 1048 SANTA MONICA, CA 90405  
TELEPHONE: (310) 398-4118 FAX: (310) 382-2117

ARCHITECT:  
ARCHI  
2718 OCEAN  
TELEPHONE

Section a  
1/4" = 1'-0" SCALE



Section b  
1/4" = 1'-0" SCALE



RECEIVED

JUL 31 2000

CALIFORNIA  
COASTAL COMMISSION  
SOUTH CENTRAL COAST DISTRICT

EXHIBIT NO. 10  
APPLICATION NO.

4-00-171

ELEVATIONS

PROJECT:  
MALIBU PACIFICA, LOT 13  
2745 LATIGO BAY VIEW DRIVE, MALIBU, CA 90263

PROJECT OWNER:  
MALIBU INVESTORS, LLC  
2716 OCEAN PARK BLVD., SUITE 1048, SANTA MONICA, CA 90405  
TELEPHONE: (310) 396-4118 FAX: (310) 392-2117

ARCHITECT:  
ARCHWEST DEVE  
2716 OCEAN PARK BLVD., SUITE 1  
TELEPHONE: (310) 399-4118

6

