

CALIFORNIA COASTAL COMMISSION

South Coast Area Office
200 Oceangate, Suite 1000
Long Beach, CA 90802-4302
(562) 590-5071

**Tu 10a**

October 26, 2000

TO: COMMISSIONERS AND INTERESTED PERSONS

FROM: PETER M. DOUGLAS, Executive Director
Charles Damm, Deputy Director
Al J. Padilla, Ports Coordinator

RECORD PACKET COPY

SUBJECT: Staff Recommendation on Port of Long Beach Port Master Plan Amendment No. 15 (allow 42 acre landfill in the common slip of Piers G and J in the Southeast Harbor Planning District, Planning District #8). For Commission consideration at meeting of November 14-17, 2000.

SUMMARY OF STAFF RECOMMENDATION

Staff recommends the Commission certify the Port of Long Beach Port Master Plan Amendment No.15, which would allow a 42 acre landfill in the Southeast Harbor Planning District Planning (Planning District #8). The staff recommends that the Commission find that the proposed amendment conforms with and carries out the port development, water quality, and marine resource policies of Chapter 8 of the Coastal Act.

I. Port Master Plan Amendment Procedure. Section 30716(a) and California Code of Regulations, Title 14 Section 13636 call for port master plan amendments to be certified in the same manner as provided in Section 30714 of the Coastal Act for certification of port master plans. Section 13628 of the regulations states that upon the determination of the Executive Director that the master plan amendment and accompanying materials required by Section 13628(a) are sufficient, the master plan amendment shall be deemed submitted to the Commission for purposes of Section 30714 of the Coastal Act. The subject amendment was deemed submitted on September 12, 2000. Within 90 days of this submittal date, the Commission, after public hearing, shall certify or reject the amendment, in whole or in part. The Commission may not modify the amendment as a condition of certification. If the Commission fails to take action on the amendment submittal within the 90-day period, the proposed amendment is deemed certified. The 90-day period expires on December 5, 2000.

Section 30714 also states that the Commission shall certify the amendment if the Commission finds both that:

1. The certified portions of the amendment conform with and carry out the policies of Chapter 8 of the Coastal Act.
2. Where the amendment provides for development listed as appealable in Section 30715, such development is in conformity with all the policies of Chapter 3 of the Act.

The proposed amendment provides for a 42 acre landfill within the common slip of Pier G and J in support of redevelopment and modernization of the existing marine terminal facilities. The amendment would also revise the plan's mitigation table to reflect the use of 21 acres of available Bolsa Chica mitigation credits. The proposed amendment does not include appealable development under Section 30715. Therefore, the sole standard of review would, thus, be the policies of Chapter 8.

II. STAFF RECOMMENDATION:

The staff recommends the Commission adopt the following resolution:

MOTION: *I move that the Commission certify the Port of Long Beach Master Plan Amendment No. 15.*

STAFF RECOMMENDATION OF CERTIFICATION:

Staff recommends a **YES** vote. Passage of this motion will result in certification of the Port Master Plan Amendment and adoption of the following resolution and findings. The motion to certify passes only upon an affirmative vote of a majority of the Commissioners present.

RESOLUTION TO CERTIFY PORT MASTER PLAN AMENDMENT:

The Commission hereby certifies the Port of Long Beach Master Plan Amendment No. 15 and adopts the findings set forth below on grounds that the amendment is consistent with Chapter 8 of the Coastal Act. Certification of the amendment complies with the California Environmental Quality Act because either 1) feasible mitigation measures and/or alternatives have been incorporated to substantially lessen any significant adverse effects of the amendment on the environment, or 2) there are no further feasible alternatives and mitigation measures that would substantially lessen any significant adverse impacts on the environment that will result from certification of the port master plan amendment.

III. FINDINGS AND DECLARATIONS

The Commission finds and declares as follows:

A. Previous Commission Action. The Commission certified the Port of Long Beach Port Master Plan on October 17, 1978. The Commission has reviewed fourteen amendments to the master plan since that date, most recently in July 1999.

B. Contents of Port Master Plan Amendments. Section 30716(a) of the Coastal Act and California Code of Regulations Title 14, Section 13656 call for Port Master Plan Amendments to be certified in the same manner as port master plans. Section 30711 of the Coastal Act provides, in part, that a port master plan shall include all the following:

1. The proposed uses of land and water, where known.
2. The proposed design and location of port land areas, water areas, berthing, and navigation ways and systems intended to serve commercial traffic within the area of jurisdiction of the port governing body.
3. An estimate of the effect of development on habitat areas and the marine environment, a review of existing water quality, habitat areas, and quantitative and qualitative biological inventories, and proposals to minimize and mitigate any substantial adverse impacts.
4. Proposed projects listed as appealable in Section 30715 in sufficient detail to determine their consistency with the policies of Chapter 3 (commencing with Section 30200) of this division.
5. Provisions for adequate public hearings and public participation in port planning and development decisions.

The Commission finds that the proposed Port Master Plan Amendment conforms with the provisions of Section 30711 of the Coastal Act. There are adequate details in the Port Master Plan Amendment submittal and associated materials for the Commission to make a determination of the proposed amendment's consistency with Chapter 8 policies of the Coastal Act.

The draft Port Master Plan Amendment and draft EIR were distributed by the Port of Long Beach for public review and comment on July 10, 2000. No comments were received. On August 7, 2000, the Board of Harbor Commissioners conducted a public hearing on the proposed amendment. On September 11, 2000, the Board

of Harbor Commissioners approved the amendment for submittal to the Coastal Commission.

C. Appealable Development. In determining the standard of review for the proposed master plan amendment, Section 30714 of the Coastal Act provides guidance and states in part that:

The Commission shall certify the plan, or portion of the plan, if the Commission finds both of the following:

- (a) The master plan, or certified portions thereof, conforms with and carries out the policies of this chapter.
- (b) Where a master plan, or certified portions thereof, provide for any of the developments listed as appealable in Section 30715, the development or developments are in conformity with all policies of Chapter 3 (commencing with Section 30200).

Section 30715(a) of the Coastal Act provides, in part, that:

- (a) ...After a port master plan or any portion thereof has been certified,... approvals of any of the following categories of development by the port governing body may be appealed to the commission:
 - (1) Developments for the storage, transmission, and processing of liquefied natural gas and crude oil in such quantities as would have a significant impact upon the oil and gas supply of the state or nation or both the state and nation. A development which has a significant impact shall be defined in the master plans.
 - (2) Waste water treatment facilities, except for those facilities which process waste water discharged incidental to normal port activities or by vessels.
 - (3) Roads or highways which are not principally for internal circulation within the port boundaries.
 - (4) Office and residential buildings not principally devoted to the administration of activities within the port; hotels, motels, and shopping facilities not principally devoted to the sale of commercial goods utilized for water-oriented purposes; commercial fishing facilities; and recreational small craft marina related facilities.
 - (5) Oil refineries.

(6) Petrochemical production plants....

The port's plan amendment does not provide for development listed as appealable in Section 30715(a). Therefore, the standard of review for the proposed amendment is Chapter 8 of the Coastal Act.

D. Summary of Proposed Plan Amendment. The Port of Long Beach proposes to amend its port master plan by obtaining Commission certification for revisions to Table V-1, Port of Long Beach Possible "Minor" Landfill Mitigation, page V-16, to reflect the use of 21 acres of the available Bolsa Chica mitigation credits. The proposed amendment will also add the following text to Section VI, headed District 8 – Southeast Harbor Planning District, under Anticipated Projects:

- *Piers G and J Terminal Development*

The Port proposes to construct 42 acres of new landfill in the common berthing slip between Piers G and J and develop necessary berth and wharf improvements for the purposes of combining and expanding the existing 235-acre marine cargo terminal complex into a 315-acre terminal. Twenty-one acres of mitigation credits, from the Port's participation in wetlands restoration at the Bolsa Chica Lowlands, will be used to offset any impacts associated with this "inner-harbor" landfill project.

The project site is located in the Southeast Harbor Planning District within the common slip of Piers G and J, in the southeast basin of the port of Long Beach (see Exhibit No. 1 and 2). Piers G and J have been used as marine terminals for containerized cargo.

The configuration of the existing Piers G and J terminals are characterized by two rectangular-shaped land areas with a combined land area of approximately 235 acres. Water access and berthing for the existing terminals is provided by a common north-to-south berthing slip that separates the two terminals.

According to the Port the current tenant at Pier G is relocating to the Port of Los Angeles. This relocation has afforded the Port of Long Beach with the opportunity to modernize by combining the Piers G and J marine terminals into one large, efficient marine terminal. Continued cargo growth from trade with Asia, development of large post-panamax vessels and carrier consolidations in the maritime industry, have necessitated the development of 300+ acre marine terminals. In an effort to modernize the existing terminal facility, the proposed amendment would fill the common berthing slip and create a new 4,200-foot long wharf in the Southeast Basin, with an east-west alignment.

The proposed landfill will allow cargo handling and staging operations to occur directly adjacent to the ship berthing and loading areas thereby increasing terminal efficiencies and limiting unnecessary cargo movements within the terminal. This enhancement will also allow the terminal operators to stage cargo for incoming vessels, which will decrease loading times and further improve terminal efficiencies.

The filling of the common berthing slip will eliminate berthing capacity from Berths G-227 through G-230 and Berths J-232 through J-234, which constitutes approximately 4,800 feet of existing wharf length. The filling of the common berthing slip and construction of a new wharf within the Southeast Basin would provide 4,200 feet of new wharf space. The reduced wharf length is adequate for a marine terminal of this size.

The proposed landfill would require approximately 2.25 million tons of rock for construction of the new wharf, and approximately 6.55 million cubic yards of fill material. Fill material would be obtained from other Port projects such as the Naval Complex Reuse, Queensgate Main Channel Deepening, Channel 2 Deepening, and/or various dredging activities throughout the Harbor District. All listed potential sources of fill material, except for the Channel 2 Deepening, have received regulatory approvals, including the necessary approvals from the Coastal Commission. The Port has indicated that they will obtain all necessary regulatory approvals prior to any dredging activities for Channel 2 Deepening.

The filling of the common berthing slip would also result in the loss of deep-water marine habitat in the Port's inner harbor area. The loss of marine habitat would be unavoidable since the project is infeasible without the landfill. To compensate for the loss of marine resources, the Port intends to apply mitigation credits from the Harbor Landfill Mitigation Credit Account approved by the Coastal Commission through certification of Port Master Plan Amendments No. 8 and 10.

In 1990 (PMPA # 6), the Commission approved a 12 acre landfill in the Southeast Basin south of the existing Pier J marine terminal (see Exhibit No. 5). The landfill will be incorporated into the proposed marine terminal expansion as proposed under this amendment request.

E. Conformance with the Coastal Act. In order for the Commission to certify the proposed amendment, the Commission must determine that the amendment conforms to the following Chapter 8 policies of the Coastal Act:

Section 30701.

The Legislature finds and declares that:

(a) The ports of the State of California, including the Humboldt Bay Harbor, Recreation, and Conservation District, constitute one of the state's primary economic and coastal resources and are an essential element of the national maritime industry.

(b) The location of the commercial port districts within the State of California, including the Humboldt Bay Harbor, Recreation, and Conservation District, are well established, and for many years such areas have been devoted to transportation and commercial, industrial, and manufacturing uses consistent with federal, state and local regulations. Coastal planning requires no change in the number or location of the established commercial port districts. Existing ports, including the Humboldt Bay Harbor, Recreation, and Conservation District, shall be encouraged to modernize and construct necessary facilities within their boundaries in order to minimize or eliminate the necessity for future dredging and filling to create new ports in new areas of the state.

Section 30705.

(a) Water areas may be diked, filled, or dredged when consistent with a certified port master plan only for the following:

(1) Such construction, deepening, widening, lengthening, or maintenance of ship channel approaches, ship channels, turning basins, berthing areas, and facilities as are required for the safety and the accommodation of commerce and vessels to be served by port facilities.

(2) New or expanded facilities or waterfront land for port-related facilities.

(3) New or expanded commercial fishing facilities or recreational boating facilities.

(4) Incidental public service purposes, including, but not limited to, burying cables or pipes or inspection of piers and maintenance of existing intake and outfall lines.

(5) Mineral extraction, including sand for restoring beaches, except in biologically sensitive areas.

(6) Restoration purposes or creation of new habitat areas.

(7) Nature study, mariculture, or similar resource-dependent activities.

(8) Minor fill for improving shoreline appearance or public access to the water.

(b) The design and location of new or expanded facilities shall, to the extent practicable, take advantage of existing water depths, water circulation, siltation patterns, and means available to reduce controllable sedimentation so as to diminish the need for future dredging.

(c) Dredging shall be planned, scheduled, and carried out to minimize disruption to fish and bird breeding and migrations, marine habitats, and water circulation. Bottom sediments or sediment elutriate shall be analyzed for toxicants prior to dredging or mining, and where water quality standards are met, dredge spoils may be deposited in open coastal water sites designated to minimize potential adverse impacts on marine organisms, or in confined coastal waters designated as fill sites by the master plan where such spoil can be isolated and contained, or in fill basins on upland sites. Dredge material shall not be transported from coastal waters into estuarine or fresh water areas for disposal.

(d) For water areas to be diked, filled, or dredged, the commission shall balance and consider socioeconomic and environmental factors.

Section 30706.

In addition to the other provisions of this chapter, the policies contained in this section shall govern filling seaward of the mean high tide line within the jurisdiction of ports:

(a) The water area to be filled shall be the minimum necessary to achieve the purpose of the fill.

(b) The nature, location, and extent of any fill, including the disposal of dredge spoils within an area designated for fill, shall minimize harmful effects to coastal resources, such as water quality, fish or wildlife resources, recreational resources, or sand transport systems, and shall minimize reductions of the volume, surface area, or circulation of water.

(c) The fill is constructed in accordance with sound safety standards which will afford reasonable protection to persons and property against the hazards of unstable geologic or soil conditions or of flood or storm waters.

(d) The fill is consistent with navigational safety.

Section 30708.

All port-related developments shall be located, designed, and constructed so as to:

- (a) Minimize substantial adverse environmental impacts.
- (b) Minimize potential traffic conflicts between vessels.
- (c) Give highest priority to the use of existing land space within harbors for port purposes, including, but not limited to, navigational facilities, shipping industries, and necessary support and access facilities.
- (d) Provide for other beneficial uses consistent with the public trust, including, but not limited to, recreation and wildlife habitat uses, to the extent feasible.
- (e) Encourage rail service to port areas and multicompany use of facilities.

1. Allowable Development

Goal 5 of the Port Master Plan recommends that land be developed for primary port facilities and port-related uses through intensification of uses, redevelopment of existing land, minor landfills, and enhancing port services located outside of the Harbor District. The proposed Piers G and J marine cargo terminal is consistent with Goal 5 of the Port master Plan through incorporation of the existing land area of the site and minor landfill. The filling of the common berthing slip and construction of a new wharf reduces the immediate need for major landfill projects to meet current terminal expansion demands.

The proposed amendment will provide waterside access to one large marine cargo terminal. The improvements will increase the size of the terminal facilities from 235 acres to 315 acres.

The proposed filling of the common berthing slip will eliminate berthing capacity from Berths G-227 through G-230 and Berths J-232 through J-234, which constitutes approximately 4,800 feet of existing wharf length. The filling of the common berthing slip and construction of a new wharf within the Southeast Basin would provide 4,200 feet of new wharf space. According to the ports, the reduced wharf length is adequate for a marine terminal of this size and will be able to accommodate the projected larger vessels, commonly referred to as "post-panamax" container vessels. These larger vessels carry between 5,000 and 7,000 twenty-foot containers and exceed 1,000 feet in length and 170 feet in width.

The Commission, therefore, finds that the proposed landfill, for the creation of a marine cargo terminal, is for port-related facilities and is allowable under Section 30705(a)(2).

2. Project Need.

The Coastal Act policies require that any approved landfill be the minimum necessary in order to achieve the purpose of the project. In this regard, the Commission has required that the port demonstrate the need for any proposed landfill through the use of a well-documented and conservative approach to justify the requested landfill acreage.

The proposed project involves filling approximately a net of 42-acres of water surface between Piers G and J. The landfill will allow the two separate terminals to be combined and used as a more efficient single terminal. The Port states that:

The current opposing berths found on Piers G and J are not consistent with modern container terminal designs that allow adequate cargo handling operations adjacent to linear wharf areas. The proposed landfill would provide the area necessary to modernize the terminal layout and accommodate a cargo handling area adjacent to the cargo loading operations. This additional area will allow the cargo to be sorted, staged, and briefly stored at the berth. The construction of a 4,200-foot wharf within the Southeast Basin will create a new deep-water marine berth. The new deep-water berth will accommodate modern, post-panamax container vessels, which will further increase the efficiency of this existing terminal by creating additional loading areas within the terminal.

The Port has indicated that forecasts for the amount of containerized cargo expected to move through the port is estimated at an average increase of between 3.8 percent and 5.6 percent per year through the year 2020 (Wharton Econometric Forecasting Associates, 1993). Port statistics show that the actual growth in containerized cargo volume has exceeded the forecasts. According to the Port actual growth between 1980 and 1987 was 11.7 percent. By the year 2020, cargo throughput at the San Pedro Bay ports is estimated to exceed 12 million TU (Twenty-foot equivalent Units), more than tripling current cargo flows (Mercer/DRI 1998).

The port states that:

For the Port to accommodate this increasing flow of international cargo, additional cargo handling facilities are necessary. Additional cargo handling capacity is typically created through expansion of existing facilities, or construction of new facilities on available land or new landfill sites. Where

possible, the Port has acquired private land areas within the Harbor District and surrounding area to accommodate the construction of new facilities on existing land area. As available land areas within the Long Beach Harbor District are developed for marine cargo terminal purposes, minor landfill projects such as the proposed project, will postpone the need for future major landfill expansion projects within the Port or other areas of the State.

Based on the Port's analysis, growth in containerized cargo volume has exceeded Port forecasts and, in order to accommodate this growth, additional and more efficient cargo handling facilities are necessary. The Port of Long Beach has been acquiring and developing existing land areas for development of port uses. Without a major landfill, the Port is attempting to increase the operating efficiencies within the Port by reuse of existing parcels of land and minor land fills. In addition, the Port has administered a policy of consolidating ancillary uses and oil operations located throughout the Harbor District to allow expansion of existing marine terminals. The Port has also been constructing on-dock and near-dock rail yards and other rail related infrastructure improvements to limit congestion and improve the movement of cargo through the terminals and the Port.

The proposed landfill is the minimum necessary to expand the existing terminal and is consistent with Section 30706(a). The fill has been designed for adequate geologic and navigational safety and will not result in any significant traffic conflicts between vessels. These considerations result in consistency with Sections 30706(c) and (d) and 30708(b). The Commission, therefore, finds, that the proposed landfill will be the minimum necessary in order to achieve the purpose of the project, will provide additional area for a high priority port use and will be consistent with Section 30706(a) and 30708(c) of the Coastal Act. Furthermore, the Commission also finds that the use of dredged sediments as landfill for the project rather than ocean disposal conforms with Section 30708(d), which states in part that port-related development shall provide for other beneficial uses consistent with public trust. The Commission and other state and federal regulatory agencies that review port development and expansion in southern California consistently urge the Port of Long Beach (and other ports and agencies that dredge in coastal waters) to pursue alternatives to ocean dumping.

3. Biological Impacts of Landfill and Mitigation Measures.

As noted above, Chapter 8 policies require that all port-related development minimize substantial adverse environmental impacts [Sections 30705(b)(c), 30706(b), 30708(a)]. The Port of Long Beach's final EIR for the proposed amendment addresses the potential for adverse effects on marine resources. The EIR states that within the project site there are three types of habitat: (1) deep-water (-35 to -55 feet), soft-bottom habitat, and fabricated subtidal and intertidal

solid substrates (pilings and bulkheads). No mudflats or sandy beaches occur within the proposed site.

According to the EIR, the soft-bottom infaunal community is dominated by polychaete worms, amphipods, and bivalve mollusks, and crustaceans (amphipods, etc.) The marine ichthyofauna is dominated generally by northern anchovy and Pacific Sardine. There is also white croaker, queenfish and California halibut.

The project area is not considered significant habitat area for any sensitive fish or wildlife species. The California least tern nests over three miles away, and the project site does not provide any foraging areas.

The proposed landfill would require the placement of approximately 42 acres of fill. Fill will consist of approximately 6.5 million cubic yards of sediment and 2.25 million tons of quarry rock for the construction of the dikes. Therefore, the 42 acre landfill will result in a net loss of approximately 1.5 acres of "inner-harbor" marine habitat (see Inner-Harbor Area map, Exhibit No. 4).

According to the Port the loss of marine habitat would be unavoidable since the project is infeasible without the landfill and all other alternatives discussed in the EIR are infeasible or more environmentally damaging. To compensate for the loss of marine resources, the Port intends to apply mitigation credits from the Harbor Landfill Mitigation Credit Account approved by the Coastal Commission through certification of Port Master Plan Amendments No.8 and No.10.

The Harbor Landfill Mitigation Credit Account was created through the Port's participation in a multi-agency wetland restoration at the Bolsa Chica Lowlands. The Commission approved the Port landfill mitigation credit account in Port Master Plan Amendment No. 8. Under PMPA No. 8, mitigation credits would be obtained by the Port through funding of land acquisition and wetland restoration at the Bolsa Chica Lowlands. The Port's participation created a total of 267 acres of landfill mitigation credits (Port Master Plan amendments No.8 and No.10) to be used for future landfill projects. The Commission found that the proposed wetland restoration project at Bolsa Chica would adequately compensate for marine resource losses that would occur from landfill projects within the ports.

Under PMPA NO. 8, the Port can use the mitigation credits at a ratio of 1:2 for "inner-harbor" landfills and 1:1 for "outer-harbor" landfills. The proposed Pier G and J landfill site is located in an "inner-harbor" area. The proposed "inner-harbor" 42 acre landfill will require 21 acres of the available Bolsa Chica mitigation credits based on the "inner-harbor" mitigation ratio of 1:2. This will reduce the remaining available mitigation credits (229.25 acres) in the account to a total of 208.25 acres once the landfill project is constructed.

The proposed amendment would permit activities that would generate adverse effects on marine habitat and resources, primarily as a result of loss of marine habitat due to filling. Adverse effects on existing marine life and habitat will be permanent due to filling and the loss of habitat area. However, the Port, based on the Commission approved mitigation ratios, will use 21 mitigation credits that have been accumulated through the Bolsa Chica Harbor Landfill Mitigation Credit Account. The use of mitigation credits for port landfill projects has been approved by the Commission as proper mitigation for loss of habitat within the Ports. The Commission has found that by purchasing mitigation credits for the restoration of Bolsa Chica wetlands, adverse landfill impacts on marine habitat would be minimized and would provide numerous beneficial uses consistent with the public trust. Therefore, the Commission finds that the projects' impacts from the loss of marine habitat will be properly mitigated and will be consistent with Sections 30706(b) and 30708(a) of the Coastal Act.

a. **Water Quality.** Dredging of material in the vicinity of the closure dike, placement of fill, armor rock, and pier pilings would result in short-term impacts to existing water quality due to resuspension of sediments and, possibly, sediment-associated contaminants. Short-term, insignificant turbidity increases would be expected during construction.

All dredging and in-water disposal activities would be carried out in accordance with federal (U.S. EPA and U.S. Army Corps of Engineers) and state (Regional Water Quality Control Board) regulations and permit conditions.

Wharf construction, including pile driving and vessel operations, would result in local, insignificant water quality impacts. The proposed amendment would permit activities that may generate long-term and short-term adverse effects on water quality, primarily as a result of construction activities. Dredging of material, placement of fill, armor rock, and pier pilings, could result in short-term impacts to existing water quality due to resuspension of sediments and, possibly, sediment-associated contaminants.

The Port will require control measures, such as the use of silt curtains during construction activities to reduce any potentially significant water quality degradation to a level of insignificance. These controls would be consistent with the requirements of the Clean Water Act's NPDES permit for construction activities. Moreover, all construction and dredging activities will be carried out in accordance with federal and state regulations and permit conditions. Therefore, the Commission finds that with the addition of the proposed mitigation measures and compliance with those standards, the adverse effects on marine resources or water quality will not be significant and the amendment is consistent with Sections 30705(b)(c) 30706(b), and 30708(a) of the Coastal Act.

4. Risk Management Plan

Section 30708(a) of the Coastal Act requires that all port-related developments be located, designed and constructed so as to minimize substantial adverse environmental impacts. The Commission certified the Ports' Risk Management Plan (RMP) on June 16, 1981, as Port Master Plan Amendment No. 1.

The Commission certified RMP is to be used for the siting of new hazardous liquid cargo facilities and any proposed modification, expansion or relocation of existing hazardous liquid cargo facilities in a manner that minimizes or eliminates risks to life and property in and around the port through the physical separation of hazards and "vulnerable resources". Vulnerable resources are defined in the RMP as significant residential, recreational and working populations, and facilities that have high economic value or are critical to the economy or national defense.

The risk to "vulnerable resources" from hazardous materials is analyzed by determining the area in which people would be hurt and property would be damaged if a "worst case" accident occurred. The area where "vulnerable resources" could be injured or damaged by a worst case accident is called a "hazard footprint". The boundary of a hazard footprint is determined by calculating the distance at which impacts of the worst probable events will be reduced to levels that are not likely to cause injury or property damage.

The generally does not allow placement of vulnerable resources within a hazard footprint. The design criteria of the RMP recognizes that there are situations where vulnerable resources may be located within a hazard footprint area. Under these situations, application of additional protection measures such as the installation of an approved early warning system, development of a comprehensive emergency evacuation plan, or personal training, may be required.

In the Port's analysis of the project there were no hazard footprints in the vicinity of the proposed project. Furthermore, the proposed cargoes that would be handled at the proposed marine cargo terminal would not include hazardous liquid bulk facilities and the terminal will not create any new hazardous liquid cargo facilities. Therefore, The Commission finds that the proposed project will be consistent with the Ports RMP and will minimize substantial adverse environmental impacts consistent with Section 30708(a) of the Coastal Act.

5. Summary

In summary, the Commission finds that the proposed port master plan amendment will allow the Port of Long Beach to construct needed cargo and shipping facilities and other port related facilities, and all adverse impacts to the marine environment will be adequately mitigated. As proposed, the port master plan amendment is

consistent with all applicable procedural provisions and policies of the California Coastal Act of 1976.

6. Consistency with the California Environmental Quality Act (CEQA).

The California Environmental Quality Act (CEQA) requires less environmentally damaging alternatives to be considered and the imposition of mitigation measures to lessen significant adverse effects that may result from the proposal. The Commission finds that for the reasons discussed in this report, all adverse effects have been mitigated to a level of insignificance thus there are no additional feasible alternatives or feasible mitigation measures available that could substantially reduce any adverse environmental impacts. The Commission further finds that the proposed Port Master Plan amendment will not result in significant environmental effects within the meaning of the California Environmental Quality Act.

Introduction and Project Description






EXHIBIT NO. 1
Application Number POLB PMPA #15
Vicinity Map California Coastal Commission



Scale in Feet
0 500 1000 1500 2000

EXHIBIT NO.	2
Application Number	20LB PMPA #15
District Map	
California Coastal Commission	

Figure 1
Planning District Map




Figure 2
Area of Proposed Landfill

EXHIBIT NO. 3

Application Number


POLB PMPA#15


Project Site

California Coastal Commission

Figure 6

INNER HARBOR AREAS





LOCATION OF ANTICIPATED PROJECTS

- | | |
|---|--|
| 1 Berths 95-97 Marine Terminal Development
(with 8 acres of fill) | 4 Pier J Southeast Basin Fill
(12 acres) |
| 2 North Harbor Acquisition/Development | 5 North American Materials |
| 3 West Seventh Street Terminal Expansion
(with 0.15 acres of fill) | 6 Master Road and Railway Transportation
Improvements (not shown) *
to Figure V-2. |

FIG

I-7

EXHIBIT NO. 5

APPLICATION NO.

PMPPA #15

PMPPA #6 L2nd L11



Commission