

CALIFORNIA COASTAL COMMISSION

South Coast Area Office
200 Oceangate, Suite 1000
Long Beach, CA 90802-4302
(562) 590-5071

**RECORD PACKET COPY**

Filed: March 15, 2000
49th Day: May 3, 2000
180th Day: September 11, 2000
Staff: KFS-LB *[Signature]*
Staff Report: March 23, 2000
Hearing Date: April 11-14, 2000
Commission Action:

STAFF REPORT: REGULAR CALENDAR

APPLICATION NUMBER: 5-99-205

APPLICANTS: Catalina Express
County of Orange

AGENT: Moffatt & Nichol Engineers

PROJECT LOCATION: Dana Point Harbor, City of Dana Point, Orange County

PROJECT DESCRIPTION: Demolition of a 48 foot portion of an existing 180 foot long 6 to 12 foot wide 18 inch high dock and removal of one 14 inch diameter piling. Replacement of the 48 foot section with a 40 foot long, 12 foot wide, 4 foot high float. Also, addition of 4 new 18" diameter steel pipe pilings and one 80 foot long, 12 foot wide, 4 foot high float. The new floats are being constructed to accommodate a 95 foot long 150 passenger ferry with service to Catalina Island. One hundred (100) parking spaces have been leased to accommodate the proposed use with access to an additional 50 parking spaces for overflow parking purposes.

LOCAL APPROVALS RECEIVED: City of Dana Point approval-in-concept dated February 2, 2000.

SUBSTANTIVE FILE DOCUMENTS: Dana Point Specific Plan/Local Coastal Program; marine biological survey dated May 13, 1999, titled *Marine Biological Survey Results, Proposed Catalina Express Landing, Dana Point Harbor, California* prepared by Coastal Resources Management of Corona del Mar, California; Regional Water Quality Control Board, San Diego Basin (9) waiver of waste discharge requirements dated December 6, 1999.

SUMMARY OF STAFF RECOMMENDATION:

The major issues of this staff report include fill of coastal waters for boating related purposes, potential impacts upon marine resources and public access. Staff recommends approval of the proposed development subject to two special conditions. Special Condition No. 1 requires minimization of construction impacts on harbor bottom and intertidal areas, appropriate storage of construction materials, removal of construction debris, and use of best management practices to reduce turbidity related impacts. Special Condition No. 2 imposes parking requirements to serve the expanded boating use including 100 spaces, plus 10 overflow spaces, as well as location and fee related requirements.

PROCEDURAL NOTE – Standard of Review:

The proposed development is occurring in Dana Point Harbor in the City of Dana Point. The Dana Point Harbor is a certified area under the Dana Point Specific Plan/Local Coastal Program. However, since the proposed development is located seaward of the mean high tide line, it is within the Commission's original permit jurisdiction under Coastal Act Section 30519(b) and must be evaluated for consistency with the Chapter 3 policies of the Coastal Act. The policies of the certified Dana Point LCP may be used for guidance.

Also, the proposed development includes use of existing parking spaces located within a portion of Dana Point Harbor that is certified under the Dana Point Specific Plan/Local Coastal Program. Typically, development located within a certified area requires a coastal development permit from the certified local government. However, in this case, the proposed physical development (i.e. dock demolition and construction) is occurring within an area of the Commission's original jurisdiction. This physical development is occurring to support a specific use, a ferry service, that is also located in the Commission's original jurisdiction. The attendant use requires provision of dedicated parking spaces in order to avoid adverse impacts upon public access which could occur if ferry passengers utilized public, as opposed to dedicated, parking spaces. While these dedicated parking spaces are being provided in a certified area, the development generating the need for the parking spaces is occurring in an area of original jurisdiction. Accordingly, no coastal development permit is required from the local government for the proposed parking spaces. Instead, this coastal development permit governs the proposed development and its contemplated mitigation.

I. STAFF RECOMMENDATION, MOTION AND RESOLUTION OF APPROVAL.

Staff recommends that the Commission make the following motion and adopt the following resolution to APPROVE the permit application with special conditions.

MOTION

I move that the Commission approve CDP #5-99-205 pursuant to the staff recommendation.

Staff recommends a YES vote. Passage of this motion will result in adoption of the following resolution and findings. The motion passes only by affirmative vote of a majority of the Commissioners present.

RESOLUTION OF APPROVAL WITH CONDITIONS

The Commission hereby **GRANTS** a permit, subject to the conditions below, for the proposed development on the grounds that the development will be in conformity with the provisions of Chapter 3 of the California Coastal Act of 1976, is located between the nearest public road and the sea and is in conformity with the public access and public recreation policies of the Coastal Act, and will not have any significant adverse effects on the environment within the meaning of the California Environmental Quality Act.

II. STANDARD CONDITIONS:

1. **Notice of Receipt and Acknowledgment.** The permit is not valid and development shall not commence until a copy of the permit, signed by the permittee or authorized agent, acknowledging receipt of the permit and acceptance of the terms and conditions, is returned to the Commission office.
2. **Expiration.** If development has not commenced, the permit will expire two years from the date this permit is reported to the Commission. Development shall be pursued in a diligent manner and completed in a reasonable period of time. Application for extension of the permit must be made prior to the expiration date.
3. **Compliance.** All development must occur in strict compliance with the proposal as set forth in the application for permit, subject to any special conditions set forth below. Any deviation from the approved plans must be reviewed and approved by the staff and may require Commission approval.
4. **Interpretation.** Any questions of intent or interpretation of any condition will be resolved by the Executive Director or the Commission.
5. **Inspections.** The Commission staff shall be allowed to inspect the site and the project during its development, subject to 24-hour advance notice.
6. **Assignment.** The permit may be assigned to any qualified person, provided assignee files with the Commission an affidavit accepting all terms and conditions of the permit.
7. **Terms and Conditions Run with the Land.** These terms and conditions shall be perpetual, and it is the intention of the Commission and the permittee to bind all future owners and possessors of the subject property to the terms and conditions.

III. SPECIAL CONDITIONS

1. CONSTRUCTION RESPONSIBILITIES

The permittee shall comply with the following construction-related requirements:

- (a) No construction materials, debris, or waste shall be placed or stored where it may be subject to wave erosion and dispersion;
- (b) Any and all debris resulting from construction activities shall be removed from the project site within 24 hours of completion of construction;
- (c) Disturbance of the harbor bottom and intertidal areas shall be minimized;
- (d) Turbidity shall be minimized through the use of best management practices including, but not limited to, the use of silt curtains.

2. PARKING REQUIREMENT

A. BY ACCEPTANCE OF THIS PERMIT, THE APPLICANT AND APPLICANT LANDOWNER ACKNOWLEDGES AND AGREES:

- 1. To provide 100 restricted parking spaces for exclusive use by the users of the proposed ferry service, within a private parking facility located within the Dana Point Harbor area east of Island Way, west of Embarcadero Place and south of Dana Point Harbor Drive; and
- 2. Between and including Memorial Day weekend and Labor Day weekend the permittee shall also provide at least an additional 10 dedicated parking spaces, for exclusive use by the users of the proposed ferry service, within a private parking facility located within the Dana Point Harbor area east of Island Way, west of Embarcadero Place and south of Dana Point Harbor Drive;
- 3. The hourly parking fee or maximum daily fee for use of the dedicated parking spaces shall not be greater than the hourly or maximum daily fee charged at the nearest public parking facility which offers at least 7 continuous hours of parking time;

B. PRIOR TO THE ISSUANCE OF THE COASTAL DEVELOPMENT PERMIT, the applicants and sublessor shall execute and record a lease restriction and sublease restriction as applicable, in a form and content acceptable to the Executive Director incorporating all of the above terms of subsection A of this condition. The lease restriction and sublease restriction shall include a legal description of the leased site and subleased site. The lease restriction and sublease restriction shall run with the land, binding all successors and assigns, and shall be recorded free of prior liens that the Executive Director determines may affect the enforceability of the restriction. The lease

restriction and sublease restriction shall not be removed or changed without a Commission amendment to this coastal development permit.

- C. **PRIOR TO ISSUANCE OF THE COASTAL DEVELOPMENT PERMIT**, the County, as applicant, landowner and master lease holder, shall submit a written agreement, subject to the review and approval of the Executive Director, stating that in the event of termination of the lease of the property that is the subject of Coastal Development Permit 5-99-205, and for so long as the development permitted pursuant to Coastal Development Permit 5-99-205 is in operation, the County will agree (i) to be bound to terms of clause (A) of this condition if it becomes the owners of the possessory interest in such property, and (ii) to include a provision in any subsequent lease of such property requiring the lessee to submit a written agreement to the Commission, for the review and approval of the Executive Director, incorporating all of the terms of clause (A) of this condition.

IV. FINDINGS AND DECLARATIONS:

The Commission hereby finds and declares:

A. PROJECT DESCRIPTION AND LOCATION

The applicant is proposing demolition of a 48 foot portion of an existing 180 foot long 6 to 12 foot wide 18 inch high dock and removal of one 14 inch diameter piling. Replacement of the 48 foot section with a 40 foot long, 12 foot wide, 4 foot high float and addition of 4 new 18" diameter steel pipe pilings and one 80 foot long, 12 foot wide, 4 foot high float (Exhibit 1, pages 4 and 5) is also proposed. The new floats are being constructed to accommodate a 95 foot long 150 passenger ferry with service to Catalina Island. In order to support the use associated with the proposed development (i.e. public ferry service), the applicant is proposing to provide 100 parking spaces (Exhibit 1, page 2 and page 6). In addition, the applicant is proposing to provide an additional 50 parking spaces on an as-needed basis for overflow parking purposes (Exhibit 1, page 2 and page 6). No physical development is proposed landward of the mean high tide line.

The development is proposed to occur at Dana Point Harbor, City of Dana Point, Orange County (Exhibit 1, page 1). The proposed physical development will occur seaward of and below the mean high tide line within the waters of Dana Point Harbor adjacent to Parcels 4 and 5 at the northeast side of the harbor (Exhibit 1, page 3 and 6). Parking will be located within the Dana Point Marina Company's parking lot number 2 (Exhibit 1, page 2). Ticketing, check-in and passenger loading will be accommodated within existing facilities operated by Dana Wharf Sportfishing.

State sovereign lands within Dana Point Harbor were legislatively granted to the County of Orange in 1961 (Exhibit 4). However, daily management of the harbor is performed by the Dana Point Marina Company on behalf of the County. Dana Point Marina Company leased the subject site to Dana Wharf Sportfishing. Dana Wharf Sportfishing subleased a portion of their site to Catalina Express. Dana Wharf Sportfishing was invited to join Catalina Express as co-

applicant on this coastal development permit application, but has declined (Exhibit 2). The County of Orange was also invited and has joined as co-applicant (Exhibit 3).

B. MARINE ENVIRONMENT

1. Fill of Coastal Waters

The proposed project involves the placement of four 18 inch diameter steel pilings in open coastal waters (i.e. Dana Point Harbor). These pilings constitute "fill" of open coastal waters as defined in Section 30108.2 of the Coastal Act. More specifically, the proposed pilings will have a total fill of approximately seven (7) square feet. Under Section 30233 of the Coastal Act, fill of open coastal waters is only allowed when several criteria are met: (a) the project must fall within one of the use categories specified; (b) the proposed project must be the least environmentally damaging feasible alternative; and (c) feasible mitigation measures to minimize adverse environmental effects must be provided. Section 30233 of the Coastal Act states, in part:

(a) The diking, filling, or dredging of open coastal waters, wetlands, estuaries, and lakes shall be permitted in accordance with other applicable provisions of this division, where there is no feasible less environmentally damaging alternative, and where feasible mitigation measures have been provided to minimize adverse environmental effects, and shall be limited to the following:

(4) In open coastal waters, other than wetlands, including streams, estuaries, and lakes, new or expanded boating facilities and the placement of structural pilings for public recreational piers that provide public access and recreational opportunities.

The proposed project meets the first criteria because the proposed development is for a boating facility. Fill of open coastal waters, such as Dana Point Harbor, for the construction of a boating facility is an allowable use under Section 30233(a)(4) of the Coastal Act. The proposed project requires 4 pilings. The pilings are necessary to secure the proposed dock floats which are necessary to support a boating facility.

The applicant has indicated that the floats will be used solely for boating purposes. Specifically, the applicant proposes to use the floats as a staging area and to facilitate the loading and unloading of passengers and supplies to the boat. The boat will provide ferry service from Dana Point to Catalina Island. This ferry service is for use by the general public. Based on the uses proposed by the applicant, the Commission finds that the proposed dock floats constitute a boating facility. As a boating facility, the proposed pier platform is a use specifically allowed under Section 30233(a)(4) of the Coastal Act.

In addition to the use-related issue, Section 30233 of the Coastal Act also requires that any project involving fill of open coastal waters be the least environmentally damaging feasible alternative. One way to reduce environmental damage to open coastal waters is to minimize the quantity of fill. In this case, the applicant is proposing to remove an existing 14 inch diameter pile and place 4 new 18 inch diameter piles. The removal of one piling will result in

the removal of 1 square foot of fill. The four new 18 inch diameter pilings will have a total fill of 7 square feet. In addition, the applicant has indicated that the proposed pilings are the smallest diameter and the minimum quantity necessary to meet current engineering standards for loads related to the 95 foot length boat. Therefore, since the proposed project minimizes the quantity of fill of coastal waters, the Commission finds that the proposed project is the least environmentally damaging feasible alternative.

Finally, Section 30233 of the Coastal Act also requires that feasible mitigation measures to minimize adverse environmental effects must be provided. The proposed project meets this requirement because the proposed pilings will provide habitat for marine organisms such as mollusks. This replacement hardscape habitat will mitigate for the loss of hard bottom habitat resulting from the placement of the pilings.

The proposed project will result in the fill of open coastal waters for a boating facility, which is an allowable use under Section 30233 of the Coastal Act. This boating facility will increase public access to coastal waters and Catalina Island by providing a public ferry service from Dana Point to Catalina Island. In addition, the proposed project is the least environmentally damaging alternative, and does provide feasible mitigation measures. Therefore, the Commission finds the proposed project is consistent with Section 30233 of the Coastal Act.

2. Marine Organisms and Water Quality

The proposed development involves construction within coastal waters. The applicant has submitted a marine biological survey dated May 13, 1999, titled *Marine Biological Survey Results, Proposed Catalina Express Landing, Dana Point Harbor, California* prepared by Coastal Resources Management of Corona del Mar, California, which evaluates impacts upon marine resources.

The survey indicates that the primary physical habitat in the project area is rock riprap. This rip rap forms a 35 foot wide slope which extends from the existing bulkhead to a point underneath the proposed dock. Soft bottom habitat occurs beyond the riprap. The riprap area is colonized by variety of invertebrates and fish including barnacles, limpets, mussels, solitary ascidians, encrusting sponges, California lobsters, kelp bass and opaleye perch. Soft bottom areas are colonized by short-spined seastar, tube dwelling and burrowing polychaete worms, mollusks, and crustaceans. No eelgrass was found in or nearby the project area.

Section 30230 of the Coastal Act states:

Marine resources shall be maintained, enhanced, and where feasible, restored. Special protection shall be given to areas and species of special biological or economic significance. Uses of the marine environment shall be carried out in a manner that will sustain the biological productivity of coastal waters and that will maintain healthy populations of all species of marine organisms adequate for long-term commercial, recreational, scientific, and educational purposes.

Section 30231 of the Coastal Act states:

The biological productivity and the quality of coastal waters, streams, wetlands, estuaries, and lakes appropriate to maintain optimum populations of marine organisms and for the protection of human health shall be maintained and, where feasible, restored through, among other means, minimizing adverse effects of waste water discharges and entrainment, controlling runoff, preventing depletion of ground water supplies and substantial interference with surface water flow, encouraging waste water reclamation, maintaining natural vegetation buffer areas that protect riparian habitats, and minimizing alteration of natural streams.

The placement of pilings has the potential to impact marine organisms and water quality in the project area. Driving pilings can result in direct impacts upon marine organisms inhabiting the location where the piles are being placed. In addition, driving piles can result in the suspension of sediment in the water column resulting in shading and sedimentation impacts upon organisms. Finally, the placement of dock floats can result in shading impacts upon sensitive light-dependent aquatic vegetation (i.e. eelgrass).

Drawings submitted by the applicant indicate that the proposed pilings will be placed in the hardbottom rip rap area. While the proposed pilings will result in impacts upon the hardbottom habitat, the pilings themselves will provide replacement hard-substrate habitat. Since the surface area of the pilings is greater than the area of impact the proposed project will increase the quantity of hard-substrate habitat. In addition, since there is no eelgrass in the project area, shading impacts from the placement of the dock floats is not anticipated to have any adverse impact upon any sensitive aquatic vegetation.

Due to the proposed project's location on the water, the proposed work may have adverse impacts upon water quality and attendant adverse impacts upon biological resources. Storage or placement of construction materials, debris, or waste in a location subject to wave erosion and dispersion would result in adverse impacts upon the marine environment that would reduce the biological productivity of coastal waters. For instance, construction debris entering coastal waters may cover and displace soft bottom habitat. In addition, the use of machinery in coastal waters not designed for such use may result in the release of lubricants or oils that are toxic to marine life. Also, the proposed pile driving activities may also result in the temporary suspension of sediment in the water column.

The Regional Water Quality Control Board has reviewed the proposed project and determined that State water quality standards will be protected and has issued a waiver of waste discharge requirements (Exhibit 6). In addition, the biological survey states that sedimentation and shading impacts are not likely due since the installation process is a temporary, short term event. The biological survey also indicates that no mortality of marine organisms is anticipated as a result of construction related sedimentation impacts. However, the biologist recommends that best management practices be used during installation to ensure that sedimentation impacts do not occur. In order to avoid adverse construction related impacts upon marine resources, Special Condition 1 outlines construction related requirements to provide for the safe storage of construction materials and the safe disposal of construction debris. In addition, Special Condition 1 requires the applicant to utilize best management

practices, such as a silt curtain, during installation of the pilings to avoid any turbidity related impacts upon water quality and marine organisms. As conditioned, the Commission finds the proposed development is consistent with Section 30230 and 30231 of the Coastal Act.

C. PUBLIC ACCESS

Section 30604(c) of the Coastal Act requires that every coastal development permit issued for any development between the first public road and the sea include a specific finding regarding the conformity of the proposed development with the public access and recreation policies of Chapter 3 of the Coastal Act. The proposed development is located between the first public road and the sea.

Section 30212 of the Coastal Act states, in relevant part:

(a) Public access from the nearest public roadway to the shoreline and along the coast shall be provided in new development projects except where:

(2) adequate access exists nearby.

Section 30224 of the Coastal Act states:

Increased recreational boating use of coastal waters shall be encouraged, in accordance with this division, by developing dry storage areas, increasing public launching facilities, providing additional berthing space in existing harbors, limiting non-water-dependent land uses that congest access corridors and preclude boating support facilities, providing harbors of refuge, and by providing for new boating facilities in natural harbors, new protected water areas, and in areas dredged from dry land.

Section 30252 of the Coastal Act states, in relevant part:

The location and amount of new development should maintain and enhance public access to the coast by...(4) providing adequate parking facilities or providing substitute means of serving the development with public transportation...

Sections 30210, 30211 and 30212 of the Coastal Act require that new development provide maximum public access and recreation, avoid interference with the public's right of acquired access, and provide public access from the nearest public roadway to the shoreline and along the coast except under certain circumstances.

Dana Point Harbor is a recreation-oriented facility that is open to the public. Public walkways and picnic areas, as well as restaurants, sport fishing, and recreation-oriented boating are available to the public. There is an existing public dock adjacent to the proposed development which provides a convenience docking area for visitors to the Dana Wharf area. In addition, there is a public boat launch ramp within 500 feet of the subject site. These existing facilities provide public access.

The proposed development consists of the addition of pilings and dock floats within Dana Point Harbor to accommodate the berthing of a boat providing ferry service to Catalina Island. The proposed ferry service is open to the public and pursuant to Public Utilities Commission Decision #93291, the ferry service is considered a "public convenience and necessity". This ferry service will provide access to the City of Avalon, a popular tourist and recreation-oriented community located on Catalina Island.

Section 30252 of the Coastal Act requires the protection of public access to the beach. An adequate quantity of public parking spaces maintains this access. However, public access can be adversely affected if commercial uses, such as the proposed ferry service, in the coastal zone do not provide adequate on-site or dedicated parking to serve the proposed development. In cases of inadequate parking, ferry users would displace other public users from public parking spaces.

The applicant is proposing to provide 100 dedicated parking spaces to provide parking for ferry passengers. These 100 parking spaces are being leased from the Dana Point Marina Company, an entity which manages the harbor on behalf of Orange County, the owner of the harbor. The proposed parking is located in Parking Lot No. 2, one of several parking lots managed by the Dana Point Marina Company for use by tenants of the harbor. These parking spaces are located approximately 2000 feet from the passenger loading area. Passengers of the ferry service are drop off passengers near the ticketing and docking area and then are directed to park in the dedicated parking lot.

The berthing location where the proposed work is to occur is being subleased from Dana Wharf Sportfishing, which has the master lease for the site from the Dana Point Marina Company. In order to handle any demand for parking exceeding the proposed 100 dedicated spaces, the applicant is proposing to provide an additional 50 parking spaces on an as-needed overflow basis to support the ferry service. These spaces are provided in a parking lot adjacent to the passenger loading area. These parking spaces are being provided to Catalina Express by Dana Wharf Sportfishing and are available because Dana Wharf Sportfishing has reduced the number of sportfishing vessels within its fleet. In the absence of these vessels, there has been an attendant reduction in demand for parking spaces within the parking lot at Dana Wharf (Exhibit 5).

The applicant has provided a parking study which indicates that the proposed 100 parking spaces plus 50 overflow parking spaces is adequate to support the ferry use. The parking study is based upon actual operation of the 95 foot long, 150 passenger vessel during a peak use season. While the proposed dock improvements have not been undertaken to accommodate continued use of the site for the 150 passenger vessel, the vessel has been operating from the site since the beginning of 1999.

This parking study shows four time periods including a peak week during the summer (August 13 through August 19, 1999), a peak week during the spring including Easter (March 26, thorough April 1, 1999), a peak week at the end of the summer (October 15 through 21, 1999) and during a low use period (December 24 through 30, 1999). This study shows that during only one day in the week, Saturday, during the peak summer season, did parking demand exceed 100 parking spaces. This peak demand was 110 parking spaces. The

additional 10 parking spaces not provided in the primary 100 space parking lot were provided in the 50 space Dana Wharf Sportfishing parking lot. No public parking spaces were required to support the ferry service.

The proposed 100 parking spaces and access to at least an additional 10 parking spaces within the 50 space overflow parking lot are required to ensure that the proposed use does not result in any adverse parking related impact upon public access in Dana Point Harbor. Therefore, the Commission imposes Special Condition 2 which requires the permittee to maintain a minimum of 100 dedicated parking spaces at all times during which the ferry service operates. In addition, Special Condition 2 requires the permittee to provide at least an additional 10 parking spaces for use during the peak use season between Memorial Day and Labor day.

The dedicated 100 space parking and 50 space "overflow" parking areas are more conveniently located to access the ticketing and proposed Catalina Express docking area than any publicly available public parking spaces, the nearest of which occur at Puerto Place within "Parcel 14" as identified on Exhibit 1, page 6). A person using the dedicated parking spaces may do so by parking in Parking Lot #2 and then returning to the loading area by walking along a wide public walkway adjacent to the "East Basin" of the harbor. However, if a person were to instead park at the public parking spaces they would need to walk from Puerto Place, along Dana Point Harbor Drive and then down Street of the Golden Lantern, which is a much longer walk than that required when parking at the Parking Lot #2.

Also, the daily fee for use of the dedicated parking spaces is \$7. The nearest public parking facility charges \$1 per hour, 24-hours a day, with no daily maximum. The typical visit to Catalina Island involves either a morning departure and late afternoon return or an overnight stay. Since under either typical scenario at least 7 hours parking time is required, the charge for use of the dedicated parking spaces is equal to or less than the cumulative fee charged for use of the nearest public parking facility. Since the dedicated parking spaces are more conveniently located and equal to or less expensive than the nearest public parking facility, it is not anticipated that ferry users would choose to use the public parking facility over the dedicated spaces.

However, in order to ensure that these conditions are retained, Special Condition 2 requires that the permittee maintain exclusive access to parking spaces in an area convenient to ferry users and at a price which encourages use of those dedicated spaces rather than use of public parking spaces. Accordingly, the permittee must maintain exclusive access to parking spaces in an area located in Dana Point Harbor area east of Island Way, west of Embarcadero Place and south of Dana Point Harbor Drive. Also, Special Condition 2 requires that the hourly parking fee or maximum daily fee for use of the restricted parking spaces shall not be greater than the hourly or maximum daily fee charged at the nearest public parking facility which offers at least 7 continuous hours of parking time. Finally, Special Condition 2 requires that any proposed changes to the location or quantity of parking spaces provided shall be reported to the Executive Director. No changes to the location of parking spaces, quantity of parking spaces, or fee charged for use of the dedicated parking spaces, shall occur without a Commission amendment to this coastal development permit unless the Executive Director determines that no amendment is required.

As conditioned, the Commission finds the proposed development is consistent with the public access policies of the Coastal Act.

D. LOCAL COASTAL PROGRAM

The proposed development is occurring in Dana Point Harbor in the City of Dana Point. The Dana Point Harbor is a certified area under the Dana Point Specific Plan/Local Coastal Program. However, since the proposed development is located seaward of the mean high tide line, it is within the Commission's original permit jurisdiction under Coastal Act Section 30519(b) and must be evaluated for consistency with the Chapter 3 policies of the Coastal Act. The policies of the certified Dana Point LCP may be used for guidance.

E. CALIFORNIA ENVIRONMENTAL QUALITY ACT

Section 13096 of the Commission's regulations requires Commission approval of Coastal Development Permit applications to be supported by a finding showing the application, as conditioned by any conditions of approval, to be consistent with any applicable requirements of the California Environmental Quality Act (CEQA). Section 21080.5(d)(2)(A) of CEQA prohibits a proposed development from being approved if there are feasible alternatives or feasible mitigation measures available which would substantially lessen any significant adverse effect which the activity may have on the environment.

The proposed project has been conditioned for consistency with the marine resource and public access protection policies of the Coastal Act. Mitigation measures, in the form of special conditions require 1) conformance with construction responsibilities, and 2) conformance with parking requirements. The proposed development, as conditioned, is consistent with the Chapter 3 policies of the Coastal Act. There are no feasible alternatives or mitigation measures available which will lessen any significant adverse impact the activity would have on the environment. Therefore, the Commission finds that the proposed project is consistent with CEQA and the policies of the Coastal Act.



RECEIVED

DEC 24 1999

CALIFORNIA
COASTAL COMMISSION

COASTAL COMMISSION
5-99-201

EXHIBIT # **1**

117°42

41

DATE GRID
AD 1927:
d. zone V. is
cks at 2,000
last three digits

DANA POINT HARBOR

Scale 1:20,000

DANA POINT

SOUNDINGS IN FATHOMS


AT MEAN LOWER LOW WATER

FIXED BRIDGE
HOB CL 45 FT
VERT CL 20 FT

Nearest
Public
Parking

Catalina Express
Dock and Ticket Sales

Four
COLREGS DEMARCATION
LINE 80 1110
(see note A)



RECEIVED
DEC 24 1999
CALIFORNIA
COASTAL COMMISSION


COASTAL COMMISSION
5-99-205
EXHIBIT # 2 OF 4

CATALINA EXPRESS



CATALINA EXPRESS
OPERATIONAL COMPONENTS

FIGURE
A


COASTAL COMMISSION
5-99-205
EXHIBIT # 1
PAGE 3 OF 6




HARBOR OFFICE



EAST JETTY



BAIT DOCK



FUEL DOCK

RECEIVED
South Coast Region
CALIFORNIA
COASTAL COMMISSION
JUN 7 1999

CATALINA EXPRESS


CATALINA EXPRESS LANDING AT DANA PT. HARBOR
PROPOSED LOCATION

Figure
1

RECEIVED
South Coast Region

DEC 24 1999

CALIFORNIA
COASTAL COMMISSION



SCALE
1" = 10'

Prepared by: Moffatt & Nichol Engineers
Date: May 1999
K: \4381\coastal\newsys.dwg

COASTAL COMMISSION
EXHIBIT # 5-99-205
PAGE 4 OF 6

CATALINA EXPRESS


PROPOSED DOCK AT DANA PT. HARBOR
PLAN VIEW

RECEIVED

South Coast Region

DEC 24 1999

CALIFORNIA
COASTAL COMMISSION



COASTAL COMMISSION
5-99-205


EXHIBIT # 1
PAGE 5 OF 6

SCALE
1" = 10'

Prepared by: Moffatt & Nichol Engineers
Date: May 1999
K:\4381\coastal\newsys.dwg

CATALINA EXPRESS

PROPOSED DOCK AT DANA PT. HARBOR
CROSS SECTION



GENERAL PARCEL MAP
Dana Point Harbor **figure 14**

SOUTH COAST PLANNING UNIT
LOCAL COASTAL PROGRAM
ENVIRONMENTAL MANAGEMENT AGENCY

COUNTY OF ORANGE

COASTAL COMMISSION
5-99-205

EXHIBIT # 1
 PAGE 6 OF 6

03/15/00
03/15/2000

13:21
13:12

MOFFATT & NICHOL → 5905084
1/144968212

DANA WHARF SPORTFISH



**DANA WHARF SPORTFISHING
& WHALE WATCHING**

34675 Golden Lantern
Dana Point, CA 92629

3/15/00

Catalina Express
Berth 95
San Pedro, Ca. 90731
Att: Greg Bombard

Dear Greg,

In response to Moffat and Nichol Engineers letter dated 3/14, we do not wish to be a co-applicant on Catalina Express's application for a Coastal Development permit.

Please understand that we still support this project 100% and feel it is very important that the dock be modified to better serve the public. If I can assist in any other way please let me know.

Sincerely,

Michael Hansen
President
Dana Wharf Sportfishing

COASTAL COMMISSION
5-99-205

EXHIBIT # 2

PAGE 1 OF 1

Phone: (949) 496-5794

Fax: (949) 496-8212

www.danawharfsportfishing.com



COUNTY OF ORANGE
PUBLIC FACILITIES & RESOURCES DEPARTMENT

Vicki L. Wilson, Director
 300 N. Flower Street
 Santa Ana, CA

P.O. Box 4048
 Santa Ana, CA 92702-4048

Telephone: (714) 834-2300
 Fax: (714) 834-5188

March 16, 2000

Mr. Greg Bombard
 Catalina Express
 Berth 95
 San Pedro, California 90731

Subject: Application For Coastal Development Permit #5-99-205

Dear Mr. Bombard:

A letter from your consultant, Moffatt & Nichol Engineers, has been received inviting the County of Orange to be a coapplicant for subject permit. The permit is requested in order to construct an extension to an existing dock in Dana Point Harbor to better serve the public. The County is the Lessor of the parcel on which the proposed dock will be installed and, in fact, has an unencumbered interest in a portion of the area on which the dock will be constructed.

The County does want to be a coapplicant on this permit application. If there are any additional steps the County must take in order to be a coapplicant, please let us know and we will satisfy the requirements promptly.

We are looking forward to this project being implemented in order to provide enhanced public access to the passenger boat and to accommodate the handicapped. If you have any questions regarding the above or need additional documentation, please contact Grace Dove of PFRD Real Property at (714) 834-8793.

Very truly yours,

Larry Park, Manager
 Harbors, Beaches and Parks
 Coastal and Historical Facilities

cc: Clare Fletcher

COASTAL COMMISSION
 5-99-205

EXHIBIT # 3
 PAGE 1 OF 1

CALIFORNIA STATE LANDS COMMISSION
100 Howe Avenue, Suite 100-South
Sacramento, CA 95825-8202



PAUL D. THAYER, Executive Officer

(916) 574-1800 FAX (916) 574-1810

California Relay Service From TDD Phone 1-800-735-2922
from Voice Phone 1-800-735-2929

RECEIVED
FEB 09 2000

Contact Phone: (916) 574-1892

Contact FAX: (916) 574-1925

**CALIFORNIA
COASTAL COMMISSION**

February 3, 2000

File Ref: G 09-00

Karl Schwing
California Coastal Commission
200 Oceangate, Suite 1000
Long Beach, CA 90802-4302

Dear Mr. Schwing:

SUBJECT: Proposed New Dock and Modification of Existing Dock By Catalina Express Landing, East Side of Dana Point Harbor, Orange County, CDP 5-99-205

Staff of the California State Lands Commission (CSLC) has reviewed information submitted by Moffatt & Nichol Engineers concerning the subject project. The sovereign lands located within Dana Point Harbor have been legislatively granted to the County of Orange, pursuant to Chapter 321, Statutes of 1961, with minerals reserved to the State. Therefore, the County assumes the day-to-day management and permitting authority for projects such as this. The 1961 statute does, however, reserve minerals to the State. Should any dredging be necessary in conjunction with this dock project, that aspect of the project would require formal authorization by the CSLC.

Susie Ming of Moffatt & Nichol Engineers has advised us that the County is fully cognizant of their responsibilities as the trustee of Dana Point Harbor, including the issuance of any permits necessary for this project. Therefore, unless dredging is involved, no further authorization from the CSLC is necessary.

If you have any questions, please call me at (916) 574-1892.

Sincerely,

Jane E. Smith
Public Land Management Specialist
Southern California Region

cc: Susie Ming, Moffatt & Nichol

COASTAL COMMISSION
5-99-205

EXHIBIT # 4
PAGE 1 OF 1

**DANA WHARF SPORTFISHING
& WHALE WATCHING**

34675 Golden Lantern
Dana Point, CA 92629

3/13/2000

Catalina Express
Berth 95
San Pedro, Ca. 90731
Att: Greg Bombard

Dear Mr. Bombard,

In our original agreement in June of 1998 we allocated 50 of our parking spaces to Catalina Express to use for the 50 passenger Express boat servicing Catalina Island.


We were able to give these parking spaces to you because four of our fishing vessels had left our operation and have not returned.

When the 149 passenger vessel replaced the 50 passenger vessel, those spots remained allocated for Catalina Express. Although all Catalina Express parking is at an off site lot we still have these 50 spots in a back up situation.

We feel that the current parking solution meets all the needs of the operation, and have already experienced maximum capacity on the vessel with no parking problems to date, and we do not for see any problems in the future.

Should you have any questions please do not hesitate to call.

Thank You,


Michael Hansen
President
Dana Wharf Sportfishing

COASTAL COMMISSION

5-99-205

EXHIBIT # 5

PAGE 1 OF 1

