CALIFORNIA COASTAL COMMISSION

45 FREMONT STREET, SUITE 2000 SAN FRANCISCO, CA 94105-2219 VOICE: (415) 904-5200 FAX: (415) 904-5400 TDD: (415) 597-5885



W21a

CD-0001-19

MAY 24, 2019

APPENDIX F: May 13, 2019 supplemental information from the Trinidad Rancheria regarding hazards

Trinidad Rancheria Responses to Coastal Commission Staff Report Regarding Coastal Consistency Determination CD-0001-19

HAZARDS

Page 3, Paragraph 3 – Hazards

The Staff Report indicated:

"The draft EA for the proposed project states that a portion of the proposed site for the hotel is a landslide area, and a draft geotechnical feasibility and preliminary design report suggests that either the hotel footprint will be modified to avoid the landslide or extensive slope stabilization features will be required to ensure structural integrity and stability of the hotel. However, the details of a selected option to ensure slope stability and structural integrity for the hotel are not provided in the BIA consistency determination and are not described in the draft EA for the proposed project. The staff recommends the Commission find it does not have sufficient information to find the proposed project consistent with Sections 30253(a) and 30253(b) of the Coastal Act. See page 21 for additional information and accompanying analysis that staff is recommending the BIA would need to provide to enable the Commission to find the project consistent with Section 30253(a) and 30253(b)."

Staff Report – Hazards – Page 20-21

F. Hazards

Section 30253(a) and (b) of the Coastal Act state:

Development shall do all of the following:

- a) Minimize risks to life and property in areas of high geologic, flood, and fire hazard.
- b) Assure stability and structural integrity, and neither create nor contribute significantly to erosion, geologic instability, or destruction of the site or surrounding area or in any way require the construction of protective devices that substantially alter natural landforms along bluffs and cliffs.

The draft EA for the proposed project states that while Humboldt County is located in a seismically active region, the proposed hotel would not be located within or on an active fault and there is little chance of an active fault on the project site. However, the draft EA for the proposed project also states:

"The active landslide that currently extends from the southwest corner of the proposed hotel southwest toward Scenic Drive has the potential to affect the foundation for the proposed hotel. However, the active landslide is relatively shallow in nature and may be

readily stabilized utilizing measures such as retaining wall systems, slope reconstruction and sub-drainage elements."

To address the potential effect to the hotel foundation, the draft EA for the proposed project identifies the following mitigation measures:

• Prior to construction of the Hotel foundation, the contractor shall implement one of the slope stabilization options recommended by the soil engineer...options include soil nail walls, reconstructed embankment, soldier pile, and welded wire walls.

A draft geotechnical feasibility and preliminary design report for the proposed hotel (attached as an appendix to the draft EA for the proposed project) also states:

Based on preliminary discussions with the design team, we expect the hotel footprint will be modified to avoid the slide feature. Depending on the final hotel layout, some level of slope stabilization should be considered to limit headward encroachment of the slide. Appropriate stabilization work may include such options as a soil nail wall, welded wire wall, or cantilevered soldier pile wall, with wall height likely on the order of 10-15 feet. If the hotel footprint cannot be modified to avoid the slide, then more extensive slope stabilization will be required, such as a drained reconstruction embankment, regraded slope, tie-bank soldier pile wall(s) or a tiered wall system.

From this information, it appears that the options for addressing the risks posed by the landslide, and also thus assuring the stability and structural integrity of the proposed hotel, have not been completely determined. Given the potential considerations raised in the draft geotechnical feasibility and preliminary design report for the proposed hotel, the selected option involves extensive slope stabilization measures. However, the details of a selected option have not been provided in the BIA consistency determination and are not described in the draft EA for the proposed project.

Therefore, staff recommends that the Commission find there is insufficient information to find the proposed project consistent with Sections 30253(a) and 30253(b) of the Coastal Act. Staff further recommends that the Commission find that in order for it to find the proposed project consistent with Sections 30253(a) and 30253(b), the BIA would need to provide information describing the measures(s) proposed to mitigate the existing landslide hazard, including design details or other proposed measures and their potential location. In addition, if stabilization measures require extensive grading or construction of retaining walls, the BIA would need to provide information sufficient for the Commission to determine consistency of those measures with Section 30251 of the Coastal Act, including its requirement to minimize the alternation of natural land forms.

Section 30253(a), 30253(b), and 30251

Development shall do all of the following:

- a) Minimize risks to life and property in areas of high geologic, flood, and fire hazard.
- b) Assure stability and structural integrity, and neither create nor contribute significantly to erosion, geologic instability, or destruction of the site or surrounding area or in any way require the construction of protective devices that substantially alter natural landforms along bluffs and cliffs.

Trinidad Rancheria Response

Section 30253(a) and (b)

- a) The Rancheria will minimize risks to life and property as part of the design of this project.
- b) The Rancheria will also assure stability and structural integrity through the design process with the direction and assistance of Crawford and Associates, Geotechnical Engineers. (See Geotechnical Update Letter in attachments).

Section 30251 Scenic and visual qualities

The scenic and visual qualities of coastal areas shall be considered and protected as a resource of public importance. Permitted development shall be sited and designed to protect views to and along the ocean and scenic coastal areas, to minimize the alteration of natural land forms, to be visually compatible with the character of surrounding areas, and, where feasible, to restore and enhance visual quality in visually degraded areas. New development in highly scenic areas such as those designated in the California Coastline Preservation and Recreation Plan prepared by the Department of Parks and Recreation and by local government shall be subordinate to the character of its setting.

Trinidad Rancheria Response

The Rancheria agrees that at the time of the release of the draft EA options for addressing the risks posed by the landslide had not been completely determined. There was a draft Geotechnical report at the time, and the citations in the draft EA were from that report. As noted below, the conclusion of the Preliminary Study indicated that "further geotechnical study by this office will be completed for final design." The Preliminary Geotechnical Feasibility Study was completed in November of 2016. (See Final Geotechnical Feasibility Report in Attachments).

The conclusion of this report indicated:

"Based on the data presented above, we consider the site is suitable for construction of the proposed hotel and complementary facilities provided that appropriate mitigation of the geologic hazards is incorporated into project design. Below, we provide a discussion of the geologic hazards, mitigation alternatives, and preliminary geotechnical recommendations for the structure foundations, retaining walls, pavement structural sections and site grading. We anticipate that the project will be somewhat modified based on these conclusions. Further geotechnical study by this office will be completed for final design, based on the final structure layout, retaining walls and site grading."

Additionally, the Principal Engineer of Crawford and Associates, Inc., Rick Sowers, wrote a Geotechnical Update Letter on May 2, 2019, for further clarification and in support of his earlier preliminary design report. Mr. Sowers' letter specifically addresses concerns raised by the Coastal Commission in its February 14, 2019 Staff Report. Below is a summary of the letter's findings.

Slope stabilization:

The updated letter recommends a "Mechanically Stabilized Earth (MSE) wall or welded wire wall retaining system, such as a Hilfiker wall". This recommendation has been reviewed by the project's civil engineer and is included in the current design. See included site plan markup "00 - SITE PLAN - HAZARDS - 11x17.pdf" showing the location of the existing slide. (See Geotechnical Update Letter in attachments).

Site Retaining Walls:

The updated letter recommends "MSE or Hilfiker walls are also considered appropriate here, with design heights to about 20 feet." This recommendation has been reviewed by the project's civil engineer and is included in the current design. (See attached Site Plan Markup "00 - SITE PLAN - HAZARDS - 11x17.pdf" showing the location of the proposed retaining walls).

Hotel Foundations:

The updated letter recommends "Foundation support for the anticipated structure loads can be achieved by cast-in-drilled-hole (CIDH) piles with minimum penetration of 10 feet into the underlying bedrock." This recommendation has been reviewed by the project's Structural Engineer and is included in the current design. (See attached letter from the Project Structural Engineer Kenneth W. Karren, Jr., P.E., S.E. of Lochsa Engineering confirming his agreement with the Geotechnical Recommendations).

Conclusion

The Rancheria will incorporate the mitigations above as well as any additional recommendations that Crawford and Associates may recommend as part of the final design criteria for geologic hazards as needed for this site. The hotel is a large investment and must be seismically sound.

¹ Final Geotechnical Feasibility Report at pg. 9.

We are working closely with our engineers to take the appropriate measures needed to ensure the stability of the hotel, to ensure the safety of the public, and to determine the best way to protect the natural environment. As design progresses, we are happy to coordinate with the Commission staff and share information and details in this regard.



Corporate Office: 1100 Corporate Drive, Suite 230 | Sacramento, CA 95831 | (916) 455-4225

Modesto: 1165 Scenic Drive, Suite A | Modesto, CA 95350 | (209) 312-7668 Pleasanton: 6200 Stoneridge Mall Road, Suite 330 | Pleasanton, CA 94588 | (925) 401-3515

Rocklin: 4220 Rocklin Road, Suite 1 | Rocklin, CA 95677 | (916) 455-4225

Ukiah: 100 North Pine Street | Ukiah, CA 95482| (707) 240-4400

May 2, 2019 CAInc File No. 16-319.2

Mr. David Tyson Trinidad Rancheria Economic Development Corporation P.O. Box 630 Trinidad, CA 95570

Subject: GEOTECHNICAL UPDATE LETTER

Trinidad Rancheria Cher-Ae Heights Hotel

Trinidad, California

Dear Mr. Tyson,

This letter updates our "Geotechnical Feasibility and Preliminary Design Report", dated November 2016, for the subject project. This letter addresses concerns raised by the California Coastal Commission in their Staff Report (file date 2/14/2019), primarily with respect to slope stabilization at the southeast corner of the proposed hotel.

Project Description

The current project is shown on a Site Plan by TBE Architects (dated 12/6/18) to include a 5-story hotel with the lower floor (and underlying level) supported on a concrete "podium" and the upper floors of wood-frame construction. The building footprint is essentially the same as that described in our 2016 geotechnical report. The southeast corner is near the head of an active slide that extends to Scenic Drive and continues below to the ocean. The active slide involves primarily terrace deposits overlying the bedrock, as discussed in the 2016 report. The Site Plan also shows new parking areas along the southwest side of the hotel with access from near the existing casino entrance at Scenic Drive.

Slope Stabilization

Stabilization near the head of the slide is required to support and protect the proposed development. We propose a Mechanically Stabilized Earth (MSE) wall or welded wire wall retaining system, such as a Hilfiker wall. These systems have been successfully used in similar environments and are common to the area. Key elements of these walls include:

- Excavate and remove disturbed slide materials within the wall area.
- Establish base of wall into undisturbed terrace soils and/or bedrock.
- Construct the wall using compacted imported backfill material and horizontal reinforcing elements (wire mats, fabric or geo-grid) placed at 1-foot intervals.
- Install sub-drainage behind the wall with gravity relief.
- Control surface runoff to direct water away from the slide area, such as with an AC dike.
- Reconstruct pavement/parking section.

Based on preliminary drawings by TBE, we estimate the wall height at about 15 feet or less. The exterior face can be vegetated or receive other face-treatment to reduce visual impacts. Similar walls along Scenic Drive are almost completely obscured by native vegetation.



Hotel Foundations

Foundation support for the anticipated structure loads can be achieved by cast-in-drilled-hole (CIDH) piles with minimum penetration of 10 feet into the underlying bedrock. Final pile tips will be provided in the design geotechnical report. CIDH piles have the advantage of requiring smaller equipment for installation than for driven piles and minimize noise/vibrations. Based on the strength data obtained from the field and laboratory tests, we recommend preliminary axial pile capacities be based on factored (allowable) adhesion value in bedrock of 1.5 kips/ft² and frictional capacity of 0.5 kips/ft² in the terrace deposits.

Retaining Walls

Additional retaining walls may be required for new parking areas southwest of the proposed hotel. The parking areas are outside of the slide limits discussed above. MSE or Hilkifer walls are also considered appropriate here, with design heights to about 20 feet. The use of rigid wall systems, such as a reinforced concrete cantilever walls, are not recommended due to height requirements, visual impacts and limited tolerance for movement.

Site Grading

Depending on the final site grades and civil design geometrics, cut/fill slopes may be considered in lieu of walls (or in combination to reduce wall heights). Fills constructed at exterior slopes of 2:1 (H:V) or flatter and cut slopes of 1½:1 (H:V) or flatter are appropriate. Grading criteria typically include the following:

- Clear the site to remove vegetation, tree roots, debris, abandoned utilities, soft or unstable soils and other deleterious materials.
- Subexcavate fill keys about 2 feet to expose undisturbed, native ground, then scarify the fill foundation and keyway to a depth of 6 inches, moisture-condition and compact to at least 90% relative compaction (per ASTM D1557).
- Provide subdrainage at the base of new fills to control springs and seasonal "perched" groundwater throughout the slopes.
- Compact fill to at least 90% relative compaction (per ASTM D1557).
- Protect exposed slopes from erosion with vegetation or other appropriate control measures.
- Direct surface runoff to suitable discharge points with erosion dissipaters, as necessary.


Stormwater Infiltration

Stormwater discharge should be directed away from the slide area to a suitable discharge point. Bedrock is exposed at the casino entrance road at Scenic Drive and this area would be suitable for a discharge point.

Please call if you have any questions on this update. Further geotechnical study and a design geotechnical report is anticipated for final design of this project.

Sincerely,

Crawford & Associates, Inc.



Principal







CAInc File: 16-319.2

May 2, 2019

T 702-365-9312 | F 702-365-9317 6345 S Jones Blvd, Suite 100 Las Vegas, NV 89118



May 10, 2019

Mr. David Nejelski Creative Director + Principal Thalden Boyd Emery Architects 1133 Olivette Executive Parkway St. Louis, MO 63132

Subject:

Cher Ae Heights Casino Hotel

Lochsa Engineering Job No. 192040.00

Dear Mr. Nejelski,

As requested, we have considered the feasibility of supporting a new hotel addition at the existing site following the recommendations of the geotechnical engineer, Crawford & Associates, Inc. The new hotel will consist of two levels of concrete podium having one level below grade with four levels of wood framing above and will be located to the southeast of the existing Casino (see Thalden Boyd Emery Architects Enlarged Site Plan and Building Section 2 dated 12/06/18).

We have been provided a geotechnical report prepared by Crawford & Associates, Inc. dated November 2016 (CAInc File No. 16-319.1) along with an update letter dated May 2, 2019 (CAInc File No. 16-319.2). Crawford has recommended pile foundations anchoring into the bedrock based on the site conditions with cast-in-drilled-hole piles (caissons) as the most appropriate solution. We agree that this is an appropriate foundation system for the new hotel. Preliminary calculations show that the hotel can be supported by 2' diameter or 3' diameter caissons with pile caps. Piles would be embedded 10' minimum into bedrock.

In our opinion, supporting the tower with a pile foundation using concrete caissons is a sound structural approach for this project.



TRINIDAD RANCHERIA CHER-AE HEIGHTS HOTEL

Trinidad, California

Prepared by:



Crawford & Associates, Inc.

4220 Rocklin Road, Suite 1 Rocklin, CA 95677

November 2016

Prepared for:

Trinidad Rancheria Economic Development Corporation

P.O. Box 630

Trinidad, CA 95570



Corporate Office: 1100 Corporate Drive, Suite 230 | Sacramento, CA 95831 | (916) 455-4225

Modesto: 1165 Scenic Drive, Suite A | Modesto, CA 95350 | (209) 312-7668

Pleasanton: 6200 Stoneridge Mall Road, Suite 330 | Pleasanton, CA 94588 | (925) 401-3515

Rocklin: 4220 Rocklin Road, Suite 1 | Rocklin, CA 95677 | (916) 455-4225 Ukiah: 100 North Pine Street | Ukiah, CA 95482 | (707) 240-4400

November 2016 CAInc File No. 16-319.1

Mr. David Tyson Trinidad Rancheria Economic Development Corporation P.O. Box 630 Trinidad, CA 95570

Subject: GEOTECHNICAL FEASIBILITY AND PRELIMINARY DESIGN REPORT

Trinidad Rancheria Cher-Ae Heights Hotel

Trinidad, California

Dear Mr. Tyson,

Attached is our Geotechnical Feasibility and Preliminary Design Report for the Trinidad Rancheria Cher-Ae Heights Hotel. Crawford & Associates, Inc. (CAInc) completed this report in accordance with our agreement with Trinidad Rancheria Economic Development Corporation (TREDC) dated August 26, 2016.

This report provides geotechnical data, geological hazards assessment, and preliminary geotechnical recommendations for the proposed hotel project.

Please call if you have questions or require additional information.

Sincerely,

Crawford & Associates, Inc.,


Benjamin D. Crawford, PE, GE

Principal

No. GE 2881

Rick Sowers, PE, CEG

Principal Engineering Geologist





November 2016

TABLE OF CONTENTS

1	INTR	ODUCTIO	ON	1
	1.1	PURPO	SE	1
	1.2	SCOPE	OF SERVICES	1
2	SITE 8	& PROJE	CT DESCRIPTION	1
3	GEOL	.ogy		2
4	PREV	IOUS EX	PLORATION	2
	4.1		EXPANSION EXPLORATIONS	
	4.2		DRIVE SLOPE STABILITY EXPLORATIONS	
5			PLORATION	
6			SUBSURFACE CONDITIONS	
0				_
	6.1 6.2		NITS	
	6.3		DWATER	
7			TESTING	
/			ICATION AND STRENGTH TESTS	
	7.1 7.2		SION TESTS	
	7.2		SION INDEX TESTS	_
8			GN PARAMETERS	
				_
9			CONCLUSIONS AND RECOMMENDATIONS	
	9.1		GIC HAZARDS	_
		9.1.1 9.1.2	FAULT RUPTURE	
		9.1.2	LIQUEFACTION POTENTIAL	_
		9.1.4	TSUNAMI	
	9.2	PRELIM	INARY RECOMMENDATIONS	
		9.2.1	HOTEL SUPPORT1	2
		9.2.2	COMPLEMENTARY FACILITIES SUPPORT	3
		9.2.3	RETAINING WALL SUPPORT & LATERAL PRESSURES	_
		9.2.4	PAVEMENT1	
	9.3	_	NG1	
10	LIMIT	TATIONS	1	4

Trinidad Rancheria Cher-Ae Heights Hotel Trinidad, California

se Heights Hotel File: 16-319.1 November 2016

CAInc

SELECT REFERENCES

Select References

FIGURES

Figure 1: Exploration Location Map

Figure 2: Cross Section AA'

Figure 3: Cross Section BB'

Figure 4: Cross Section CC'

Figure 5: Slope Remediation Examples

Figure 6: Geology Map

Figure 7: Tsunami Inundation Map

Figure 8: Fault Activity Map

Figure 9: Earthquake Fault Zone Map

Detail 1: Piezometer Logs

APPENDIX A

Boring Log Legend Boring Logs

APPENDIX B

Laboratory Test Results

APPENDIX C

LPile Outputs

APPENDIX D

SHN Proposed Expansion Cher-Ae Heights Gaming Building Boring Logs Taber Geotechnical Report – Trinidad Rancheria Expansion Project Test Pits

APPENDIX E

Site Photos

Trinidad Rancheria Cher-Ae Heights Hotel Trinidad, California

CAInc

File: 16-319.1 November 2016

1 INTRODUCTION

1.1 PURPOSE

Crawford & Associates, Inc. (CAInc) prepared this Geotechnical Feasibility and Preliminary Design Report for the Trinidad Rancheria Cher-Ae Heights Hotel project in Trinidad, California. This report provides our geotechnical data, geologic hazards evaluation, feasibility assessment and preliminary geotechnical recommendations for planning and preliminary design/costing. CAInc will prepare a final Geotechnical Design Report for the project based on further definition of project details, including final structure layouts, building loads, retaining walls, site grading and drainage/subdrainage elements.

1.2 SCOPE OF SERVICES

To prepare this report, CAInc:

- Reviewed published geologic, soils, groundwater and seismic maps pertaining to the site;
- Reviewed previous geotechnical studies at the casino and along nearby sections of Scenic Drive;
- Conducted geologic reconnaissance of the site and immediate area;
- Discussed the project elements with the design team;
- Drilled, logged, and sampled 6 exploratory borings to a maximum depth of 81.4 ft below ground surface (bgs);
- Performed laboratory testing on soil samples recovered from the borings;
- Conducted engineering analysis for preliminary foundation design; and
- Developed preliminary geotechnical recommendations based on the data and test results.

2 SITE & PROJECT DESCRIPTION

The site is located near the top of a 230±ft high bluff overlooking Trinidad Bay. Scenic Drive traverses the slope between the site and the ocean, approximately 65ft below the top of bluff. The overall slope between the casino and the ocean is about 2:1 (H:V) and is heavily vegetated, including numerous water-loving plants suggestive of shallow groundwater/springs. Scenic Drive is a county-owned road that has experienced numerous slip-outs and slides due to wave attach undercutting the ocean bluff. Several structures are present along the slope below the casino, including a residence about half-way along the slope between the casino and Scenic Drive.

The project includes a proposed 6-story hotel and complementary facilities (e.g. pool, fitness center, mechanical building, offices, etc.) located along the southwest side of the existing casino building. The hotel will be a steel-frame, stand-alone structure. The base level is expected to be near existing grade, which is generally flat within the building footprint. Some retaining walls may be incorporated into the final design to account for sloping ground to the southwest of the building.

Public access to the hotel is expected to be from a porte cochere with entrance from an existing paved roadway along the east side of the casino property; no additional grading is required for this access. Truck/delivery access is expected to be via a new road constructed from near the existing exit road at Scenic Drive with a "hairpin" turn near the existing residence and end near the northwest corner of the casino near the existing kitchen/restaurant. The road grade will be on the order of 7-12% and require





Trinidad Rancheria Cher-Ae Heights Hotel Trinidad, California

File: 16-319.1 November 2016

new cut/fills to about 10-15 feet high. New cuts may require retaining walls to about 10 ft high. We understand the existing residence will be acquired by the tribe and removed as part of this project.

We show the tentative layout on Figure 1.

GEOLOGY

The site is underlain by Pleistocene marine terrace sediments deposited on a wave-cut bench in rock of the Jura-Cretaceous Franciscan Complex. The marine terrace sediments are generally comprised of pebbly sand, silt and clay. The underlying Franciscan Complex is comprised of weathered/sheared shale. We show the site geology on Figure 6.

Rock consistent with the Franciscan Complex is exposed near beach-level and locally in the site vicinity near the intersection of Scenic Drive and the casino exit road. This rock is observed to be variablyweathered shale and greywacke sandstone, with layering dipping typically to the northeast. Some rock is very hard while some is soft (mostly within sheared shale layers). The hard rock is generally resistant to erosion, as evidenced by the "sea stacks" left standing in the bay and along the shore.

We observed marine terrace deposits exposed along the road cuts of Scenic Drive and along the slopes below the casino. These soils are partly-cemented, pebbly sand and silt.

The slopes adjacent west of the site are moderately steep with localized areas of instability. An active slide is located along at the south end of the site and extends from the top of bluff to ocean level 200+ft below. The existing casino is not affected by this feature, although the existing parking area near the mechanical building is at the head of this slide and the outer edge of the pavement has broken and dropped about 6-inches vertically. Scenic Drive crosses this slide and has experienced distress from this movement. This slope contains evidence of shallow groundwater and springs that likely contribute to the slope instability in this area.

The active Trinidad Fault is mapped near the ocean and trending about parallel to the shoreline. The proposed hotel project is located approximately 500 feet northeast of this fault. Further discussion of fault rupture hazard and seismic ground motions are presented in Sections 8 and 9 below.

PREVIOUS EXPLORATION 4

CASINO EXPANSION EXPLORATIONS 4.1

The original casino building was expanded in 2000 from 21,000±sf to 50,000±sf, including expansions to the north and south. SHN Consulting Engineers & Geologists (SHN) performed three machine-drilled borings and one hand boring for the northern expansion to a maximum depth of 27ft bgs (report dated October 1998). Taber Consultants (Taber) excavated six test pits for the southern expansion, including a retaining wall and water tank, to a maximum depth of 12ft bgs (reports dated January 1999 and May 1999). These studies show that the existing casino, retaining wall and water tank are founded on strip/ring footings established in the weathered shale bedrock. We include pertinent data from the existing casino expansions in Appendix D.





CAInc

Trinidad Rancheria Cher-Ae Heights Hotel Trinidad, California

CAInc File: 16-319.1

November 2016

4.2 SCENIC DRIVE SLOPE STABILITY EXPLORATIONS

Reviewed nearby geotechnical studies along Scenic Drive include three investigations performed by Taber (at PM 2.45, PM 2.20 and PM 1.25) and one investigation performed by SHN Consulting Engineers & Geologists (at PM 2.05). These studies show that groundwater is a primary initiator of landslides in the area. Terrace deposit and slide debris thicknesses varied from 0 to up to 40ft (generally 10-20ft), which lie on top of the weathered bedrock.

Slope stability measures to support the road have included drained, reconstructed embankments, soldier-pile retaining walls and welded-wire retaining walls.

5 CURRENT EXPLORATION

For this project, CAInc retained Geo-Ex Subsurface Exploration (Geo-Ex) to perform six (6) exploratory test borings between September 13, 2016 and September 16, 2016 ranging in depth from 31½ to 81½ ft below ground surface (bgs). Geo-Ex used a truck-mounted CME 75 drill rig equipped with flight augers or rotary wash techniques to perform this work.

During the drilling operations, penetration tests (blow counts) were performed at regular intervals using a Modified California Sampler (2.4" ID) or Standard Penetration Test Sampler (1.4" ID) to evaluate the relative density of coarse-grained (cohesionless) soil and to retain soil samples for laboratory testing. The penetration tests were performed by using a 140-pound automatic trip-hammer falling 30 inches. The recorded blow counts are shown on our boring logs and on the cross sections (Figures 3 and 4). The consistency of fine-grained (cohesive) soil was determined in accordance with ASTM D2488.

Our project engineer, Mr. Nick Anderson, logged the borings and visually classified the soils encountered according to the Unified Soil Classification System (USCS). Soil samples obtained from the borings were packaged and sealed in the field to reduce moisture loss and disturbance and delivered to laboratories for testing.

CAInc made ground water observations during drilling operations. One-inch diameter piezometers were installed in B3 and B5 to monitor future groundwater fluctuations. The remaining borings were backfilled with soil cuttings or neat cement grout. Details of the piezometer construction are shown on Detail 1.

6 SURFACE AND SUBSURFACE CONDITIONS

6.1 SOIL UNITS

We divide the soils overlying the bedrock into two general units. The uppermost unit is fill comprised of mostly stiff sandy lean clay and medium dense silty gravel. This unit is present across the majority of the hotel site and generally less than about 5 feet in depth.

The fill is underlain by marine terrace deposits within the northern half of the hotel footprint. These deposits are generally orange-tan, medium dense to very dense, silty and clayey sand with variable amounts of gravel and cementation. We encountered these soils to a depth of about 8 feet in B3 (near center of hotel footprint); the thickness then increases rapidly to a depth of 43 feet at B2 (north end of





November 2016

File: 16-319.1

hotel footprint). The sharp drop in the bedrock surface toward the north likely represents deposition over an eroded, wave-cut bedrock surface.

6.2 BEDROCK

We encountered bedrock consistent with the Franciscan Complex as described above in each of the borings below the fill and/or terrace soils. The rock is predominately decomposed to moderately weathered shale with lesser sandstone and mudstone layers. Where decomposed, the rock is mostly angular rock fragments within a sheared clay matrix. The rock unit was drillable to the full depth of our test borings (maximum 81.4 ft, B3) with power auger and rotary wash methods; rock coring was not required for drill penetration. Table 1 summarizes the bedrock depth/elevation and description at the exploration locations completed by this office and those of SHN (1998) and Taber (1998) for the casino expansion work.

Table 1: Bedrock Summary

Exploration	Boring/Test Pit Number	Depth (ft)	Approximate Elevation (ft)	Description
	B1	6.0	210	Sandstone/Mudstone, fractured
	B2	Unknown	Unknown	Unknown
SHN (1998)	В3	6.0	213	Sandstone/Mudstone, fracture, highly weathered
	HB1	Unknown	Unknown	Unknown
	TP1	6.5	227.5	Shale, completely weathered and fractured
	TP2	8.5	230.0	Shale, weathered and completely fractured
	TP3	6.5	229.0	Shale, completely weathered and fractured/sheared
Taber (1998)	TP4	10.0	228.0	Shale, completely weathered and fractured/sheared
	TP5	4.0	227.0	Shale, completely weathered and fractured/sheared
	TP6	1.0	234.0	Shale, highly weathered and completely fractured
	B1	>31	<184	Not encountered
	B2	43.2	181.8	Shale, soft
CAInc	В3	8.0	222.0	Shale, decomposed to moderately weathered
(2016)	В4	4.0	226.0	Shale, decomposed to moderately weathered
	B5	3.5	226.5	Shale, intensely to moderately weathered
	В6	4.0	226.0	Shale, very intensely to moderately weathered

We present detailed logs of our test borings in Appendix A. Data from the SHN and Taber studies are included in Appendix D.







File: 16-319.1 November 2016

6.3 GROUNDWATER

We encountered free groundwater during drilling in boring B3 at a depth of about 16.5 ft; this level rose to about depth 12 ft within 24 hours after drilling. The remaining borings were dry to full auger depth. Piezometers were installed in B3 and B5 to monitor seasonal groundwater fluctuations. The casino's Facilities Manager, Butch Rindels, is collecting groundwater readings using an electronic water level meter on a weekly basis. Through October, groundwater in both B3 and B5 has been measured at about depth 8-12 ft, as shown below. Groundwater rises significantly shortly after heavy rains.





In general, we interpret groundwater to be seasonally present within the terrace soils near the bedrock contact. The groundwater is likely "perched" over the less-permeable bedrock and daylights onto the subjacent slope as springs/seeps, as evidenced by extensive water-loving plants along the slopes below the casino. Groundwater within the bedrock unit appears to be intermittent and restricted to the decomposed/sheared zones.





Trinidad Rancheria Cher-Ae Heights Hotel Trinidad, California CAInc

File: 16-319.1 November 2016

7 LABORATORY TESTING

CAInc completed the following laboratory tests on representative soil samples obtained from our exploratory borings:

- Moisture Content / Dry Density (ASTM D2216 / D2937)
- Particle Size Analysis (ASTM D422)
- No. 200 Sieve Wash (ASTM D1140)
- Atterberg Limits (ASTM D4318)
- Expansion Index Test (ASTM D4829)
- Unconsolidated-Undrained Triaxial Shear Strength Test (ASTM D2850)
- Unconfined Compressive Strength (ASTM D2166)
- Direct Shear Strength (ASTM D3080)
- R-value (CTM 301)
- Sulfate/Chloride Content (CTM 417/422)
- pH/Minimum Resistivity (CTM 643)

We present the complete laboratory test results in Appendix B.





File: 16-319.1 November 2016

7.1 CLASSIFICATION AND STRENGTH TESTS

Table 2 summarizes the results of classification and strength tests on representative samples from the terrace soils and weathered bedrock.

Table 2: Classification and Strength Tests

Sub-	Sample		Classification Tests				Strength Tests		
surface Unit	Boring - Sample Number	Depth (ft)	Moisture Content (%)	Dry Density (pcf)	% Passing 200	Liquid Limit	Plastic Limit	Cohesion (psf)	Friction Angle (°)
	B1-1	6.0	18.3	105.3	24	NP	NP	-	-
	B1-2	11.0	9.2	123.4	16	-	-	-	-
	B1-3	16.0	12.7	103.1	15	-	-	-	-
	B1-4	21.0	13.4	94.5	-	-	-	85	34.4
	B1-5	25.0	-	-	22	-	-	-	-
	B1-6	31.0	6.3	124.3	-	ı	ı	-	-
Terrace Deposits	B2-2	8.0	6.9	114.9	-	1	1	-	-
Deposits	B2-3	13.0	14.6	113.0	18	-	-	-	-
	B2-4	18.0	13.0	116.3	22	-	-	-	-
	B2-5	23.0	8.5	109.9	15	-	-	-	-
	B2-6	28.0	13.7	95.0	-	-	-	50	34.3
	B2-7	33.0	-	-	23	-	-	-	-
	B3-1	5.3	15.5	100.9	-	-	-	-	-
	B3-2	11.0	8.5	133.0	-	-	-	3,051	-
	B3-3	16.0	4.9	138.2	-	-	-	2,387	-
	B3-4	21.0	-	-	-	27	14	-	-
	B3-6	31.0	8.1	127.7	-	-	-	-	-
	B3-10	51.0	7.0	142.3	-	-	-	-	-
	B4-1	6.0	8.8	129.6	-	-	-	1,272	-
	B4-2	11.0	8.5	137.1	-	-	-	-	-
Bedrock	B4-4	21.0	-	-	-	33	17	-	-
	B4-7	36.0	6.2	143.0	-	-	-	1,400	21.8
	B5-1	6.0	4.1	137.3	-	-	-	-	-
	B5-3	16.0	-	-	-	24	13	-	-
	B5-4	21.0	5.8	148.7	-	-	-	-	-
	B5-7	36.0	-	-	-	29	14	-	-
	B5-8	41.0	6.2	141.0	-	-	-	1,225	27.5
	B6-2	11.0	6.6	123.6	-	-	-	3,783	-





November 2016

File: 16-319.1

Based on these results, we assign an average angle of internal friction value of 32 degrees to the terrace soils and modeled the weak bedrock with an undrained shear strength of 3,750 psf (represented as a very stiff to hard clay). The rock specimens tested were of the sheared matrix material that is weak relative to the rock mass as a whole; overall, we consider the rock unit to be classed as "soft" and "highly weathered", with typical allowable bearing pressures on the order of 4-8 tsf (8,000-16,000 psf).

7.2 CORROSION TESTS

Table 3 summarizes the results of soil corrosivity tests on samples from various levels within the bedrock unit.

Minimum Boring - Sample Chloride Sulfate Depth (ft) рΗ Resistivity Number Content (ppm) Content (ppm) (ohm-cm) B3-7 36.0 8.57 1,070 12.1 225.9 21.0 12.0 B4-4 8.18 1,150 175.2 40.0 8.54 19.4 B4-8 1,850 3.7 B5-9 46.0 8.55 800 12.9 131.8 B6-1 6.0 7.72 1,720 6.9 100.4

Table 3: Soil Corrosion Test Summary

According to Caltrans Corrosion Guidelines, a site is considered corrosive to foundation elements if one or more of the following conditions exist: Chloride concentration is greater than or equal to 500 ppm, sulfate concentration is greater than or equal to 2000 ppm, minimal resistivity of 1000 ohm-cm or less, or the pH is 5.5 or less.

Based on Caltrans guidelines, the site soils are non-corrosive to cementitious materials but may be corrosive to ferrous material. We recommend consulting a corrosion engineer to develop possible corrosion mitigation measures, as needed.

7.3 EXPANSION INDEX TESTS

Results of Expansion Index (EI) tests conducted on both the terrace soils and the bedrock show EI = 3 and 54, respectively. Table 4 summarizes these results and those previously performed for the casino expansion in 2000 by Taber Consultants.

Table 4: Expansion Index Test Summary

Exploration	Boring - Sample Number	Description	EI	Expansion Potential
Current (2016)	Bulk 1	Terrace Deposits	3	Very Low
Crawford (2016)	Bulk 2	Bedrock	54	Medium
Tabor (1000)	TP1@4'	Terrace Deposits	14	Very Low
Taber (1998)	TP3@8'	Bedrock	30	Low





November 2016

File: 16-319.1

These results indicate that some portions of the bedrock (likely the decomposed, clay-rich matrix) may be at least moderately expansive and require consideration in design of some project elements (e.g., slab-on-grade floors, flatwork, etc).

8 SEISMIC DESIGN PARAMETERS

The USGS Interactive Deaggregation Page¹ indicates a maximum peak horizontal ground acceleration (PGA) of 0.52g for a seismic event with a 10% probability of exceedance in 50 years.

Based on our exploratory borings and the previous site investigations, we provide the California Building Code (CBC) seismic parameters as shown in Table 5. We determined these values using a site latitude of 41.0530°N and longitude of 124.1293°W.

Table 5: Seismic Parameters

Site Class	С
Risk Category	I/II/III/IV
Ss – Acceleration Parameter	2.440 g
S1 – Acceleration Parameter	1.001 g
Fa – Site Coefficient	1.000
Fv – Site Coefficient	1.300
SMS – Adjusted MCE* Spectral Response Acceleration Parameter	2.440 g
SM1 – Adjusted MCE* Spectral Response Acceleration Parameter	1.301 g
SDS – Design Spectral Acceleration Parameter	1.627 g
SD1 – Design Spectral Acceleration Parameter	0.868 g
TI – Long-Period Transition Period**	12

^{*} Maximum Considered Earthquake

9 PRELIMINARY CONCLUSIONS AND RECOMMENDATIONS

Based on the data presented above, we consider the site is suitable for construction of the proposed hotel and complementary facilities provided that appropriate mitigation of the geologic hazards is incorporated into project design. Below, we provide a discussion of the geologic hazards, mitigation alternatives, and preliminary geotechnical recommendations for the structure foundations, retaining walls, pavement structural sections and site grading.

We anticipate that the project will be somewhat modified based on these conclusions. Further geotechnical study by this office will be completed for final design, based on the final structure layout, retaining walls and site grading.

¹ http://geohazards.usgs.gov/deaggint/2008/ accessed June 8, 2016





^{**} Figure 22-12, ASCE 7-10

File: 16-319.1 November 2016

9.1 GEOLOGIC HAZARDS

9.1.1 FAULT RUPTURE

The active Trinidad Fault is mapped near the shoreline approximately 500±ft to the southwest of the proposed hotel. The California Geologic Survey (CGS) considers a fault to be active if it has shown evidence of ground displacement during the Holocene period, defined as about the last 11,000 years. The hotel lies at the eastern edge of an Alquist–Priolo Earthquake Fault Zone (EFZ) as defined by CGS.



The Earthquake Fault Zone Act requires structures for human occupancy to be set-back a minimum of 50 ft from an active fault. EFZ boundaries are commonly set at 500 feet from major active faults to accommodate imprecise fault locations and possible branches of active faults. The basis for establishing the Trinidad EFZ is a Fault Evaluation Report (FER-138, California Division of Mines and Geology, 1982); this report concludes that the fault scarp can be traced with confidence north of the site but is less distinct along the coast to the south. The relatively wide zone in this area reflects the imprecise location of the Trinidad Fault and potential for other branches of this fault to exist.

Except for the northwest corner, the proposed hotel footprint is positioned outside of the mapped EFZ. While we cannot say conclusively that an active fault is not present within this footprint, we consider the likelihood of an active fault through the site to be low and that the risk of fault rupture does not represent a "fatal flaw" to the project. Further investigation would be necessary to confirm this assessment, if required.

9.1.2 LANDSLIDES

Landslides are common along the slopes below the site, particularly at and below Scenic Drive. These slides are typically initiated at the beach level by wave erosion that undercuts the toe of slope preferentially within the "weak rock" areas of the shale bedrock. This erosion leads to block failures within the bedrock that translate upslope as individual translational/rotational slides. Several of these slides have affected Scenic Drive in this vicinity and have been the subject of past site investigations;





November 2016

File: 16-319.1

roadway slope stabilization measures taken by Humboldt County have included retaining walls systems, slope reconstruction and subdrainage elements.

An active slide extends upslope of Scenic Drive to near the southwest corner of the proposed hotel. This slide appears to be relatively shallow (perhaps on the order of 10-15 feet deep). The head of the slide is near the edge of the existing casino parking area. We show the approximate limits of this slide on Figure 1.

The active slide appears to involve primarily the terrace deposits overlying the bedrock. Groundwater is a major contributor to slope instability and appears to move within and through the terrace materials, "daylighting" out-of-slope where the rock is exposed. Areas of surface seepage, springs and water-loving vegetation are evidence of seasonal, shallow groundwater within the slope.

Based on preliminary discussions with the design team, we expect the hotel footprint will be modified to avoid the slide feature. Depending on the final hotel layout, some level of slope stabilization should be considered to limit headward encroachment of the slide. Appropriate stabilization work may include such options as a soil nail wall, welded wire wall or cantilevered soldier pile wall, with wall height likely on the order of 10-15 feet. If the hotel footprint cannot be modified to avoid the slide, then more extensive slope stabilization will be required, such as a drained, reconstructed embankment, regraded slope, tie-back soldier pile wall(s) or a tiered wall system. Table 6, below, summarizes a few of these options. Figure 5 shows some conceptual design elements.

Table 6: Slope Stabilization Options

Stabilization Technique/System	Advantages	Disadvantages
Soil Nail Wall	 Minor grading required to install "nails" (comprised of steel bars placed in pre-drilled holes, grouted in place) "Top-down" construction minimizes ground disturbance Cost-effective 	Requires drain elements against the excavation face and permanent facing connected to the nail heads
Drained, Reconstructed Embankment	 Provides secure slope stabilization if slope geometry and slide depth is confirmed Utilizes on-site soils for reconstruction 	 Requires significant grading and subdrainage Requires keyway at toe into intact material Likely requires work beyond property limits
Lightweight Fill Slope	 Unloads the slope and creates usable fill Free draining material Possibly qualifies for state grant funds 	 Requires significant grading and off-haul of native soils Costly (without the use of State grant) Limited contractors have experience
Soldier Pile and Lagging Wall	 Stabilizes the upper portion of the slope May provide additional usable area 	 Requires moderate grading Requires tie-backs for systems typically greater than 8-10 ft high
Tensar Geopier SRT System	Suitable for shallow unstable soilLow impactCost-effective	 Proprietary design Loud installation Slide plane may be too deep (>15ft limit)
Welded Wire (e.g., Hilfiker) Wall	 Flexible and cost-effective Local product (based in Eureka, CA) Commonly used in the area 	Requires secure support at toe of wall Requires backslope excavation into the slope





File: 16-319.1 November 2016

9.1.3 LIQUEFACTION POTENTIAL

Liquefaction can occur when saturated, loose to medium dense, granular soils (generally within 50 ft of the surface), or specifically defined cohesive soils, are subjected to ground shaking. Based on the soil, rock, and groundwater conditions encountered during our exploration and current industry accepted liquefaction evaluation methods, liquefaction is not generally expected to occur, unless sustained high groundwater levels are identified within the granular terrace soils. Liquefaction potential is considered low within the underlying bedrock.

9.1.4 TSUNAMI

The coastal area is mapped within a tsunami inundation hazard to an elevation of less than 50ft as shown on Figure 7. The casino site is at an elevation approximately 230 feet above the ocean level and is therefore outside of the hazard mapping.

9.2 PRELIMINARY RECOMMENDATIONS

9.2.1 HOTEL SUPPORT

The site is considered stable for hotel foundations established within undisturbed terrace deposits and/or bedrock. Due to the potential for landsliding along the subjacent slope and the variable materials across the longitudinal footprint (involving both weak bedrock and terrace soils), we do not recommend spread footings or other shallow foundation systems for the hotel structure. Pile foundations, achieving penetration into the bedrock unit, are therefore recommended. Driven piles (e.g., pre-cast concrete, cast-in-steel-shell (CISS), pipe piles, and H-piles) may be feasible, however, are not considered as appropriate as drilled piles due to vibrations/noise from the pile-driving equipment and variable driving conditions into the rock unit.

We consider cast-in-drilled-hole (CIDH) piles to be most appropriate; these piles require smaller equipment for installation than for driven piles and minimize noise/vibrations. The potential for groundwater and caving soils will require casing and minimum 24-inch diameter piles. For use in preliminary design, we recommend using skin friction only due to the "wet" method installation. Based on the strength data obtained from the field and laboratory tests, we recommend preliminary axial pile capacities be based on factored (allowable) adhesion value in bedrock of 1.5 kips/ft² and frictional capacity of 0.5 kips/ft² in the terrace deposits. Piles should be embedded a minimum of 10ft into bedrock. See Figure 4 for our interpreted bedrock profile along the longitudinal axis of the hotel.

We performed preliminary lateral pile analysis for both 24-inch and 36-inch diameter CIDH piles with 1% steel and a fixed-head condition (as requested by Steve Vasquez, PE) for ½-inch of deflection at the top of the pile. We performed two models – one model assuming terrace deposits and one model assuming bedrock to the surface. We summarize these results in Table 7. We will perform additional analysis to develop axial and lateral pile capacities for final design.

Table 7: Lateral Pile Analysis (Shear Resistance, ½-in deflection)

Soil/Rock Deposit	24-inch CIDH	36-inch CIDH
Terrace Deposits	75 kips	150 kips
Bedrock	127 kips	235 kips





November 2016

File: 16-319.1

We include deflection vs depth, bending moment vs depth, and shear resistance vs depth graphs in Appendix C.

9.2.2 COMPLEMENTARY FACILITIES SUPPORT

Soil support for the complementary facilities (e.g. fitness center, mechanical building, offices, etc.) are available by means of shallow spread or isolated footings bearing in compacted fill, undisturbed terrace deposits, or bedrock at least 2ft below nearest adjacent grade and at least 2ft wide. Allowable bearing pressure on the order of 2,000 psf in compacted fill or terrace deposits and 4,000 psf in bedrock is available for support. Maintain a minimum 5ft horizontal clearance from the top of slope.

Support for the pool (currently shown at the south end of the hotel, near the slide) may require drilled piers into bedrock depending on final layouts. Use similar adhesion values as for the hotel support. The pool should be set back a minimum of 10ft from the top of slope and the slope adequately stabilized to prevent headward encroachment of the slide.

9.2.3 RETAINING WALL SUPPORT & LATERAL PRESSURES

Depending on final structure layouts, retaining walls up to 10ft in height (e.g., concrete cantilever walls or similar) may be required for this project. On level ground, adequate soil support for the retaining wall foundations are available by means of shallow spread footings bearing in newly compacted fill, undisturbed terrace deposits, or bedrock at least 2ft below nearest adjacent grade and 2ft wide. Allowable bearing pressure on the order of 2,000 psf in compacted fill or terrace deposits and 4,000 psf in bedrock is available for support.

On sloped ground, soil support may be available on spread footings with reduced bearing pressure. However, drilled piers into bedrock may be recommended depending on the location and proximity to slide features.

Retaining walls should be drained with a minimum of 1ft thick permeable rock with filter fabric backing, or an appropriate geocomposite drain (e.g., Mirafi G-series or equivalent).

For preliminary design, use the equivalent fluid weights (EFWs) shown in Table 8 below to design assuming level backfill conditions. These values are based on a soil friction of 32 degrees and assume the use of native granular terrace soils or granular import for backfill. These use of native soils will be verified as part of the final design study.

Table 8: Equivalent Fluid Weights

Condition	Static EFW (pcf)	Seismic EFW (pcf)
Active	39	45
Passive	203	152

For static design, apply the resultant of the static at-rest earth pressure at a depth of 0.33H from the base of the wall where H equals the wall height.

For seismic design, apply the additional resultant force of the seismic at-rest earth pressure at a depth of 0.66H from the base of the wall where H equals the wall height.





CAInc

Trinidad Rancheria Cher-Ae Heights Hotel Trinidad, California File: 16-319.1 November 2016

9.2.4 PAVEMENT

We completed one R-Value test (CTM 301) on a bulk sample of near surface (granular fill) soil. Test results indicate an R-value of 74 by stabilometer. Using a maximum Caltrans allowable R-Value of 50 and Chapter 600 of the Caltrans Highway Design Manual (CHDM), 6th Edition, and assuming similar native (granular) soils at pavement subgrade, we recommend the sections shown in Table 9 below for design of entrance and parking lot pavement.

Table 9: Pavement Design

Traffic Index (TI)	5.0	6.0	7.0	8.0	9.0
Hot Mix Asphalt (feet)	0.20	0.25	0.30	0.40	0.45
Class 2 Aggregate Base (feet)	0.30	0.35	0.45	0.45	0.55

^{*}The upper 0.2 feet of HMA may be replaced with rubberized hot mix asphalt.

If select import fill is used for pavement subgrade, we recommend the R-value of import fill to be greater than 50.

9.3 GRADING

For preliminary design of the truck/delivery access road, use fill slopes of 2:1 (H:V) or flatter and cut slopes of 1½:1 or flatter. Fill slopes constructed at 1½:1 may be acceptable depending on the quality of the embankment fill.

General grading recommendations typically include clearing the site to remove vegetation, tree roots, debris, abandoned utilities, soft or unstable areas, and other deleterious materials. For this site, we estimate an average sub-excavation average of about 2 feet to expose undisturbed, native ground. This exposed surface should then be scarified to a minimum depth of 6 inches, moisture-conditioned, and compacted to at least 90% relative compaction per ASTM D1557. Local swale and/or spring areas may create wet ground conditions that would require drainage and/or drying of soil to achieve the required compaction.

Due to the presence of springs and possible "perched" groundwater throughout the slopes, we recommend subdrainage at the base of new fills. Depending on the final alignment and fill prism, a trenched underdrain or blanket drains may be suitable along the upslope side of the fill sections. Final subdrain details will depend on the selected alignment and fill dimensions and be addressed in the geotechnical design report.

Site soils are erodible (especially the granular terrace soils) and surface drainage will require control by directing runoff to suitable discharge points with erosion dissipaters, as necessary.

10 LIMITATIONS

CAInc performed these services in accordance with generally accepted geotechnical engineering principles and practices currently used in this area. This report is intended to provide assistance to the design team for project feasibility, planning and preliminary design/costing. CAInc will complete a Geotechnical Report for final design based on specific structure layout, grades, loading conditions and other details. Do not use this report for different locations and/or projects without the written consent of CAInc. Where referenced, we used ASTM or Caltrans standards as a general (not strict) guideline only.





Trinidad Rancheria Cher-Ae Heights Hotel Trinidad, California

File: 16-319.1 November 2016

CAInc

CAInc based this report on the current site conditions. We assumed the soil/rock and groundwater conditions are representative of the subsurface conditions on the site. Actual conditions between explorations will vary.

Our scope did not include evaluation of on-site hazardous materials.

Logs of our explorations are presented in Appendix A. The lines designating the interface between soil types are approximate. The transition between soil types may be abrupt or gradual. Our recommendations are based on the final logs, which represent our interpretation of the field logs and general knowledge of the site and geological conditions.





Aalto, K.R., Geology of Trinidad, CA, Humboldt State University, 2009.

Bradley, D.R., Stephens, T.A., <u>Geotechnical Report: Proposed Expansion, Cher-Ae Heights Gaming</u> Building, SHN Consulting Engineers & Geologists, 1998.

Davis, J.F., <u>State of California, Special Studies Zone: Trinidad Quadrangle</u>, California Division of Mines and Geology, 1983.

Delattre, M., Rosinski, A., <u>Preliminary Geologic Map of Onshore Portions of the Crescent City and Orick</u> 30' x 60' Quadrangles, California, California Geological Survey, 2012.

Johnson, R.S., Cargay, E.A., <u>Geotechnical Evaluation and Proposed Remediation of a Slope Failure, Mile Post 2.05 Scenic Drive, South of Trinidad, California</u>, SHN Consulting Engineers & Geologists, 1992.

McKnight, J.T., Lindberg, D.N., Figueroa, C., <u>Engineering Geologic Report for Slide Movement on Scenic Drive and Effects on the Joy Sundberg Residence: Geohazard Investigation – Foundation and Slope Stability, Trinity Valley Consulting Engineers, 2013.</u>

Smith, T.C., Fault Evaluation Report FER-138. California Division of Mines and Geology, 1982.

Sowers, R.D., Addendum No. 1 to "Geotechnical Investigation", Taber Consultants, 1999.

Sowers, R.D., Geotechnical Investigation: Trinidad Rancheria Expansion Project, Taber Consultants, 1999.

Sowers, R.D., <u>Subsurface Investigation: Scenic Drive PM 2.20 (south of Bingo Parlor)</u>, Taber Consultants, 1999.

Taber, H.R., Subsurface Investigation: Trinidad Scenic Drive near Cher-Ae Lane, Taber Consultants, 1986.

Taber, H.R., Subsurface Investigation: Trinidad Scenic Drive, Vicinity PM 1.25, Taber Consultants, 1994.

<u>Tsunami Inundation Map for Emergency Planning: Trinidad Quadrangle, Crannell Quadrangle</u>, California Geological Survey, 2009.





Trinidad Rancheria Cher-Ae Heights Hotel Trinidad, California

CAInc


File: 16-319.1 November 2016


Detail 1

FIGURES Exploration Location Map Figure 1 **Cross Section AA'** Figure 2 **Cross Section BB'** Figure 3 **Cross Section CC'** Figure 4 **Slope Remediation Examples** Figure 5 **Geology Map** Figure 6 **Tsunami Indundation Zone** Figure 7 **Fault Activity Map** Figure 8 **Earthquake Fault Zone Map** Figure 9


Piezometer Logs















Project Mgr.	AJK	11/1/16
Project Eng.	NRA	11/1/16
Designer		
Checked By		
Drawn By	NRA	11/1/16
	D	Doto

Trinidad Rancheria Cher-Ae Heights Hotel 27 Scenic Drive Trinidad, California 95570

Figure 3
Cross Section BB'

Project No. 16-319.1 Scale 1"=20' Date 11/1/16









Project Mgr.	AJK	11/1/16
Project Eng.	NRA	11/1/16
Designer		
Checked By		
Drawn By	NRA	11/1/16
The state of the s	By	Date


Trinidad Rancheria Cher-Ae Heights Hotel 27 Scenic Drive Trinidad, California 95570


Figure 4
Cross Section CC'

Project No. 16-319.1 Scale 1"=30' Date 11/1/16









Quaternary Fault (Age)

---- <150 years

---- <15,000 years

- <130,000 years</p>

Quaternary Fault (Age)

<750,000 years</p>

<1.6 million years

Location

Well Constrained

--- Moderately Constrained

----- Inferred

Project Mgr.	AJK	11/1/16
Project Eng.	NRA	11/1/16
Designer		
Checked By		
Drawn By	NRA	11/1/16
·	Ву	Date


Source: Google Earth with USGS Fault Map overlay



Trinidad Rancheria Cher-Ae Heights Hotel 27 Scenic Drive Trinidad, California 95570

Figure 8
Fault Activity Map

Project No.	16-319.1
Scale	1"=20,000
Date	11/1/16



Checked By Drawn By NRA 11/1/16 Ву Date



Suite 230 Sacramento, CA 95831 (916) 455-4225

Cher-Ae Heights Hotel 27 Scenic Drive Trinidad, California 95570

Zone Map

Project No.	16-319.1
Scale	NTS
Date	11/1/16

Piezometer Logs **B**3 **B**5 230.0' 230.0' Grout -Bentonite -Chips Solid 1-inch Ø Pipe #3 Sand Slotted 1-inch Ø Pipe - Grout 4.5" 11/1/16 Project Mgr. Project Eng. NRA Trinidad Rancheria Detail 1 & Associates, Inc. Geotechnical Engineering, Design and Construction Services Designer Cher-Ae Heights Hotel Piezometer Logs Checked By NRA 11/1/16 Drawn By 1100 Corporate Way Suite 230 Sacramento, CA 95831 (916) 455-4225 27 Scenic Drive

Date

Project No. 16-319.1

1"=10'

11/1/16

Scale

Trinidad, California 95570

GEOTECHNICAL FEASIBILITY AND PRELIMINARY DESIGN REPORT

Trinidad Rancheria Cher-Ae Heights Hotel <u>Trinidad</u>, <u>California</u>

CAInc

File: 16-319.1 November 2016

APPENDIX A

Boring Log Legend Boring Logs






	UNIFIED SOIL CLASSIFICATION (ASTM D 2487-06)								
MATERIAL TYPES	CRITERIA FOR	ASSIGNING SO	IL GROUP NAMES	GRAPHIC SYMBOL		SOIL GROUP NAMES			
	GRAVELS	CLEAN GRAVELS	Cu ≥ 4 AND 1 ≤ Cc ≤ 3		GW	WELL-GRADED GRAVEL			
COARSE-	> 500/ OF COADCE	<5% FINES	Cu < 4 AND/OR 1 > Cc > 3		GP	POORLY-GRADED GRAVEL			
GRAINED	>50% OF COARSE FRACTION RETAINED	GRAVELS WITH FINES	FINES CLASSIFY AS ML OR MH		GM	SILTY GRAVEL			
SOILS	ON NO. 4 SIEVE	>12% FINES	FINES CLASSIFY AS CL OR CH	6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	GC	CLAYEY GRAVEL			
>50% RETAINED ON	SANDS	CLEAN SANDS	Cu ≥ 6 AND 1 ≤ Cc ≤ 3		sw	WELL-GRADED SAND			
NO. 200 SIEVE	<50% OF COARSE FRACTION RETAINED ON NO. 4 SIEVE	<5% FINES	Cu < 6 AND/OR 1 > Cc > 3		SP	POORLY-GRADED SAND			
SIEVE		SANDS WITH FINES	FINES CLASSIFY AS ML OR MH		SM	SILTY SAND			
		>12% FINES	FINES CLASSIFY AS CL OR CH		sc	CLAYEY SAND			
FINE-	SILTS AND CLAYS	INORGANIC	PI>7 AND PLOTS ON OR ABOVE "A" LINE		CL	LEAN CLAY			
GRAINED		INORGANIC	PI>4 AND PLOTS BELOW "A" LINE		ML	SILT			
SOILS	LIQUID LIMIT <50	ORGANIC	LL (oven dried)<0.75/LL (not dried)		OL	ORGANIC CLAY OR SILT			
>50% PASSING	SILTS AND CLAYS	INORGANIC	PI PLOTS ON OR ABOVE "A" LINE		СН	FAT CLAY			
NO. 200		INORGANIC	PI PLOTS BELOW "A" LINE		МН	ELASTIC SILT			
SIEVE	LIQUID LIMIT >50	ORGANIC	LL (oven dried)<0.75/LL (not dried)		ОН	ORGANIC CLAY OR SILT			
HIGHLY	ORGANIC SOILS		RGANIC MATTER, , ORGANIC ODOR	76 76 76 76 76 76 76 76 76 76 76 76	PT	PEAT			
NOTE:	NOTE: Cu=D ₆₀ /D ₁₀ SAMPLE TYPES								

 $Cc=(D_{30})^2/D_{10} \times D_{60}$

BLOW COUNT

The number of blows of a 140-lb. hammer falling 30-inches required to drive the sampler the last 12-inches of an 18-inch drive. The notation 50/0.4 indicates 4-inches of penetration achieved in 50 blows.



С

Shelby tube

Standard Penetration (SPT)

Auger or backhoe cuttings

ADDITIONAL TESTS

Rock core

- Consolidation

Compaction Curve

CR - Corrosivity Testing

CU - Consolidated Undrained Triaxial

Modified California 2"

California Standard 2.5"

- Direct Shear

- Expansion Index

Ρ - Permeability

- Partical Size Analysis PA

- Plasticity Index

- Pocket Penetrometer PP

R - R-Value

SE Sand Equivalent

Specific Gravity

- Shrinkage Limit

SW - Swell Potential

- Pocket Torvane Shear Test

- Unconfined Compression

Unconsolidated Undrained Triaxial

GROUND WATER LEVELS

Later water level after drilling



Water level at time of drilling



BORING LOG / TEST PIT LEGEND AND SOIL DESCRIPTIONS

LOG OF BORING B1

PROJECT NO: 16-319.1

PROJECT: Trinidad Rancheria Hotel

LOCATION: Trinidad, CA

CLIENT: TREDC LOGGED BY: NRA

DEPTH OF BORING: 31.5 (ft)

BEGIN DATE: 9/13/2016

COMPLETION DATE: 9/13/2016 SURFACE ELEVATION: 215 (ft)

SURFACE CONDITION: Asphalt WATER DEPTH: Not encountered

READING TAKEN: 9/13/2016 HAMMER EFFICIENCY: 70% DRILLING CONTRACTOR: Geo-Ex Subsurface


DRILLING METHOD: Solid-Stem Auger

DRILL RIG: CME 75

HAMMER TYPE: Auto 140lb, 30" drop

SAMPLER TYPE & SIZE: MCAL (2.5"ID), SPT (1.4"ID)

BOREHOLE DIAMETER: 4.5 (in)
BACKFILL METHOD: Soil cuttings






Crawford & Associates, Inc. 1100 Corporate Way, Suite 230 Sacramento, CA 95831 (916) 455-4225 PROJECT NUMBER: 16-319.1
PROJECT: Trinidad Rancheria Hotel

BORING: B1 ENTRY BY: NRA

CHECKED BY: SHEET 1 of 2





Crawford & Associates, Inc. 1100 Corporate Way, Suite 230 Sacramento, CA 95831

(916) 455-4225

PROJECT NUMBER: 16-319.1 PROJECT: Trinidad Rancheria Hotel

BORING: B1 ENTRY BY: NRA

CHECKED BY: SHEET 2 of 2

LOG OF BORING B2

PROJECT NO: 16-319.1

PROJECT: Trinidad Rancheria Hotel

LOCATION: Trinidad, CA

CLIENT: TREDC LOGGED BY: NRA

DEPTH OF BORING: 45.1 (ft)

BEGIN DATE: 9/13/2016

COMPLETION DATE: 9/13/2016 SURFACE ELEVATION: 225 (ft)

SURFACE CONDITION: Asphalt WATER DEPTH: Not encountered

READING TAKEN: 9/13/2016 HAMMER EFFICIENCY: 70% DRILLING CONTRACTOR: Geo-Ex Subsurface


DRILLING METHOD: Hollow-Stem Auger

DRILL RIG: CME 75

HAMMER TYPE: Auto 140lb, 30" drop

SAMPLER TYPE & SIZE: MCAL (2.5"ID), SPT (1.4"ID)

BOREHOLE DIAMETER: 8 (in)
BACKFILL METHOD: Soil cuttings






Crawford & Associates, Inc. 1100 Corporate Way, Suite 230 Sacramento, CA 95831 (916) 455-4225 PROJECT NUMBER: 16-319.1
PROJECT: Trinidad Rancheria Hotel

BORING: B2 ENTRY BY: NRA

CHECKED BY: SHEET 1 of 2





PROJECT NUMBER: 16-319.1
PROJECT: Trinidad Rancheria Hotel

BORING: B2 ENTRY BY: NRA

CHECKED BY: SHEET 2 of 2

LOG OF BORING B3

PROJECT NO: 16-319.1

PROJECT: Trinidad Rancheria Hotel

LOCATION: Trinidad, CA

CLIENT: TREDC LOGGED BY: NRA

DEPTH OF BORING: 81.4 (ft)

BEGIN DATE: 9/13/2016

COMPLETION DATE: 9/14/2016 SURFACE ELEVATION: 230 (ft)

SURFACE ELEVATION: 230 (ft) SURFACE CONDITION: Asphalt

WATER DEPTH: 16.5

READING TAKEN: 9/14/2016 HAMMER EFFICIENCY: 70% DRILLING CONTRACTOR: Geo-Ex Subsurface

DRILLING METHOD: Rotary Wash


DRILL RIG: CME 75

HAMMER TYPE: Auto 140lb, 30" drop

SAMPLER TYPE & SIZE: MCAL (2.5"ID), SPT (1.4"ID)

BOREHOLE DIAMETER: 4.5 (in)

BACKFILL METHOD: Piezometer Installed






Crawford & Associates, Inc. 1100 Corporate Way, Suite 230 Sacramento, CA 95831 (916) 455-4225

PROJECT NUMBER: 16-319.1 PROJECT: Trinidad Rancheria Hotel

BORING: B3 ENTRY BY: NRA

CHECKED BY: SHEET 1 of 3






PROJECT NUMBER: 16-319.1
PROJECT: Trinidad Rancheria Hotel

BORING: B3 ENTRY BY: NRA

CHECKED BY: SHEET 2 of 3





PROJECT NUMBER: 16-319.1
PROJECT: Trinidad Rancheria Hotel

BORING: B3 ENTRY BY: NRA

CHECKED BY: SHEET 3 of 3

LOG OF BORING B4

PROJECT NO: 16-319.1

PROJECT: Trinidad Rancheria Hotel

LOCATION: Trinidad, CA

CLIENT: TREDC LOGGED BY: NRA

DEPTH OF BORING: 61 (ft)

BEGIN DATE: 9/15/2016

COMPLETION DATE: 9/15/2016 SURFACE ELEVATION: 230 (ft)

SURFACE ELEVATION: 230 (ft)
SURFACE CONDITION: Asphalt

WATER DEPTH: Not encountered

READING TAKEN: 9/15/2016 HAMMER EFFICIENCY: 70% DRILLING CONTRACTOR: Geo-Ex Subsurface


DRILLING METHOD: Rotary Wash

DRILL RIG: CME 75

HAMMER TYPE: Auto 140lb, 30" drop

SAMPLER TYPE & SIZE: MCAL (2.5"ID), SPT (1.4"ID)

BOREHOLE DIAMETER: 4.5 (in)
BACKFILL METHOD: Cement grout






Crawford & Associates, Inc. 1100 Corporate Way, Suite 230 Sacramento, CA 95831 (916) 455-4225 PROJECT NUMBER: 16-319.1
PROJECT: Trinidad Rancheria Hotel

BORING: B4 ENTRY BY: NRA

CHECKED BY: SHEET 1 of 3






PROJECT NUMBER: 16-319.1
PROJECT: Trinidad Rancheria Hotel

BORING: B4 ENTRY BY: NRA

CHECKED BY: SHEET 2 of 3





PROJECT NUMBER: 16-319.1
PROJECT: Trinidad Rancheria Hotel

BORING: B4 ENTRY BY: NRA

CHECKED BY: SHEET 3 of 3

LOG OF BORING B5

PROJECT NO: 16-319.1

PROJECT: Trinidad Rancheria Hotel

LOCATION: Trinidad, CA

CLIENT: TREDC LOGGED BY: NRA

DEPTH OF BORING: 61.5 (ft)

BEGIN DATE: 9/16/2016

COMPLETION DATE: 9/16/2016 SURFACE ELEVATION: 230 (ft)

SURFACE CONDITION: Asphalt WATER DEPTH: Not encountered

READING TAKEN: 9/16/2016 HAMMER EFFICIENCY: 70% DRILLING CONTRACTOR: Geo-Ex Subsurface

DRILLING METHOD: Rotary Wash


DRILL RIG: CME 75

HAMMER TYPE: Auto 140lb, 30" drop

SAMPLER TYPE & SIZE: MCAL (2.5"ID), SPT (1.4"ID)

BOREHOLE DIAMETER: 4.5 (in)

BACKFILL METHOD: Piezometer Installed





Crawford & Associates, Inc. 1100 Corporate Way, Suite 230 Sacramento, CA 95831 (916) 455-4225

PROJECT NUMBER: 16-319.1
PROJECT: Trinidad Rancheria Hotel

BORING: B5 ENTRY BY: NRA

CHECKED BY: SHEET 1 of 3


			FIEL	D			၅၉		(%)				TORY		
ELEVATION (ft)	DEPTH (ft)	SAMPLE	SAMPLE NO	BLOWS PER 6 IN.	BLOWS PER FOOT	POCKET PEN. (TSF)	GRAPHIC LOG	DESCRIPTION	RECOVERY(%)	PLASTIC LIMIT	LIQUID	MOISTURE (%)	DRY DENSITY (PCF)	% PASSING 200 SIEVE	REMARKS
204	26		5	7 5 11	16			Moderately weathered. SEDIMENTARY ROCK (Shale) (continued).	61						
	27														
	29	1													Easier drilling.
	30 -	Y	6	33 37 51	88				22						Sample very disturbed.
	32			01											
	33	1													
	35	X	7	9 16 16	32			Intensely to moderately weathered.	83	14	29				PI
	37									14	29				
	38														
	40	Y	8	23 32 38	70			Moderately weathered.	22			6	144		Triaxial Shear Strength - Staged
	42			00								0	141		DU phi = 27.5 degrees cohesion = 1225 psf
	44														
	45	X	9	17 10 13	23			Intensely to moderately weathered.	78						Corrosion Testing
	47			10											pH = 8.55 Min. Resistivity = 800 ohm-cm Chlorides = 12.9 ppm Sulfates = 131.8 ppm
	49														Tougher drilling. Drill bit grinding on rock.
	50		10 /	50/2	REF /			Light grayish green and white, slightly weathered, intensely fractured, partly serpentinized.	100						
178	52														
	54														
	55														



PROJECT NUMBER: 16-319.1 PROJECT: Trinidad Rancheria Hotel

BORING: B5 ENTRY BY: NRA

CHECKED BY: SHEET 2 of 3





PROJECT NUMBER: 16-319.1
PROJECT: Trinidad Rancheria Hotel

BORING: B5 ENTRY BY: NRA

CHECKED BY: SHEET 3 of 3

LOG OF BORING B6

PROJECT NO: 16-319.1

PROJECT: Trinidad Rancheria Hotel

LOCATION: Trinidad, CA

CLIENT: TREDC LOGGED BY: NRA

DEPTH OF BORING: 31.5 (ft)

BEGIN DATE: 9/15/2016

COMPLETION DATE: 9/16/2016 SURFACE ELEVATION: 230 (ft)

SURFACE CONDITION: Asphalt WATER DEPTH: Not encountered

READING TAKEN: 9/16/2016 HAMMER EFFICIENCY: 70% DRILLING CONTRACTOR: Geo-Ex Subsurface


DRILLING METHOD: Solid-Stem Auger

DRILL RIG: CME 75

HAMMER TYPE: Auto 140lb, 30" drop

SAMPLER TYPE & SIZE: MCAL (2.5"ID), SPT (1.4"ID)

BOREHOLE DIAMETER: 4.5 (in)
BACKFILL METHOD: Soil cuttings






Crawford & Associates, Inc. 1100 Corporate Way, Suite 230 Sacramento, CA 95831 (916) 455-4225

PROJECT NUMBER: 16-319.1 PROJECT: Trinidad Rancheria Hotel

BORING: B6 ENTRY BY: NRA

CHECKED BY: SHEET 1 of 2





PROJECT NUMBER: 16-319.1
PROJECT: Trinidad Rancheria Hotel

BORING: B6 ENTRY BY: NRA

CHECKED BY: SHEET 2 of 2

GEOTECHNICAL FEASIBILITY AND PRELIMINARY DESIGN REPORT

Trinidad Rancheria Cher-Ae Heights Hotel <u>Trinidad</u>, California

CAInc

File: 16-319.1 November 2016

APPENDIX B

Laboratory Test Results







CAInc File No: 16-319.1 Date: 9/30/16 Technician: CAP

MOISTURE-DENSITY TESTS - D2216

5 2 3 4 1 Sample No. B1-1 B1-2 B1-3 B1-6 B2-2 **USCS Symbol** SM GC SM SP GΡ Depth (ft.) 6 11 16 31 8 Sample Length (in.) 5.544 5.600 5.651 5.622 5.218 Diameter (in.) 2.388 2.374 2.374 2.405 2.375 0.01338 0.01437 0.01434 0.01448 0.01478 Sample Volume (ft³) Total Mass Soil+Tube (g) 1087.8 1151.6 1058.3 1157.9 998.2 Mass of Tube (g) 276.0 275.1 295.8 271.8 253.0 Tare No. P10 P9 P1 P9 G1 Tare (g) 131.7 254.6 131.4 254.5 20.7 Wet Soil + Tare (g) 580.3 741.6 506.6 740.6 59.5 Dry Soil + Tare (g) 700.7 711.8 510.8 464.4 57.0 333.0 Dry Soil (g) 379.1 446.1 457.3 36.4 Water (g) 69.5 40.9 42.2 28.8 2.5 Moisture (%) 9.2 12.7 18.3 6.3 6.9

123.4

103.1

124.3

114.9

Notes:

105.3

Dry Density (pcf)



CAInc File No: 16-319.1 Date: 9/30/16 Technician: CAP

MOISTURE-DENSITY TESTS - D2216

5 2 3 1 4 B2-5 Sample No. B2-3 B2-4 B3-1 B3-6 **USCS Symbol** SC SM SMSMRock Depth (ft.) 13 18 23 5.5 31 Sample Length (in.) 5.983 5.361 5.589 3.618 4.657 Diameter (in.) 2.377 2.392 2.358 2.408 2.418 0.01377 0.01453 0.01512 0.00954 0.01238 Sample Volume (ft³) Total Mass Soil+Tube (g) 771.5 1081.2 1138.4 1120.3 1040.1 Mass of Tube (g) 272.4 272.0 302.4 267.5 265.1 Tare No. P18 P8 D17 C15 Q6 Tare (g) 129.0 127.6 186.3 20.8 20.7 Wet Soil + Tare (g) 591.4 509.7 496.0 71.9 69.5 Dry Soil + Tare (g) 471.8 532.6 465.8 65.0 65.9 44.3 45.2 Dry Soil (g) 403.6 338.2 285.5 Water (g) 58.8 43.9 24.2 6.9 3.7 Moisture (%) 14.6 13.0 8.5 15.5 8.1 **Dry Density (pcf)** 113.0 116.3 109.9 100.9 127.7

Notes:



CAInc File No: 16-319.1 Date: 9/30/16

Technician: CAP

MOISTURE-DENSITY TESTS - D2216

1 2 3 4 5

	1	2	3	4	5
Sample No.	B3-10	B4-2	B5-1	B5-4	
USCS Symbol	Rock	Rock	Rock	Rock	
Depth (ft.)	51	11	6	21	
Sample Length (in.)	5.983	5.907	5.749	5.635	
Diameter (in.)	2.377	2.375	2.369	2.377	
Sample Volume (ft ³)	0.01536	0.01514	0.01466	0.01447	
Total Mass Soil+Tube (g)	1334.7	1296.5	1235.5	1221.9	
Mass of Tube (g)	273.4	274.3	284.9	189.8	
Tare No.	H5	D15	G7	C5	
Tare (g)	20.7	20.9	20.5	21.1	
Wet Soil + Tare (g)	61.7	56.1	102.1	82.8	
Dry Soil + Tare (g)	59.0	53.4	98.89	79.4	
Dry Soil (g)	38.4	32.5	78.39	58.3	
Water (g)	2.7	2.8	3.21	3.4	
Moisture (%)	7.0	8.5	4.1	5.8	
Dry Density (pcf)	142.3	137.1	137.3	148.7	


Notes:



CAInc File No: 16-319.1 Date: 10/3/16 Technician: KKL/CAP

Plastic Index - ASTM D4318

Sample ID	Depth (ft)	Liquid Limit	Plastic Limit	PI
B1-1	6	NP	NP	NP
B3-4	21	27	14	13
B4-4	21	33	17	16
B5-3	16	24	13	11
B5-7	36	29	14	15




Note: For B1-1, the material was not able to be rolled into a 3.2 mm diameter thread for the plastic limit and the soil pat slid in the cup when performing the liquid limit.



CAInc File No: 16-319.1 Date: 10/4/16 Technician: KKL Sample ID: B1-1 Depth: 6'

USCS Classification: Silty SAND




% Cobble	% G	ravel		% Fines		
∕₀ CODDIE	Coarse	Fine	Coarse	Medium	Fine	Silt/Clay
	0	8	2	6	60	
0		В		68	-	24

		Sieve #	Opening mm	Cummulative Mass Retained (g)	% Passing %
	Cobbles	3"	75	0.0	100%
		2"	50	0.0	100%
	Coarse	1-1/2"	37.5	0.0	100%
	Coarse	1"	25.0	0.0	100%
Gravel		3/4"	19.0	0.0	100%
		1/2"	12.5	14.3	96%
	Fine	3/8"	9.50	17.1	95%
		#4	4.75	31.2	92%
	Coarse	#10	2.00	38.7	90%
	Medium	#20	0.825	49.3	87%
Sand	iviedium	#40	0.425	59.2	84%
Salia		#60	0.250	74.8	80%
	Fine	#100	0.150	198.1	48%
		#200	0.075	286.7	24%



CAInc File No: 16-319.1 Date: 10/3/16 Technician: KKL Sample ID: B1-2 Depth: 11'

USCS Classification: Clayey GRAVEL with SAND




% Cobble	% G	ravel		% Fines			
∕₀ CODDIE	Coarse	Fine	Coarse	Coarse Medium Fine			
	0	48	11	10	15		
0	4	8		36	-	16	

		Sieve #	Opening mm	Cummulative Mass Retained (g)	% Passing %
	Cobbles	3"	75	0.0	100%
		2"	50	0.0	100%
	Coarse	1-1/2"	37.5	0.0	100%
	Coarse	1"	25.0	0.0	100%
Gravel		3/4"	19.0	0.0	100%
		1/2"	12.5	48.2	87%
	Fine	3/8"	9.50	76.7	80%
		#4	4.75	182.5	52%
	Coarse	#10	2.00	223.7	41%
	Medium	#20	0.825	249.4	34%
Sand	iviedium	#40	0.425	260.3	31%
Salia		#60	0.250	276.4	27%
	Fine	#100	0.150	303.3	20%
		#200	0.075	318.8	16%



CAInc File No: 16-319.1 Date: 10/7/16 Technician: CAP Sample ID: B1-5 Depth: 26'

USCS Classification: Silty SAND




% Cobble	% Gı	ravel		% Fines		
% CODDIE	Coarse	Fine	Coarse	Silt/Clay		
	0	0	1	2	75	
0)		78		22

		Sieve #	Opening mm	Cummulative Mass Retained (g)	% Passing %
	Cobbles	3"	75	0.0	100%
		2"	50	0.0	100%
	Coarse	1-1/2"	37.5	0.0	100%
	Codise	1"	25.0	0.0	100%
Gravel		3/4"	19.0	0.0	100%
		1/2"	12.5	0.0	100%
	Fine	3/8"	9.50	0.0	100%
		#4	4.75	0.0	100%
	Coarse	#10	2.00	1.1	99%
	Medium	#20	0.825	2.8	98%
Sand	iviedium	#40	0.425	5.6	97%
Sanu		#60	0.250	11.0	94%
	Fine	Sieve # mm Mass Retained (g) 3" 75 0.0 2" 50 0.0 1-1/2" 37.5 0.0 3/4" 19.0 0.0 1/2" 12.5 0.0 3/8" 9.50 0.0 #4 4.75 0.0 #10 2.00 1.1 #20 0.825 2.8 #40 0.425 5.6			46%
		#200	0.075	132.8	22%



CAInc File No: 16-319.1 Date: 10/4/16 Technician: KKL Sample ID: B2-3 Depth: 13'

USCS Classification: Silty SAND with GRAVEL




% Cobble	% Gı	ravel		% Sand		% Fines
∕₀ CODDIE	Coarse Fine		Coarse	Medium	Fine	Silt/Clay
	0	29	13	15	25	
0	29			53	-	18

		Sieve #	Opening mm	Cummulative Mass Retained (g)	% Passing %
	Cobbles	3"	75	0.0	100%
		2"	50	0.0	100%
	Coarse	1-1/2"	37.5	0.0	100%
	Codise	1"	25.0	0.0	100%
Gravel		3/4"	19.0	0.0	100%
		1/2"	12.5	12.5	97%
	Fine	3/8"	9.50	45.7	89%
		#4	4.75	116.9	71%
	Coarse	#10	2.00	167.7	58%
	Medium	#20	0.825	203.6	50%
Sand	iviedium	#40	0.425	229.9	43%
Saliu		#60	0.250	301.9	25%
	Fine	Mass Retained (g 3" 75 0.0 2" 50 0.0 1-1/2" 37.5 0.0 1" 25.0 0.0 3/4" 19.0 0.0 1/2" 12.5 12.5 3/8" 9.50 45.7 #4 4.75 116.9 #10 2.00 167.7 #20 0.825 203.6 #40 0.425 229.9			19%
		#200	0.075	332.1	18%



CAInc File No: 16-319.1 Date: 10/3/16 Technician: KKL Sample ID: B2-5 Depth: 23'

USCS Classification: Silty SAND




% Cobble	% Gravel			% Sand				
∕₀ CODDIE	Coarse Fine		Coarse	Medium	Fine	Silt/Clay		
	0	0	3	38	44			
0	0			85	-	15		

		Sieve #	Opening mm	Cummulative Mass Retained (g)	% Passing %
	Cobbles	3"	75	0.0	100%
		2"	50	0.0	100%
	Coarse	1-1/2"	37.5	0.0	100%
	Coarse	1"	25.0	0.0	100%
Gravel		3/4"	19.0	0.0	100%
		1/2"	12.5	0.0	100%
	Fine	3/8"	9.50	0.0	100%
		#4	4.75	0.8	100%
	Coarse	#10	2.00	7.4	97%
	Medium	#20	0.825	80.5	72%
Sand	iviedium	#40	0.425	117.3	59%
Sand		#60	0.250	130.1	54%
	Fine	#100	30%		
		#200	0.075	243.0	15%



CAInc File No: 16-319.1 Date: 10/7/16 Technician: CAP Sample ID: B2-7 Depth: 33'

USCS Classification: Silty SAND



% Cobble	% Gravel			% Sand				
% CODDIE	Coarse	Coarse Fine		Medium	Fine	Silt/Clay		
	0	0 0		0 3 74				
0	0			77				

		Sieve #	Opening mm	Cummulative Mass Retained (g)	% Passing %
	Cobbles	3"	75	0.0	100%
		2"	50	0.0	100%
	Coarse	1-1/2"	37.5	0.0	100%
	Codise	1"	25.0	0.0	100%
Gravel		3/4"	19.0	0.0	100%
		1/2"	12.5	0.0	100%
	Fine	3/8"	9.50	0.0	100%
		#4	4.75	0.0	100%
	Coarse	#10	2.00	0.3	100%
	Medium	#20	0.825	1.3	99%
Sand	iviedium	#40	0.425	4.5	97%
Saliu		#60	0.250	13.6	90%
	Fine	#100	0.150	86.1	40%
		#200	0.075	109.5	23%



CAInc File No: 16-319.1 Date: 10/3/16

Technician: KKL

200 Wash - ASTM D1140


Max Particle Size (100% Passing)	Standard Sieve Size	Recommended Min Mass of Test Specimens
2 mm or less	No. 10	20 g
4.75 mm	No. 4	100 g
9.5 mm	3/8 "	500 g
19.0 mm	3/4 "	2.5 kg
37.5 mm	1 1/2 "	10 kg
75.0 mm	3 "	50 kg

Table from 6.2 of ASTM D1140

Sample No.	B1-3	B2-4		
USCS Symbol	SM	SC		
Depth (ft.)	16	18		
Tare No.	P1	P8		
Tare (g)	131.4	127.6		
Dry Soil + Tare (g)	464.4	465.8		
Dry Mass before (g)	333.0	338.2		
Dry Mass after (g)	281.4	265.1		
Percent Fines (%)	15	22		

			EX	PANSI	ON INI	DEX TE	ST				
Project	No:	S9763-05	-86	JOB	Crawford	16-319.1				AST	M D4829
Sample		Bulk 1				DATE	10/5-7/16			вү	MR
Init	ial Ht =	1	inches	$G_s =$	2.7		Factor =	(4)(1728) (π)(4.01)		=	0.3016
$EI_{raw} =$						$ity (pcf) = \gamma$	$t_d = (Calc$	'd Dry Wt,	gms) (Fac		
	Н		/E0 CV/65	. E I \		– 0/	:_4	· ·	ht. in inche	•	
E	∃ I corrected	$=EI_{raw}$ -	(50-S)(65	<u>+⊏ 1_{raw})</u> 220-S	wnere:	w = % mo S = satura	ation in per		21 - 50 l		
0.		(100)(w)(¢	Gs)(γd)			H = initial $\Delta H = total$		n height	51 - 90 I 91 - 130	MEDIUM HIGH	
Sa	turation =	[(Gs)(62.4							> 130	VERY HIGH	l
		TRI	AL 1					TRI	AL 2		
DATE ar	nd TIME	LOAD	DIAL READ	REV COUNT	TOTAL EXPAN	DATE aı	nd TIME	LOAD	DIAL READ	REV COUNT	TOTAL EXPAN
		D	RY					D	RY		
		1 psi				10/5/2016	3 1:16 PM	1 psi	0.2278		
		1 psi			0.0000	10/5/2016	6 1:26 PM	1 psi	0.2274		-0.0004
		W	ET								
		1 psi			0.0000	10/5/2016	3 2:06 PM	1 psi	0.2104		-0.0170
		1 psi			0.0000	10/5/2016	3 2:32 PM	1 psi	0.2304		0.0030
		1 psi			0.0000	10/5/2016	6 4:07 PM	1 psi	0.2302		0.0028
		1 psi			0.0000	10/5/2016	6 4:32 PM	1 psi	0.2307		0.0033
		1 psi			0.0000	10/5/2016	6 4:50 PM	1 psi	0.2307		0.0033
		1 psi			0.0000	10/6/2016	8:05 AM	1 psi	0.2303		0.0029
		1 psi			0.0000	10/6/2016	9:27 AM	1 psi	0.2303		0.0029
		1 psi			0.0000			1 psi			
			AL 1						AL 2		
Moi	sture Con			Density	A.64	Moi	sture Con			Density	A #4
Tare No.	Before	After		Before	After	Tare No.	Before Adj	After MT-6		Before	After
Gross Wet Wt (gm)	983.7		Wet+ring (gms)	549.5		Gross Wet Wt (gm)	·	854.45	Wet+ring (gms)	550.7	588.65
Gross Dry Wt (gm)	901.6		Ring (gms)	192.8		Gross Dry Wt (gm)		771.58	Ring (gms)	192.8	
Water Loss (gm)	82.1		Wet Soil (gms)	356.7		Water Loss (gm)		82.87	Wet Soil (gms)	357.9	
Tare Wt. (gm)	224		Calc'd dry soil (gms)	318.2		Tare Wt. (gm)		459.43	Calc'd dry soil (gms)	314.5	312.8
Net Dry Wt (gm)	677.6		Dry Dens (pcf)	96.0		Net Dry Wt (gm)		312.15	Dry Dens (pcf)	94.9	94.0
% Moisture	12.1	<u> </u>				% Moisture	13.8	26.5			
Calculated		n (%)		43.3		Calculated Saturation (%)			48.0	90.5	
Total Swe						Total Swe	` '				.3
Expansion	Index					Expansion	n Index				3

			EX	PANSI	ON INI	DEX TE	ST				
Project	No:	S9763-05	5-86	JOB	Crawford	16-319.1				AST	M D4829
Sample		Bulk 2				DATE	10/5-7/16			ву	MR
Init	tial Ht =	1	inches	G _s =	2.7		Factor =	(4)(1728) (π)(4.01)		=	0.3016
					Dry Dens	$ity (pcf) = \gamma$	_d = <u>(Calc</u>	'd Dry Wt,	gms) (Fac		
	Н		/50 SV/65	, E / \	bono.	= 0/ ====	iatura ia d	•	ht. in inche		
1	E I corrected	$=EI_{raw}$ -	<u>(50-S)(65</u>	<u>+⊏ 1 _{raw})</u> 220-S	wnere:	w = % mo S = satura H = initial	ition in per		21 - 50 L	'ERY LOW _OW MEDIUM	
Sa	turation =	(100)(w)(0 [(Gs)(62.4				ΔH = total	change in	height	91 - 130 > 130 \	HIGH /ERY HIGH	l
			AL 1					TRI	AL 2		
DATE ar	nd TIME	LOAD	DIAL READ	REV COUNT	TOTAL EXPAN	DATE a	nd TIME	LOAD	DIAL READ	REV COUNT	TOTAL EXPAN
DATE at	IG THVIL		RY	000111	270 701	DATE	IIG TIIVIL		RY	000111	
		1 psi				10/5/2016	6 2:19 PM	1 psi	0.2706		
		1 psi			0.0000	10/5/2016	6 2:29 PM	1 psi	0.2711		0.0005
		W	ET								
		1 psi			0.0000	10/5/2016	6 4:05 PM	1 psi	0.3075		0.0364
		1 psi			0.0000	10/5/2016	6 4:30 PM	1 psi	0.3110		0.0399
		1 psi			0.0000	10/5/2016	6 4:52 PM	1 psi	0.3121		0.0410
		1 psi			0.0000	10/6/2016	8:04 AM	1 psi	0.3245		0.0534
		1 psi			0.0000	10/6/2016	9:26 AM	1 psi	0.3246		0.0535
		1 psi			0.0000						
		1 psi			0.0000						
		1 psi			0.0000						
		TRI	AL 1						AL 2		
Moi	sture Con			Density		Moi	isture Con			Density	1
Tare No.	Before	After		Before	After	Tare No.	Before Adj	After MT-6		Before	After
Gross Wet Wt (gm)	734.19		Wet+ring (gms)			Gross Wet Wt (gm)	,	661.45	Wet+ring (gms)	624.3	657.18
Gross Dry Wt (gm)	686.5		Ring (gms)			Gross Dry Wt (gm)		593.57	Ring (gms)	199.6	
Water Loss (gm)	47.69		Wet Soil (gms)	0		Water Loss (gm)		67.88	Wet Soil (gms)	424.7	
Tare Wt. (gm)	111.4		Calc'd dry soil (gms)	0.0		Tare Wt. (gm)		205.1	Calc'd dry soil (gms)	393.2	389.5
Net Dry Wt (gm)	575.1		Dry Dens (pcf)	0.0		Net Dry Wt (gm)		388.47	Dry Dens (pcf)	118.6	111.5
% Moisture	8.3					% Moisture	8.0	17.5			
Calculated		on (%)		0.0		Calculated Saturation (%)			51.4	92.4	
Total Swe						Total Swe					.4
Expansion	ındex			<u> </u>		Expansion	ı ındex			5	4





Sample Description Gravel up to 1/2" removed a	nd patched as possible
Sample ID	B3-2
Sample Depth (feet)	11.00
Material Description	Black lean CLAY with gravel (shale)
Initial Conditions at Start of Test	
Height (inch) average of 3	4.97
Diameter (inch) average of 3	2.39
Moisture Content (%)	8.5
Dry Density (pcf)	133.0
Estimated Specific Gravity	2.7
Saturation (%)	86.5
Shear Test Conditions	
Strain Rate (%/min)	0.9925
Major Principal Stress at Failure (psf)	6100
Strain at Failure (%)	6.5
Test Results	
Unconfined Compressive Strength (tons/ft ²)	3.1
Unconfined Compressive Strength (lbs/ft ²)	6101
Shear Strength (tons/ft ²)	1.5
Shear Strength (lbs/ft ²)	3051



Geocon Consultants, Inc. 3160 Gold Valley Drive, Suite 800 Rancho Cordova, California 95742

GEOCON Telephone: (916) 852-9118
Fax: (916) 852-9132


Project: Crawford 16-319.1

Unconfined Compressive Strength (ASTM D2166)

Location:

Number: S9763-05-86

Figure:





Sample Description Sample partially remolded in	Sample Description Sample partially remolded in order to perform test (1/2" gravel)			
Sample ID	B3-3			
Sample Depth (feet)	16.00			
Material Description	Black lean CLAY with gravel (shale)			
Initial Conditions at Start of Test				
Height (inch) average of 3	4.69			
Diameter (inch) average of 3	2.42			
Moisture Content (%)	4.9			
Dry Density (pcf)	138.2			
Estimated Specific Gravity	2.7			
Saturation (%)	60.4			
Shear Test Conditions				
Strain Rate (%/min)	0.9872			
Major Principal Stress at Failure (psf)	4770			
Strain at Failure (%)	2.5			
Test Results				
Unconfined Compressive Strength (tons/ft ²)	2.4			
Unconfined Compressive Strength (lbs/ft ²)	4774			
Shear Strength (tons/ft ²)	1.2			
Shear Strength (lbs/ft ²)	2387			



GEOCON Telephone: (916) 852-9118


Fax: (916) 852-9132

Unconfined Compressive Strength (ASTM D2166)

Project: Crawford 16-319.1

Location:

Number: S9763-05-86





Sample Description Sample partially remolded in order to perform test				
Sample ID	B4-1			
Sample Depth (feet)	6.00			
Material Description	Black lean CLAY with gravel (shale)			
Initial Conditions at Start of Test				
Height (inch) average of 3	4.94			
Diameter (inch) average of 3	2.39			
Moisture Content (%)	8.8			
Dry Density (pcf)	129.6			
Estimated Specific Gravity	2.7			
Saturation (%)	79.6			
Shear Test Conditions				
Strain Rate (%/min)	0.9967			
Major Principal Stress at Failure (psf)	2540			
Strain at Failure (%)	4.5			
Test Results				
Unconfined Compressive Strength (tons/ft ²)	1.3			
Unconfined Compressive Strength (lbs/ft ²)	2544			
Shear Strength (tons/ft ²)	0.6			
Shear Strength (lbs/ft²)	1272			



GEOCON Telephone: (916) 852-9118


Fax: (916) 852-9132

Unconfined Compressive Strength (ASTM D2166)

Project: Crawford 16-319.1

Location:

Number: S9763-05-86





Sample Description	
Sample ID	B6-2
Sample Depth (feet)	11.00
Material Description	Dark gray lean CLAY
Initial Conditions at Start of Test	
Height (inch) average of 3	4.97
Diameter (inch) average of 3	2.39
Moisture Content (%)	6.6
Dry Density (pcf)	123.6
Estimated Specific Gravity	2.7
Saturation (%)	49.3
Shear Test Conditions	
Strain Rate (%/min)	1.0151
Major Principal Stress at Failure (psf)	7570
Strain at Failure (%)	3.0
Test Results	
Unconfined Compressive Strength (tons/ft ²)	3.8
Unconfined Compressive Strength (lbs/ft ²)	7566
Shear Strength (tons/ft ²)	1.9
Shear Strength (lbs/ft ²)	3783



GEOCON Telephone: (916) 852-9118


Fax: (916) 852-9132

Unconfined Compressive Strength (ASTM D2166)

Project: Crawford 16-319.1

Location:

Number: S9763-05-86





GEOCON Telephone: (916) 852-9118


Fax: (916) 852-9132

Triaxial Shear Strength - UU Test (staged)

Project: Crawford 16-319.1

Location:

Number: S9763-05-86






Telephone: (916) 852-9118 Fax: (916) 852-9132

Triaxial Shear Strength - UU Test (staged)

Project: Crawford 16-319.1

Location:

Number: S9763-05-86



Boring Number	B1-4		
Sample Depth (feet)			
Material Description	Olive Silty SA	ND	
Initial Conditions at Start of Test			
Sample ID (psf)	1000	2000	3000
Height (inch)	1.00	1.00	1.00
Diameter (inch)	2.375	2.375	2.375
Moisture Content (%)	14.1	13.0	13.1
Dry Density (pcf)	93.9	93.7	95.8
Estimated Specific Gravity	2.70	2.70	2.70
Saturation (%)	47.9	43.9	46.7
		·	***

Shear Test Conditions			
Strain Rate (%/min)	1.004	1.049	1.026
Major Principle Stress at Failure (psf)	769	1447	2138
Strain at Failure (%)	5.89	9.26	9.68

Test Results

φ, degrees 34.4

85 c, psf




Fax: (916) 852-9132

Direct Shear Strength Test (ASTM D3080)

Project: Crawford Lab 16-319.1

Location:

Number: S9763-05-86





φ, degrees **34.3**

c, psf **50**



Geocon Consultants, Inc. 3160 Gold Valley Drive, Suite 800 Rancho Cordova, California 95742

GEOCON Telephone: (916) 852-9118


CONSULTANTS, INC. Fax: (916) 852-9132

Direct Shear Strength Test (ASTM D3080)

Project: Crawford Lab 16-319.1

Location:

Number: S9763-05-86



Sample ID) & Description				
[[Boring Number	Bulk-1			
	Sample Depth (feet)				
Ī	Material Description	Dark reddish br	own Silty SAN	D with gravel	
Test Data					
	Specimen	D	E	F	
<u> </u>	Exudation Pressure (psi)	180	330	740	
<u> </u>	Expansion Dial (.0001")	22	25	38	
<u> </u>	Expansion Pressure (psf)	95	108	165	
	Resistance 'R' Value	66	75	77	
1	Moisture at test (%)	16.5	15.6	14.7	
<u> </u>	Dry density at test (pcf)	106.7	104.2	110.0	
Ī	R Value at 300 psi exudati	on pressure	7	4]
Ī	R Value by expansion pres	ssure (TI=5.0)	6	3]



Geocon Consultants, Inc. 3160 Gold Valley Drive, Suite 800 Rancho Cordova, California 95742 Telephone: (916) 852-9118


Fax: (916) 852-9132

R Value By Exudation

Project: Crawford 16-319.1

Location:

Number: S9763-05-86



Rancho Cordova, CA 95742 (916) 852-8557

> Date Reported 09/28/16 Date Submitted 09/23/16

To:

Nick Anderson

Crawford and Associates 5701 Lonetree Blvd, Suite 110

Rocklin, CA, 95765

From: Gene Oliphant, Ph.D. \ Randy Horney General Manager \ Lab Manager

The reported analysis was requested for the following:

Location: 16-319.1 Site ID: B6-1 Thank you for your business.

* For future reference to this analysis please use SUN # 72899 - 152178

EVALUATION FOR SOIL CORROSION


Soil pH 7.72

Minimum Resistivity 1.72 ohm-cm (x1000)

Chloride 6.9 ppm 0.0007 %

Sulfate-S 100.4 ppm 0.01 %

METHODS:



Rancho Cordova, CA 95742 (916) 852-8557

> Date Reported 09/28/16 Date Submitted 09/23/16

To:

Nick Anderson

Crawford and Associates 5701 Lonetree Blvd, Suite 110

Rocklin, CA, 95765

From: Gene Oliphant, Ph.D. \ Randy Horney General Manager \ Lab Manager

The reported analysis was requested for the following:


Location: 16-319.1 Site ID: B5-9 Thank you for your business.

* For future reference to this analysis please use SUN # 72899 - 152177

EVALUATION FOR SOIL CORROSION

Soil pH	8.55		
Minimum Resistivity	0.80	ohm-cm (x1000)	
Chloride	12.9 ppm	0.0013	%
Sulfate-S	131.8 ppm	0.0132	%

METHODS:



Rancho Cordova, CA 95742 (916) 852-8557

> Date Reported 09/28/16 Date Submitted 09/23/16

To:

Nick Anderson

Crawford and Associates 5701 Lonetree Blvd, Suite 110

Rocklin, CA, 95765

From: Gene Oliphant, Ph.D. \ Randy Horney General Manager \ Lab Manager

The reported analysis was requested for the following:


Location: 16-319.1 Site ID: B4-8 Thank you for your business.

* For future reference to this analysis please use SUN # 72899 - 152176

EVALUATION FOR SOIL CORROSION

Soil pH	8.54		
Minimum Resistivity	1.85	ohm-cm (x1000)	
Chloride	3.7 ppm	0.0004	%
Sulfate-S	19.4 ppm	0.0019	%

METHODS:



Rancho Cordova, CA 95742 (916) 852-8557

> Date Reported 09/28/16 Date Submitted 09/23/16

To:

Nick Anderson

Crawford and Associates 5701 Lonetree Blvd, Suite 110

Rocklin, CA, 95765

From: Gene Oliphant, Ph.D. \ Randy Horney General Manager \ Lab Manager

The reported analysis was requested for the following:

Location: 16-319.1 Site ID: B4-4 Thank you for your business.

* For future reference to this analysis please use SUN # 72899 - 152175

EVALUATION FOR SOIL CORROSION


Soil pH 8.18

Minimum Resistivity 1.15 ohm-cm (x1000)

Chloride 12.0 ppm 0.0012 %

Sulfate-S 175.2 ppm 0.0175 %

METHODS:



Rancho Cordova, CA 95742 (916) 852-8557

> Date Reported 09/28/16 Date Submitted 09/23/16

To:

Nick Anderson

Crawford and Associates 5701 Lonetree Blvd, Suite 110

Rocklin, CA, 95765

From: Gene Oliphant, Ph.D. \ Randy Horney General Manager \ Lab Manager

The reported analysis was requested for the following:

Location: 16-319.1 Site ID: B3-7 Thank you for your business.

* For future reference to this analysis please use SUN # 72899 - 152174

EVALUATION FOR SOIL CORROSION

Soil pH 8.57 Minimum Resistivity 1.07 ohm-cm (x1000) Chloride 12.1 ppm 0.0012 % Sulfate-S 225.9 ppm 0.0226 %

METHODS:

GEOTECHNICAL FEASIBILITY AND PRELIMINARY DESIGN REPORT

Trinidad Rancheria Cher-Ae Heights Hotel <u>Trinidad</u>, California

CAInc


File: 16-319.1 November 2016


APPENDIX C


LPile Outputs
































Preliminary 36-inch CIDH in Bedrock Shear Force (kips)







GEOTECHNICAL FEASIBILITY AND PRELIMINARY DESIGN REPORT

Trinidad Rancheria Cher-Ae Heights Hotel <u>Trinidad</u>, California CAInc

File: 16-319.1 November 2016

APPENDIX D

SHN Geotechnical Report – Proposed Expansion Cher-Ae Heights Gaming Building Boring Logs
Taber Geotechnical Report – Trinidad Rancheria Expansion Project Test Pit Logs





BORING LOG KEY


SAN	APLE TYPES	SYMBOLS	
	DISTURBED SAMPLE (BULK)	<u>\sqrt{\sq}}}}}}}}}}} \end{\sqrt{\sq}}}}}}}}}}} \end{\sqrt{\sqrt{\sqrt{\sq}}}}}}}}} \end{\sqrt{\sqrt{\sqrt{\sqrt{\sqrt{\sqrt{\sqrt{\sqrt{\sq}}}}}}}}}} \end{\sqrt{\sq}\sqrt{\sqrt{\sqrt{\sqrt{\sqrt{\sqrt{\sq}}}}}}}}}} \end{\sqrt{\sqrt{\sqrt{\sqrt{\sqrt{\sqrt{\sq}}}}}}}}} \sqrt{\sqrt{\sqrt{\</u>	INITIAL WATER LEVEL
	HAND DRIVEN TUBE SAMPLE	<u></u>	STABILIZED WATER LEVEL
			GRADATIONAL CONTACT
I	1.4" I.D. STANDARD PENETRATION TEXT SAMPLE (SPT)	_	WELL DEFINED CONTACT
	2.5" I.D. MODIFIED CALIFORNIA SAMPLE (NOT RETAINED)	SS	SPLIT SPOON
	MODIFIED CALIFORNIA SAMPLE (RETAINED)		
	CORE BARREL SAMPLE (NOT RETAINED)		
	CORE BARREL SAMPLE (RETAINED)		

METHOD OF SOIL CLASSIFICATION

MAJ	OR DIVISIONS	SYMBOLS	TYPICAL NAMES	
		GW	WELL GRADED GRAVELS OR GRAVEL-SAND MIXTURES, LITTLE OR NO FINES	
S	GRAVELS (MORE THAN 1/2 OF	GP	POORLY GRADED GRAVELS OR GRAVEL-SAND MIXTURES, LITTLE OR NO FINES	
SOILS SOIL ZE)	COARSE FRACTION > NO.4 SIEVE SIZE)	GM	SILTY GRAVELS, GRAVEL-SAND-SILT MIXTURES	
GRAINED HAN 1/2 OF 200 SIEVE SIZ		GC	CLAYEY GRAVELS, GRAVEL-SAND-CLAY MIXTURES	
GRA THAN 1		SW	WELL GRADED SANDS OR GRAVELLY SANDS, LITTLE OR NO FINES	
	SANDS (MORE THAN 1/2 OF	SP	POORLY GRADED SANDS OR GRAVELLY SANDS, LITTLE OR NO FINES	
COARSE (MORE 1	COARSE FRACTION < NO.4 SIEVE SIZE)	SM	SILTY SANDS, SAND-SILT MIXTURES	1
		SC	CLAYEY SANDS, SAND-CLAY MIXTURES	
(0		ML	INDRGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY	
SOILS OF SOIL SIZE)	SILTS & CLAYS	CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS	
INED 1/2 OF SIEVE SI	LESS THAN 50	OL	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY	Ì
GRAINED THAN 1/2 200 SIEVE	CILTO & CLAVE	МН	INORGANIC LILTS, MICACEOUS OR DIATOMACEOUS FINE SANDY OR SILTY SOILS, ELASTIC SILTS	
		CH	INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS	
UQUID LIMIT GREATER THAN 50		ОН	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTY CLAYS, ORGANIC SILTS	
HIGHLY	Y ORGANIC SOILS	PT	PEAT AND OTHER HIGHLY ORGANIC SOILS	1

CLASSIFICATION	U.S. STANDARD SIEVE SIZE	
BOULDERS	ABOVE 12"	CHART
COBBLES	12" TO 3"	1
GRAVEL CDARSE FINE	3" TO NO. 4 3" TD 3/4" 3/4" TO NO. 4	A SIZE
SAND: COARSE MEDIUM FINE	NO. 4 TO NO. 200 NO. 4 TO NO. 10 NO. 10 TO NO. 40 NO. 40 TO NO. 200	GRAIN
SILT & CLAY	BELOW NO. 200	

**



CONSISTANCY OF FINE GRAINED SOILS		DENSITY COARSE GRA		
CLASSIFICATION	COHESION (PSF)	CLASSIFICATION	STANDARD PENETRATION (BLOW COUNT)	
VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD	0-250 250-500 500-1000 1000-2000 2000-4000 4000+	VERY LOOSE LOOSE MEDIUM DENSE VERY DENSE	0-4 4-10 10-30 30-50 50+	

MOISTURE CLASIFICATIONS	
DRY	٦
DAMP	ļ
MOIST	١
WET	

BASED ON UNIFIED SOILS CLASSIFICATION SYSTEM

PROJE	ct _c	her-A	e Heig	hts				JOB NUMBER 098210			
LOCATION Trinidad, California								DATE DRILLED 9/17/98	DATE DRILLED 9/17/98		
GROUND SURFACE ELEVATION 286 ft.								SAMPLER TYPE 2.5" ID Mod	. CA; 1.4" SPT w/ no		
							Aug	er liners; downhole 130 lb	hammer, rope & pull		
LOGGE			1					TOTAL DEPTH OF HOLE 19.5			
			661		_			TOTAL BLEFTT OF TIOLE	1		
MOISTURE (%)	DRY DEN (PCF)	UNC CMP (PSF)	UNC CMP (PSF) BY POCKET PER	DEPTH (ft.) SAMPLES	BLOWS/6 IN	GRAPHIC LOG	USGS CLASS	MATERIALS DESCRIPTION	REMARKS		
				-				ASPHALT/CONCRETE			
24.1	87	1050	_	1 - - 2 - - 3 - - 4 -	7 9 19			FILL, GRAVEL, aggragate base, rounded to 3/4" maximum dimension. FILL, SILT, sandy, clayey, very stiff, damp, light brown, with angular gravel fragments to 1/4" maximum dimension.	fairly cohesive		
1.5	117	-1	>5000	5 - 6 - 7 - 8 -	14 31 27	***************************************		SANDSTONE, fractured to 2.5" maximum dimension, with minor gray clay.	Very fine sand parti seen under lens. ⁷ Becomes denser per driller		
7.2	123	_	>5000	12 -	17 25 50/ 5"			MUDSTONE, fractured to larger than 2.5" maximum dimension, with moisture in fractures, minor clayey silt, plastic.			
				- 13 - - 14 - - 15 - - 16 - - 17 - - 18 - - 19 -	50/ 3"	Service of the control of the contro		MUDSTONE, bedded.	No recovery. Increasing gravel oper driller Very dry, gray cutti Hard drilling		
				20 - 21 - 22 - 23 - 24 - 25 - 26 - 27 - 28 -	5"	7		Bottom of boring at 19.5 feet. No free goundwater observed.			

PROJEC	CT Cher	-Ae He:	ights				JOB NUMBER <u>098210</u>			
LOCATI	ION Tr	hidad,	Califor	กia			DATE DRILLED _9/17/98	DATE DRILLED _9/17/98		
GROUNE	SURFAC	CE ELEVA	ATION _	89.3	ft.		SAMPLER TYPE 2.5" ID Mod	. CA; 1.4" SPT w/ no		
EXCAVATION METHOD 8.5" Hollow Stem Auger							r liners; downhole 130 lb	liners; downhole 130 lb hammer, rope & pull		
LOGGEE	BY CO						TOTAL DEPTH OF HOLE 26.0	ft.		
MOISTURE (%)	DRY DEN (PCF)	A POO	.;	BLOWS/6 IN	GRAPHIC LOG	USGS CLASS	MATERIALS DESCRIPTION	REMARKS		
			1 -		XX		ASPHALT/CONCRETE FILL, GRAVEL, aggragate base, rounded			
			3 - 3 - 5 - 6 -	37 50/ 3"		SM	to 3/4" maximum dimension. SILT, gravelly, soft, damp to dry, light brown, roots, with gravel to 1/2" maximum dimension, topsoil. SAND, silty, very dense, damp, light brown and reddish brown, with angular weathered gravel to 2" maximum dimension.	Colluvium?		
			- 7 - - 8 - - 9 -	50/ 5"	355533565134T		SANDSTONE, fractured, weathered, very fine grained, dry, greenish brown.			
			10 -	B 22 24			MUDSTONE, highly weathered, stiff, damp, gray, with silt and clay.			
			13 - - 14 - - 15 -	18 35 41			MUDSTONE, highly weathered, stiff, damp, gray, with silt and clay, with minor rounded mudstone gravel, with quartz vein.			
1 0 . 1	131 -	_	16 - 17 - 18 - 19 - 20 -	10 11 13	-24		SILTSTONE, highly weathered, very stiff damp, gray.	Very hard drilling. Dry cuttings with rounded gravel.		
			21 – 22 – 23 – 24 – 25 –	15 27 40 19 50/			MUDSTONE, highly weathered, fractured, damp, gray.			
			- 26 - - 27 -	6"			Bottom of boring at 26.0 feet. No free groundwater observed.	Auger refusal		

安金

2487-90)

Pt

Highly

organic


soils

OH

Taber Consultants Engineers and Geologists 536 Goveston Street West Socramento, CA, 95691 (916) 371–1690 Fax (916) 371–7265

(50% or more is smaller than No. 200 sieve)

UNIFIED SOIL CLASSIFICATION SUMMARY SC CL ML SM SP GC GM GW Cleon sonds < 5% fines Sands with fines Gravels with fines Clean gravels < 5% fines >12% fines > 12% fines Silts and clave Silts and clays Liquid limit 50 or more Liquid limit less than 50 Sands-50% or more of coorse Gravels-more than 50% of coarse fraction is smaller than No 4. Sleve fraction is lorger than No. 4 sieve Fine grained sails Caarse grained soils



LABORATORY CLASSIFICATION CRITERIA

(More than 50% is larger than No. 200 sieve)

GW and SW - $Cu \ge 4$ for GW and 6 FOR SW; 1 < $Cc \le 3$

GP and SP-Clean gravel or sand not meeting requirements for GW and SW.

GM and SM-Atterberg limits of fines below "A" line or P.I. less than 4.

GC and SC-Atterberg limits of fines above "A" line with P.I. greater than 7.

1	F: ();			Sand	<u> </u>		Gr	avel	Cabbia	Double of
	Fines (silt or	clay)	Fine	Ме	dium C	eenpo	Fine	Coarse	Cobbie	s Bouiders
	Sieve sizes	20	00	40	10	4	. 3	/4"	3"	10"

Classification of earth materials shown on the test boring logs is based on field inspection and should not be construed to imply laboratory analysis unless so stated.

MATERIAL SYMBOLS

0000	Gravel	~~~ ~~~	Peat or organic matter
	Sand		Fill moterial
	Silt		Shale
	Clay		Sandstone
	Sandy clay or clayey sand		Limestone
	Sandy silt or silty sand		Metamorphic rock
	Silty clay or clayey silt		Igneous rock

CONSISTENCY CLASSIFICATION FOR SOILS

No. of Blows*	Granular	Cohesive
0-5	Very loose	Very soft
6-10	Loose	Soft
11-20	Semicompact	Stiff
21-35	Compact	Very stiff
36-70	Dense	Harđ
> 70	Very dense	Very hard

* According to the Standard Penetration Test (ASTM 0 1586)

Where standard penetration test has not been performed, consistencies shown on logs are estimated.

KEY TO "OTHER TESTS" LABORATORY

- Hydrometer

- Expansion Index

- Atterberg Limits

- Gradation

SE - Sond Equivalent

- Consolidation

Maximum Dry Density Determination

- Stabilometer Resistance Value

- Direct Shear


- Triaxial Shear

- Permeability


Ch - Corrosivity Testing

SG - Specific Gravity

LEGEND OF BORING



LEGEND OF PENETRATION TEST



[&]quot;+" indicates extrapolated blow count

Taber Consultants
Engineers and Geologists
536 Calveston Street
West Sociamento, CA 98691
(918) 371-1830 Fair (918) 371-7265

TYPE: Case 490 with 18-Inch Bucket Test Pit No. 1 ELEVATION: 304± (Stiff) Red brown CLAYEY SILT with very fine SAND and ROOTS/ROOTLETS 84 (Semicompact-compact) orange brown and brown 29 S 88 SILTY very fine-fine SAND with thin lenses of .G,E Baa CLAYEY SILT and fine-coarse SANDY GRAVEL (Very hard) blue gray gravelly rock fragments in CLAYEY matrix (completely weathered and fractured and sheared sedimentary ROCK-SHALE) 10 Groundwater measured at 6.3ft. depth; Test pit backfilled with spoils, tamped/wheel rolled 12-22-98 15 Test Pit No. 2 ELEVATION: 308.5± TYPE: Case 490 with 18-Inch Bucket (Loose) red brown SILTY very fine-fine SAND with ROOTS/ROOTLETS (Semicompact) light brown SILTY very fine-fine 2.5 80 23 5 (Compact-dense) light brown and oronge brown SĈ SILTY and CLAYEY fine SAND with thin SILTY layers 1 В Baa SM 2.5 2 97 25 2-22-98 (Very hard) dark brown/black weathered and completely fractured sedimentary ROCK-SHALE 10 Groundwater measured at 9.0ft. depth; Test pit backfilled with spoils, tamped/wheel rolled 12-22-98 15 20 OTHER TESTS DRY DENSITY (Ibs/cu. ft.) SIZE Š THE BORING LOGS SHOW SUBSURFACE CONDITIONS AT THE DATES AND LOCATIONS INDICATED AND IT IS NOT WARRANTED THAT THEY ARE REPRESENTATIVE OF SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND TIMES UNIFIED SOIL CLAS SAMPLE (inches) SAMPLE FEET DEPTH IN FEE

DATE:

W.E.N.

LOGGED BY:

12-22-98

Since 1954 (916) 371-1690 Fax (918) 371-TYPE: Case 490 with 18-Inch Bucket ELEVATION: 305.5+ Test Pit No. 3 (Loose) gray coarse GRAVEL cover over (compactdense) orange brown to gray weakly cemented SILTY very fine-fine SAND to fine-medium SAND (Very hard) dark blue gray CLAY with fine-coarse ROCK fragments (completed weothered and fractured/sheared sedimentary ROCK-SHALE) C R.F Baa 10 Groundwater measured at 6.3ft. depth; Test pit backfilled with spoils, tamped/wheel rolled on 12-22-98 15 Test Pit No. 4 TYPE: Case 490 with 18-Inch Bucket ELEVATION: 308± (Compact to dense) orange brown to light brown weakly cemented SILTY very fine-fine SAND (Semicompact-compact) gray fine SAND grading to coarse SAND ⁻⁹⁸ (Compact-dense) gray fine-coarse SANDY GRAVEL/GRAVELLY SAND and COBBLES 10 (Very stiff-hard) dark gray CLAY with ROCK fragments (completely weathered and fractured/ sheared sedimentary ROCK-SHALE 15 Groundwater measured at 8.5ft. depth; Test pit bockfilled with spoils, tamped/wheel rolled on 12-22-98 20 OTHER TESTS Š THE BORING LOGS SHOW SUBSURFACE CONDITIONS AT THE DATES AND LOCATIONS INDICATED AND IT IS NOT WARRANTED THAT THEY ARE REPRESENTATIVE OF SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND TIMES SAMPLE FEET DEPTH IN FEET 12-22-98 W.E.N. LOGGED BY: DATE:

Taber Consultants
Engineers and Geologists
356 Colvents Stret
West Socramento, CA 95691
(916) 371-1990 Fax (916) 371-7285 Since 1954 (916) 371-1690 Faz (916) 371-TYPE: Case 490 with 18-Inch Bucket Test Pit No. 5 ELEVATION: 301± (Loose-semicompact) orange brown SILTY SAND with ROOTS/ROOTLETS (Stiff) gray CLAY S 103 23 2.5 Baa D (Very hard) gray GRAVELLY ROCK fragments in CLAYEY matrix (completely weathered and fractured/sheared sedimentary ROCK-SHALE) No free groundwater encountered. Test pit backfilled with spoils, tamped with bucket on 12-22-98. 10 15 Test Pit No. 6 ELEVATION: 305± TYPE: Case 490 with 18-Inch Bucket (Loose) gray fine-coarse GRAVEL (fill) over (semicompact) orange brown fine SANDY SILT (Very hard) black highly weathered and completely fractured sedimentary ROCK-SHALE Groundwater measured at 6.5ft. depth; 10 Test pit backfilled with spoils, tamped/wheel rolled on 12-22-98 15 20 OTHER TESTS Š THE BORING LOGS SHOW SUBSURFACE CONDITIONS AT THE DATES AND LOCATIONS INDICATED AND IT IS NOT WARRANTED THAT THEY ARE REPRESENTATIVE OF SUBSURFACE CONDITIONS AT OTHER LOCATIONS AND TIMES SAMPLE Moisture (%) ව්දු FEET DEPTH IN FEE

DATE:

W.E.N.

LOGGED BY:

12-22-98

GEOTECHNICAL FEASIBILITY AND PRELIMINARY DESIGN REPORT

Trinidad Rancheria Cher-Ae Heights Hotel <u>Trinidad</u>, California

CAInc

File: 16-319.1 November 2016

APPENDIX E

Site Photos







Photo 1: Looking east at head of landslide



Photo 2: "Water loving plants" beneath landslide at Scenic Drive







Photo 3: Vertical drop at landslide scarp



Photo 4: Exposed bedrock at Casino Entrance







Photo 5: Sea stacks at beach west of Scenic Drive



Photo 6: Weathered bedrock





