CALIFORNIA COASTAL COMMISSION

455 MARKET STREET, SUITE 300 SAN FRANCISCO, CA 94105-2219 FAX (415) 904-5400 Voice (415) 904-5200



Th9c/Th10a


CDP No. 9-23-0548/CC-0002-23 November 16, 2023

EXHIBITS

| XHIBIT 1 (VICINITY MAP)2 |
|---|
| XHIBIT 2 (OVERVIEW MAP)3 |
| XHIBIT 3 (CABLE ROUTE FROM SHORE OF CALIFORNIA TO EDGE OF OUTER CONTINENTAL SHELF)4 |
| XHIBIT 4 (CABLE ROUTE FROM UNITED STATES TO JAPAN)6 |
| XHIBIT 5 (MAPPING OF SEAFLOOR HABITAT)7 |
| XHIBIT 6 (UPDATED CENTRAL CALIFORNIA JOINT CABLE FISHERIES LIAISON COMMITTEE AGREEMENT)12 |
| XHIBIT 7 (MITIGATED NEGATIVE DECLARATION MITIGATION MEASURES)13 |


10/5/23, 4:42 PM Google Maps





Map data ©2023 Google 2 mi

Exhibit 1



AECOM

Seren Juno Network America, Inc.

Exhibit 2




Figure 2-1. Project Area



Figure 2-2. Project Components

Prepared for: NEC Corporation of America AECOM





Figure 1-1. Cable Route


Figure 3-2. Planned Cable Burial within the US EEZ




Exhibit 5

JUNO Project: CSLC Application









Prepared for: NEC Corporation of America AECOM 18



Central California Joint Cable/Fisheries Liaison Committee

2030 Van Beurden Drive, Los Osos, CA
Post Office Box 2033, Morro Bay, California 93443
Phone: (805) 771 - 9637 | Mobile: (805) 441 - 4838 | www.cencalcablefishery.com
William Blue, Chairman of the Board | Christopher Kubiak, Liaison Officer

CORPORATION CERTIFIED RESOLUTION

I, Christopher Kubiak, do hereby certify:

- 1. That I am the duly elected and acting Secretary of Central California Joint Cable/Fisheries Liaison Committee, a California nonprofit mutual benefit corporation organized and existing under the laws of the State of California (hereinafter the "*Corporation*").
- 2. That the following is a true and correct copy of a Resolution duly adopted at a meeting of the Board of Directors of the Corporation, duly held and convened on the 19th day of September, 2023, at which meeting a duly constituted quorum of the Board of Directors was present and acting throughout, and that such Resolution has not been modified, rescinded or revoked, and is at present in full force and effect, to wit:

RESOLVED: *That*, The Agreement Between Cable Companies and Fishermen (the "*Agreement*") is amended to include the PC Landing Corp. JUNO Cable Project as a Covered Cable;

Pursuant to Section 1.07 of the Agreement, as amended: The PC Landing Corp. JUNO Cable Project constitutes a new project by a Current Member Cable Company;

Pursuant to ARTICLE III, Section 3.03 of the Agreement: PC Landing Corp. will annually contribute fifty thousand dollars (\$50,000) to the Commercial Fishing Industry Improvement Fund for the JUNO Cable Project. Within thirty (30) days of receipt of an invoice, which initial invoice shall not be presented until after PC Landing Corp. receives final approval from all agencies of the State of California and all local agencies for the JUNO Cable Project and begins installation of the associated cable in the Covered Area, PC Landing Corp. shall pay to the Committee for deposit into the Committee's Commercial Fishing Industry Improvement Fund the prorated amount based on fifty thousand dollars (\$50,000) per year beginning the date cable installation begins in the Covered Area and ending on December 31st of that year (the equivalent of a daily rate of one hundred thirty-six dollars and ninety-eight cents (\$136.98)). Annually thereafter, PC Landing Corp. shall deposit fifty thousand dollars (\$50,000) for the JUNO Cable Project to the Commercial Fishing Industry Improvement Fund, or as directed by the Committee, within thirty (30) days of receipt of an invoice from the Committee, which shall be issued at the beginning of each calendar year; and

Pursuant to ARTICLE III, Section 3.02 of the Agreement, PC Landing Corp. shall pay its share of the actual Committee Liaison Office Budget within thirty (30) days of their receipt of an invoice from the Committee.

IN WITNESS WHEREOF, I have hereunto subscribed my name this 29th day of September 2023, at Los Osos, California.

(Authorized Signature of Certifying Officer)

Name: Christopher J Kubiak

Christophen Kubiak

Title: Secretary, Central California Joint Cable/Fisheries Liaison Committee

Exhibit 6

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|---|---|--------------------------------------|---|---|--------------------|---------------------|
| | | Air Quality | | | | |
| Increase of any criteria pollutant for which the Project region is non-attainment | MM AQ-1: Standard Control Measures for Construction Equipment. The following SLOAPCD standard air quality MMs shall be implemented during terrestrial construction. Note that measures less stringent than those required by MM AQ-2 have been removed from the list. Maintain all construction equipment in proper tune according to manufacturer's specifications. Fuel all off-road and portable diesel-powered equipment with CARB-certified motor vehicle diesel fuel (nontaxed version suitable for use off-road). All on- and off-road diesel equipment shall not idle for more than 5 minutes. Signs shall be posted in the designated queuing areas and job sites to remind drivers and operators of the 5-minute idling limit. Diesel idling within 1,000 feet of sensitive receptors is not permitted. Staging and queuing areas shall not be located within 1,000 feet of sensitive receptors. Electrify equipment when feasible. Substitute gasoline-powered in place of diesel-powered equipment, where feasible. Use alternatively fueled construction equipment onsite where feasible, such | Air Quality Terrestrial Project area | Implement SLOAPCD standard air quality MMs during construction | Implementing MM will reduce air quality impacts during construction | Applicant and CSLC | During construction |
| | as compressed natural gas (CNG), | | | | | |

Exhibit 7

April 2020

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|--|--|-----------------------------|---|--|----------------------|------------------------|
| | liquefied natural gas (LNG), propane, or biodiesel. | | | | | |
| Increase of any criteria pollutant for which the Project region is non- attainment (cont.) | MM AQ-2: Best Available Control Technology. Diesel construction equipment used during terrestrial construction shall be equipped with Tier 3 or Tier 4 CARB-certified off-road engines and 2010 on-road-compliant engines. | Terrestrial Project area | Construction equipment equipped with BACT | Implementing MM will reduce air quality impacts during construction | Applicant and CSLC | During construction |
| Increase of any criteria pollutant for which the Project region is non-attainment (cont.) | MM AQ-3: Fugitive Dust Mitigation. The following SLOAPCD fugitive dust MMs shall be implemented during terrestrial construction: Reduce the amount of the disturbed area, where possible. Use water trucks or sprinkler systems to prevent airborne dust from leaving the site. If wind speeds are more than 15 miles an hour, water more often. Use reclaimed (non-potable) water whenever possible. Spray all dirt stockpile areas everyday as needed. Implement permanent dust control measures identified in the approved Project revegetation and landscape plans as soon as possible once soil-disturbing activities are finished. Exposed ground areas that are planned to be reworked at dates greater than 1 month after initial grading should be sown with a fast-germinating, non-invasive grass seed, and watered until vegetation is established. | Terrestrial Project area | Implement SLOAPCD fugitive dust MMs during construction | Implementing MM will reduce air quality impacts during construction | Applicant and CSLC | During construction |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|------------------|--|----------|------------------------------------|---------------------------|----------------------|--------|
| Potential Impact | Mitigation Measure (MM) All disturbed soil areas not subject to revegetation should be stabilized using approved chemical soil binders, jute netting, or other methods approved in advance by the SLOAPCD. All roadways, driveways, and sidewalks to be paved should be completed as soon as possible. In addition, building pads should be laid as soon as possible after grading unless seeding or soil binders are used. Do not drive any construction vehicles more than 15 miles per hour on any unpaved surface at the construction site. Cover or maintain at least 2 feet of freeboard (minimum vertical distance between top of load and top of trailer) on all trucks hauling dirt, sand, soil, or other loose materials in accordance with California Vehicle Code section 23114. Install wheel washers where vehicles enter and exit unpaved roads onto streets, or wash off trucks and equipment leaving the site. Sweep streets at the end of each day if visible soil material is carried onto adjacent paved roads. Water sweepers | Location | Reporting | | | Timing |
| | with reclaimed water should be used where feasible. Show all of these fugitive dust MMs on grading and building plans. Designate a person or persons (by the contractor or builder) to monitor the | | | | | |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|--------------------------------------|--|-----------------|---|---|----------------------|-----------------------|
| | fugitive dust emissions and enhance implementing measures as necessary to minimize dust complaints, reduce visible emissions below 20 percent opacity (cloudiness), and prevent transport of dust offsite. Their duties shall include holidays and weekend periods when work may not be in progress. The name and telephone number of such persons shall be provided to the SLOAPCD Compliance Division prior to the start of any grading, earthwork, or demolition. | | | | | |
| Expose sensitive | Implement MM AQ-1: Standard Control N | | | i ipment (see abo | ove) | |
| receptors to | Implement MM AQ-2: Best Available Con | | | | | |
| substantial pollutant concentrations | Implement MM AQ-3: Fugitive Dust Mitig | ation (see abov | e) | | | |
| Concentrations | Biolo | gical Resourc | 202 | | | |
| Impacts on special- | MM BIO-1: Provide Worker | Terrestrial | Training | Implementing | Applicant and | Before, |
| status species and | Environmental Awareness Training. | Project area | materials | MM will | CSLC | during, and |
| habitats | The Applicant shall provide an environmental awareness training before starting construction activities for all construction personnel (including new personnel as they are added to the Project) working on the terrestrial and marine Project components. This training would be given by biological monitors and cultural monitors (approved by CSLC staff) to help the trainees understand the following: | | approved by CSLC staff 30 days before start of construction On-site monitor to submit list of trained personnel and | educate construction workers regarding special-status species and habitat | | after construction |
| | Surrounding common and special- status species and their habitats Applicable regulatory requirements | | training materials to CSLC after construction | | | |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|---|---|-----------------------------|--|---|----------------------|--------------------------------|
| | • MMs designed to avoid or minimize impacts on sensitive resource areas The training materials shall be developed and approved by the CSLC staff at least 30 days before starting Project activities in the terrestrial and marine work areas. The biological monitors shall maintain a list of all contractors who have been trained and shall submit this list and the final training material to CSLC staff within 30 days after construction starts and after construction is completed. The lead environmental monitor shall be the main contact for reporting any special-status species observed in or near the Project area by any employee or contractor. The Applicant shall provide the contact information for the lead environmental monitor and the biological monitors to on-site construction workers, USFW, CDFW, and CSLC staff before construction starts. | | | | | |
| Impacts on Special- Status Species and Habitats (cont.) | MM BIO-2: Conduct Biological Surveying and Monitoring. A biological monitor (typically with a college degree in a field of biology or environmental science, knowledge of species surveying for, and experience with pre-construction and construction monitoring), approved by CSLC staff, shall be present onsite to survey the work area for special-status wildlife species (e.g., California redlegged frog, western pond turtle, northern California legless lizard, Blainville's horned lizard, and two-striped garter snake) and nesting birds (as applicable) | Terrestrial Project area | On-site monitor to verify Submit daily monitoring report for work within CSLC's jurisdiction and weekly report for work outside CSLC's jurisdiction | Implementing MM will reduce the potential for impacts on special-status species and habitat | Applicant and CSLC | Before and during construction |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|---|---|-----------------------------|---|---|----------------------|--------------------------------|
| | prior to starting work in the terrestrial work area to minimize potential impacts on any special-status species or other wildlife that may be present during Project construction. | | | | | |
| | The biological monitor shall be onsite at all times during Project construction for all work west of the UPRR in and adjacent to natural habitats and not during work occurring east of the UPRR on city streets in developed areas. If at any time during Project construction, special-status species are observed in the Project area or within a predetermined radius surrounding the terrestrial Project components (as determined by the biological monitor), the biological monitor shall have the authority to stop all work, and the Applicant shall contact the appropriate agency, (i.e., CDFW or USFWS and CSLC staff) to discuss ways to protect the special-status species. | | | | | |
| | Construction monitoring reports for work under CSLC's jurisdiction shall be submitted daily and for work outside of the CSLC's jurisdiction shall be submitted weekly. | | | | | |
| Impacts on Special- Status Species and Habitats (cont.) | MM BIO-3: Delineate Work Limits to Protect Sensitive Biological Resources. Natural areas outside the construction work area shall not be disturbed. Before starting Project construction, the following areas shall be staked and flagged by the biological monitor (MM BIO-2), in coordination with the CSLC, and inspected throughout | Terrestrial Project area | On-site monitor to verify in coordination with CSLC | Implementing MM will reduce the potential for impacts on special-status species and habitat | Applicant and CSLC | Before and during construction |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|--|--|-----------------------------|---|---|----------------------|---------------------|
| Direct Impacts on | construction to ensure that they are visible for construction personnel: Identify construction work area limits at the cable landing site. Delineate bore pits and staging area (for equipment and fueling), and site these areas at least 100 feet from Meadow Creek. Mark areas using stakes and flags to identify environmentally sensitive areas (Meadow Creek and associated wetland and riparian communities) that would remain marked during construction. | Torrestrial | On site | Implementing | Applicant and | During |
| Direct Impacts on Sensitive Biological Resources | MM BIO-4: Install Metal Covers or Some Kind of Escape Ramps in Open Trenches. To prevent accidental entrapment of wildlife species during construction, all excavated holes and trenches that will be left open overnight shall have a metal cover or some kind of soil ramp installed, allowing wildlife an opportunity to exit. If escape ramps are installed, a biological monitor or the construction inspector (for work in developed areas east of the UPRR) shall inspect excavations before starting construction each day to confirm that no wildlife species are entrapped or to remove wildlife species that are unable to escape on their own. Any wildlife handling will be conducted under the biological monitor's applicable collection permit or as authorized by the appropriate wildlife agency. If a biological monitor is not present, the lead environmental monitor | Terrestrial Project area | On-site monitor to inspect daily before starting construction | Implementing MM will reduce the potential for impacts on special-status species and habitat | Applicant and CSLC | During construction |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|---|---|--------------------------|---|---|----------------------|--------------------------------|
| | for the Project would be contacted immediately to determine the appropriate course of action. | | | | | |
| Impacts from Horizontal Directional Drilling Activities | MM BIO-5: Implement Best Management Practices for Horizontal Directional Drilling Activities. A. When using the large marine HDD equipment to install landing pipes, the following shall be submitted to CSLC staff for review at least 60 days before starting construction: Engineering design drawings for construction certified by a Californiaregistered Civil/Structural Engineer. A site-specific geotechnical report certified (stamped, signed, and dated) by a California-registered Geotechnical Engineer, including boring logs and any geotechnical recommendations (including, but not limited to, identification of reasonably foreseeable risks during HDD installation and proposed risk mitigations) for safe HDD installation. If HDD is under CSLC jurisdiction, a minimum depth of 35 feet is required unless a shallower depth is recommended by a Californiaregistered Geotechnical Engineer. B. When using small HDD equipment to install the underground conduit system, do the following to reduce possible environmental impacts: Engineering design drawings for the underground conduit system | Terrestrial Project area | Submit geotechnical report to CSLC 60 days before starting construction On-site monitor to verify BMPs during construction | Implementing MM will reduce the potential for impacts on special-status species and habitat | Applicant and CSLC | Before and during construction |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|--|--|-----------------------------|---|---|----------------------|--------------------------------|
| Accidental Release of Drilling Fluid (Special-Status Species, Habitats, and Water Quality) | construction would be certified by a California registered Civil/Structural Engineer. • Prevent the underground conduit from becoming exposed by natural scour of the streambed by boring a minimum of 5 feet below the streambed of Meadow Creek. • Locate drill entry and exit points far enough from the banks of Meadow Creek to minimize impacts on the creek system. • Avoid removal of riparian vegetation along Meadow Creek between bore entry and exit points in preparation of trenchless stream crossing operations. MM BIO-6: Prepare and Implement an Inadvertent Return Contingency Plan. A Final Inadvertent Return Contingency Plan for the large and small HDD including the following objectives shall be submitted to CSLC staff for review at least 30 days before starting construction: • Measures to stop work, maintain appropriate control materials onsite, contain and remove drilling mud before demobilization, prevent further migration of drilling mud into the stream or waterbody, and notify all applicable authorities. • Control measures of constructing a dugout/ settling basin at the bore exit site to contain drilling mud to prevent sediment and other deleterious substances from entering waterbodies. | Terrestrial Project area | Submit Plan to CSLC 30 days before start of construction On-site monitor to verify during construction | Implementing MM will reduce the potential for impacts on special-status species and habitat | Applicant and CSLC | Before and during construction |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|-----------------------------|--|-----------------------------|--|--|----------------------|--------------------------------|
| Impacts on Nesting Birds | Workers shall monitor the onshore and offshore to identify signs of an inadvertent release of drilling fluids. Any abandonment contingency plans in case the HDD operations are forced to be suspended and a partially completed bore hole abandoned. Complete list of the agencies (with telephone number) to be notified, including but not limited to the CSLC's 24-hour emergency notification number (562) 590-5201, and the California Governor's Office of Emergency Services (Cal OES) contact number (800) 852-7550. MM BIO-7: Conduct Pre-Construction Nesting Bird Surveys and Implement Avoidance Measures. If construction occurs during the nesting season (typically from February 1 to September 1), the following conditions (designed to protect both special-status and non-special-status birds) shall be implemented: Areas within the terrestrial BSA: No more than 1 week before starting Project-related construction, a biological monitor, approved by CSLC staff, shall survey the non-developed natural areas within the Project area to look for nesting activity. Areas outside the terrestrial BSA: Areas outside the BSA (but within the line-of-sight from active construction) would be surveyed using binoculars | Terrestrial Project area | If construction occurs during nesting season, conduct surveys 1 week before start of construction On-site monitor to verify; coordination with USFWS/CDFW | Implementing MM will reduce the potential for impacts on nesting birds | Applicant and CSLC | Before and during construction |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|------------------|---|----------|------------------------------------|---------------------------|----------------------|--------|
| | and accessing within the public right-of- | | | | | |
| | way. | | | | | |
| | If no active nests are detected during | | | | | |
| | these surveys, no additional measures | | | | | |
| | are required. | | | | | |
| | If an active nest is found, an | | | | | |
| | appropriate avoidance buffer (based on | | | | | |
| | the species as explained below) would | | | | | |
| | be established around the nest site to | | | | | |
| | avoid disturbance or destruction of the | | | | | |
| | nest until the end of the breeding | | | | | |
| | season (generally August 31) or until | | | | | |
| | after biological monitor determines that | | | | | |
| | the young have fledged and moved out | | | | | |
| | of the area (this date varies by | | | | | |
| | species). Suitable buffer distances may | | | | | |
| | vary between species. The extent of | | | | | |
| | these buffers will be determined by the | | | | | |
| | biological monitor in coordination with | | | | | |
| | the applicable wildlife agency (i.e., | | | | | |
| | CDFW and/or USFWS), and will | | | | | |
| | depend on the bird species, level of | | | | | |
| | construction disturbance, line-of-sight | | | | | |
| | between the nest and the disturbance, | | | | | |
| | ambient levels of noise and other | | | | | |
| | disturbances, and other topographical | | | | | |
| | or artificial barriers. No disturbances | | | | | |
| | shall occur within the protective | | | | | |
| | buffer(s) until all young birds have | | | | | |
| | fledged, as confirmed by the biological | | | | | |
| | monitor. | | | | | |
| | A biological monitor shall be retained | | | | | |
| | by the Applicant (MM BIO-2) and shall | | | | | |
| | be onsite during construction activities | | | | | |
| | in non-developed areas of the Project | | | | | |
| | (west of the UPRR). | | | | | |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|----------------------------|---|------------------------|---|---|----------------------|-------------------------------|
| Entanglement of Wildlife | MM BIO-8: Inspection and Burial of Cable. The marine fiber optic cable shall be buried to the extent feasible in accordance with the following: Bury the cable to the extent practicable in areas with soft bottom substrate and water depths of 5,904 feet or less. Submit a burial report after each Project phase with detailed descriptions of all buried and unburied sections and justification for any unburied sections. | Marine Project area | Submit burial report after each Project phase | Implementing MM will reduce the potential for impacts on marine species | Applicant and CSLC | During and after construction |
| Impacts on Marine Wildlife | MM BIO-9: Cable Entanglements and Gear Retrieval. If fishers snag a cable and lose or cut gear, the Applicant shall use all feasible measures to retrieve the fishing gear or inanimate object. Retrieval shall occur no later than 42 days after discovering or receiving notice of the incident. If full removal of gear is not feasible, the Applicant shall remove as much gear as practicable to minimize harm to wildlife (e.g., fishes, birds, and marine mammals). Within 14 days of completing the recovery operation, the Applicant shall submit to CSLC staff a report describing the following: Nature and location of the entanglement (with a map) Method used for removing the entangled gear or object, or the method used for minimizing harm to wildlife if gear retrieval proves infeasible. | Marine Project area | Retrieval within 42 days of discovery Submit recovery report within 14 days of recovery completion | Implementing MM will reduce the potential for impacts on marine species | Applicant and CSLC | During and after construction |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|-------------------|---|----------------|------------------------------------|---------------------------|----------------------|--------------|
| Impacts on Marine | MM BIO-10: Prepare and Implement a | Marine Project | Submit Plan | Implementing | Applicant and | Before, |
| Mammals and Sea | Marine Wildlife Monitoring and | area | 60 days prior | MM will reduce | CSLC | during, and |
| Turtles | Contingency Plan. The Applicant shall | | to the start of | the potential | | after |
| | prepare and implement a Marine Wildlife | | marine | for impacts on | | construction |
| | Monitoring and Contingency Plan | | installation | marine wildlife | | |
| | (MWMCP) for installing or repairing | | activities | | | |
| | cables with the following elements, | | | | | |
| | procedures, and response actions: | | Qualified | | | |
| | Awareness training for Project vessel | | biologist to | | | |
| | crew that includes identification of | | provide | | | |
| | common marine wildlife and avoidance | | documentation | | | |
| | procedures included in the MWMCP for | | | | | |
| | Project activities. | | | | | |
| | Have two qualified shipboard marine | | | | | |
| | mammal observers onboard all cable | | | | | |
| | installation vessels during cable | | | | | |
| | installation activities. The MWMCP | | | | | |
| | shall establish the qualifications of and | | | | | |
| | required equipment for the observers. | | | | | |
| | In consultation with the National Marine | | | | | |
| | Fisheries Service, establish a safety | | | | | |
| | work zone around all Project work | | | | | |
| | vessels that defines the distance from | | | | | |
| | each work vessel that marine | | | | | |
| | mammals and sea turtles may | | | | | |
| | approach before all operations must | | | | | |
| | stop until the marine mammal or sea | | | | | |
| | turtle has moved beyond. | | | | | |
| | Project-specific control measures for | | | | | |
| | Project vessels (including support | | | | | |
| | vessels) and actions to be undertaken | | | | | |
| | when marine wildlife is present, such | | | | | |
| | as reduced vessel speeds or | | | | | |
| | suspended operations. | | | | | |
| | Reporting requirements and | | | | | |
| | procedures for wildlife sightings and | | | | | |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|---|---|---------------------|--|--|----------------------|---------------------|
| | contacts made to be reported in the post-installation reports. The MWMCP shall identify the resource agencies to be contacted in case of marine wildlife incidents and to receive reports at the conclusion of Project installation. The MWMCP shall be submitted to the CSLC and CCC for review at least 60 days before starting marine installation activities. | | | | | |
| Impacts on Hard Substrate Habitat Areas | MM BIO-11: Minimize Crossing of Hard Bottom Substrate. At least 30 days before starting construction of Phase 1, a pre-construction seafloor survey shall be conducted and provided to CSLC covering the proposed cable lease area and the temporary construction corridor (including construction vessels anchoring areas and depicting seafloor contours, all significant bottom features, hard bottom areas, sensitive habitats, the presence of any existing wellheads, pipelines, and other existing utilities) to identify any hard bottom habitat, eelgrass, kelp, existing utilities (including but not limited to pipelines), and power cables. The proposed cable routes and anchoring locations shall be set to avoid hard bottom habitat (to the extent feasible), eelgrass, kelp, existing utilities (including but not limited to pipelines), and power cables, as identified in the seafloor survey. | Marine Project area | Submit survey map at least 30 days before start of construction for Phase 1 | Implementing MM will reduce the potential for impacts on hard substrate habitat areas | Applicant and CSLC | Before construction |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|-------------------------------------|---|---------------------|--|--|----------------------|---|
| Impacts on Hard Substrate Organisms | MM BIO-12: Contribute Compensation to Hard Substrate Mitigation Fund. The following would be proposed if slow-growing hard substrate organisms are damaged: CCC compensation fees (based on past projects) will be required to fund the U.C. Davis Wildlife Health Center's California Lost Fishing Gear Recovery Project or other conservation programs for impacts on high-relief hard substrate affected by the Project. The amount of the hard bottom mitigation fee shall be calculated by applying a 3:1 mitigation ratio to the total square footage of affected hard bottom and multiplying that square footage by a compensation rate of \$14.30 per square foot. A final determination of the amount of high-relief hard substrate affected (used to calculate the total compensation fee) will be based on a review of the final burial report from the cable installation. The total assessment and methods used to calculate this figure will be provided to the CSLC and CCC for review and approval. Both the CSLC and CCC also will be provided documentation of the total amount of mitigation paid and the activities for which the funds will be used. | Marine Project area | Applicant will provide retirement verification to the CSLC | Compensation fees will help reduce impacts on hard substrate | Applicant | Immediately after Project construction and after determination based on final burial report |

Table 4-1. Mitigation Monitoring Program

| | Table 4-1. Willigation Monitoring 1 Togram | | | | | | | |
|--|--|-----------------|------------------------------------|------------------------------|----------------------|--------------|--|--|
| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing | | |
| Impacts on Native | MM BIO-13: Control of Marine | Marine Project | | Implementing | Applicant and | During | | |
| Species | Invasive Species. The Applicant shall | area | monitor to | MM will reduce | CSLC | construction | | |
| | ensure that the underwater surfaces of all Project vessels are clear of biofouling | | verify | the potential for impacts on | | | | |
| | organisms prior to arrival in State waters. | | | marine native | | | | |
| | The determination of underwater surface | | | species | | | | |
| | cleanliness shall be made in consultation | | | | | | | |
| | with CSLC staff. Regardless of vessel | | | | | | | |
| | size, ballast water for all Project vessels | | | | | | | |
| | must be managed consistent with | | | | | | | |
| | CSLC's ballast management regulations, | | | | | | | |
| | and Biofouling Removal and Hull | | | | | | | |
| | Husbandry Reporting Forms shall be | | | | | | | |
| | submitted to CSLC staff as required by regulation. No exchange of ballast water | | | | | | | |
| | for Project vessels shall occur in waters | | | | | | | |
| | shallower than the 5,904-foot isobath. | | | | | | | |
| Impacts on Wetlands | Implement MM BIO-5: Implement Best M | lanagement Pra | ctices for Horiz | ontal Direction | al Drilling Activi | ties (see | | |
| | above) | | | | . . | | | |
| | Implement MM BIO-6: Prepare and Imple | ement an Inadve | ertent Return C | ontingency Plar | າ (see above) | | | |
| Impacts on | Implement MM BIO-1 through MM BIO-13 | (see above) | | | | | | |
| Environmentally | | | | | | | | |
| Sensitive Areas | | | | | | | | |
| | | ural Resource | | | | | | |
| Disturbance of | MM CUL-1/TCR-1: Discovery of | Marine and | Qualified | Implementing | Applicant and | Prior to and | | |
| shipwrecks, | Previously Unknown Cultural or Tribal | | archaeologist, | MM will reduce | CSLC | throughout | | |
| Archaeological Sites, | Cultural Resources . In the event that potential cultural or tribal resources are | Project areas | tribal monitor, | potential | | construction | | |
| Historic, Cultural, or Tribal Cultural | uncovered during Project | | monitoring plan, and | impacts on archaeological | | | | |
| Resources | implementation, all earth-disturbing work | | treatment plan | resources | | | | |
| | within 100 feet of the find shall be | | if needed | . 55541 555 | | | | |
| | temporarily suspended or redirected until | | | | | | | |
| | an approved archaeologist and tribal | | | | | | | |
| | monitor, if retained, has evaluated the | | | | | | | |
| | nature and significance of the discovery. | | | | | | | |
| | In the event that a potentially significant | | | | | | | |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|------------------|---|----------|------------------------------------|---------------------------|----------------------|--------|
| | cultural or tribal cultural resource is discovered, Applicant, CSLC and any local, state, or federal agency with approval or permitting authority over the Project that has requested/required notification shall be notified within 48 hours. The location of any such finds must be kept confidential and measures shall be taken to secure the area from site disturbance and potential vandalism. Impacts to previously unknown significant cultural or tribal cultural resources shall be avoided through preservation in place if feasible. Damaging effects to tribal cultural resources shall be avoided or minimized following the measures identified in Public Resources Code section 21084.3, subdivision (b), if feasible, unless other measures are mutually agreed to by the lead archaeologist and culturally affiliated tribal monitor that would be as or more effective. A treatment plan, if needed to address a find, shall be developed by the archaeologist and, for tribal cultural resources, the culturally affiliated tribal monitor, and submitted to CSLC staff for review and approval prior to implementation of the plan. If the archaeologist or tribe determines that damaging effects on the cultural or tribal cultural resource shall be avoided or minimized, then work in the area may resume. | | | | | |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|------------------|---|----------|------------------------------------|---------------------------|----------------------|--------|
| | Title to all shipwrecks, archaeological sites, and historic or cultural resources on or in the tide and submerged lands of California is vested in the State and under CSLC jurisdiction. The final disposition of shipwrecks, archaeological, historical, and tribal cultural resources recovered on State lands under CSLC jurisdiction must be approved by the CSLC. | | | | | |
| | MM CUL-2/TCR-2: Cultural Resources Monitoring. Prior to Phase 1 ground-disturbing activities, the Applicant shall prepare a Cultural Resources Monitoring Plan subject to CSLC approval. The Plan shall include, but not be limited to, the following measures: The Applicant shall notify/invite a qualified archeologist and a representative of a California Native American tribe that is culturally affiliated to the Project site to monitor all ground disturbing activities in the Project site. The Applicant shall provide a minimum 5-day notice to the archeologist and tribal monitor prior to all activities requiring monitoring. The Applicant shall provide the archeologist and tribal monitor safe and reasonable access to the Project site. Guidance on identification of potential cultural resources that may be encountered. | | | | | |
| | The archeologist and Native American representative shall provide construction | | | | | |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|--|---|---------------------|--|--|----------------------|------------------------|
| | personnel with an orientation on the requirements of the Plan, including the probability of exposing cultural resources, guidance on recognizing such resources, and direction on procedures if a find is encountered. | | | | | |
| Disturbance of Marine Archaeological Resources | MM CUL-3: Conduct a Pre-Construction Offshore Archaeological Resources Survey. Using results of an acoustic survey (e.g., a CHIRP [compressed high-intensity radiated pulse] system survey) for evidence of erosion/incision of natural channels; the nature of internal channel-fill reflectors; and overall geometry of the seabed, paleochannels, and the surrounding areas will be analyzed for their potential to contain intact remains of the past landscape with the potential to contain prehistoric archaeological deposits. The analysis would include core sampling in various areas, including but not limited to, paleochannels to verify the seismic data analysis. Based on the CHIRP survey and coring data, a Marine Archaeological Resources Assessment Report shall be produced by a qualified maritime archaeologist and reviewed by the California Coastal Commission or the State Historic Preservation Officer and the CSLC to document effects on potentially historic properties. | Marine Project area | Qualified archaeologist, Marine Archaeological Resources Assessment Report, if needed | Implementing MM will reduce potential impacts on marine archaeological resources | Applicant and CSLC | Before construction |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|---|--|---------------------|--|--|--------------------|------------------------|
| Disturbance of Archaeological Resources (Offshore Historic Shipwrecks) | MM CUL-4: Conduct a Pre-Construction Offshore Historic Shipwreck Survey. A qualified maritime archaeologist, in consultation with the CSLC, shall conduct an archaeological survey of the proposed cable routes. The archaeological survey and analysis shall be conducted following current CSLC, Bureau of Ocean Energy Management (BOEM), and U.S. Army Corps of Engineers (San Francisco and Sacramento Districts) standard specifications for underwater/marine remote sensing archaeological surveys (Guidelines for Providing Geological and Geophysical, Hazards, and Archaeological Information Pursuant to 30 CFR part 585). | Marine Project area | Qualified maritime archaeologist | Implementing MM will reduce potential impacts on marine archaeological resources | Applicant and CSLC | Before construction |
| | The archaeological analysis shall identify and analyze all magnetic and side-scan sonar anomalies that occur in each cable corridor, defined by a lateral distance of 0.5 kilometer on each side of the proposed cable route. This analysis shall not be limited to side-scan and magnetometer data, and may include shallow acoustic (subbottom) data as well as autonomous underwater vehicle and multibeam data that may have a bearing on identification of anomalies representative of potential historic properties. The analysis shall include evaluation to the extent possible of the potential significance of each anomaly that cannot be avoided within the cable corridor. If sufficient data are not available | | | | | |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|---------------------------------------|--|------------------------|------------------------------------|--|-----------------------|--------------|
| | to identify the anomaly and make a recommendation of potential significance, the resource(s) shall be considered as potentially eligible for listing in the NRHP and CRHR, and treated as a historic property. If any cultural resources are discovered as the result of the marine remote sensing archaeological survey, the proposed cable route or installation procedures shall be modified to avoid the potentially historic property. BOEM administratively treats identified submerged potentially historic properties as eligible for inclusion in the NRHP under Criterion D, and requires project proponents to avoid them unless the proponent chooses to conduct additional investigations to confirm or refute their qualifying characteristics. BOEM typically determines a buffer (e.g., 50 meters) from the center point of any given find beyond which the project must be moved, in order to ensure that adverse effects on the potential historic property will be avoided | | | | | |
| Disturbance of | during construction. | Marina Project | Qualified | Implementing | Applicant and | Before |
| Marine Archaeological Resources | MM CUL-5: Prepare and Implement an Avoidance Plan for Marine Archaeological Resources. Pursuant to section 30106 and 30115 of the Coastal Act of 1976, "where developments would adversely impact archaeological resources as identified by the State Historic Preservation Officer, reasonable mitigation measures shall be required" (Pub. Resources Code, § 30244). An | Marine Project area | maritime archaeologist | Implementing MM will reduce potential impacts on marine archaeological resources | Applicant and CSLC | construction |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|------------------------------|--|-----------------------------|--|---|----------------------|-------------------------|
| Disturbance of Human Remains | avoidance plan, therefore, shall be developed and implemented to avoid all documented resources from the Marine Archaeological Resources Assessment Report and the Offshore Historic Shipwreck Survey Report, address discoveries of as yet unidentified resources encountered during the planned marine survey and construction, and provide mitigation monitoring if deemed necessary during construction to ensure compliance. MM CUL-6/TCR-3: Unanticipated Discovery of Human Remains. If human remains are encountered, all provisions provided in California Health and Safety Code section 7050.5 and California Public Resources Code section 5097.98 shall be followed. Work shall stop within 100 feet of the discovery, and both the archaeologist and CSLC staff must be contacted within 24 hours. The archaeologist shall consult with the County Coroner. If human remains are of Native American origin, the County Coroner shall notify the Native American Heritage Commission within 24 hours of this determination, and a Most Likely Descendent shall be identified. No work is to proceed in the discovery area until consultation is complete and procedures to avoid or recover the remains have been implemented. | Terrestrial Project area | Contact archaeologist and CSLC within 24 hours; archaeologist consults with County Coroner | Implementing MM will reduce potential impacts on human remains | Applicant and CSLC | Throughout construction |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|----------------------|--|-----------------|------------------------------------|---------------------------|----------------------|--------------|
| | Cultural | Resources - | Tribal | | | |
| | Implement MM CUL-1/TCR-1: Discovery | of Previously U | Inknown Cultur | al or Tribal Cult | ural Resources | (see above) |
| | Implement MM CUL-2/TCR-2: Cultural R | | | | | |
| | Implement MM CUL-6/TCR-3: Unanticipa | ted Discovery | of Human Rema | ains (see above) | | |
| | Greenho | use Gas Emis | ssions | | | |
| GHG Emissions | MM GHG-1: Purchase GHG Carbon | Up to 24 nm | Applicant will | Purchase of | Applicant | Before |
| during Construction | Offsets for Construction Emissions. | off the | provide | carbon offsets | '' | construction |
| | The Applicant shall purchase carbon | California | retirement | will reduce | | |
| | offsets equivalent to the Project's | coast | verification to | GHG | | |
| | projected GHG emissions (2,729 metric | | the CSLC | emissions | | |
| | tons CO2e) to achieve a net zero | | | impacts | | |
| | increase in GHG emissions during the | | | | | |
| | construction phase for emissions within | | | | | |
| | 24 nm (required only for 3 nm) of the | | | | | |
| | California coast. A carbon offset is a | | | | | |
| | credit derived from the reduction of GHG | | | | | |
| | emissions through a separate reduction | | | | | |
| | project, often in a different location from | | | | | |
| | the emission source. To be acceptable for | | | | | |
| | an emissions reduction credit, the carbon | | | | | |
| | offset must be permanent, quantifiable, | | | | | |
| | verifiable, and enforceable. Several | | | | | |
| | existing voluntary offset exchanges have | | | | | |
| | been validated by the CARB, including | | | | | |
| | the California Action Reserve Voluntary | | | | | |
| | Offset Registry, American Carbon | | | | | |
| | Registry, and Verified Carbon Standard. | | | | | |
| | The Applicant shall purchase all offsets | | | | | |
| | prior to groundbreaking and provide | | | | | |
| | copies of the offset retirement verification | | | | | |
| | to the CSLC. | | | | | |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting | Effectiveness Criteria | Responsible | Timing | | | | |
|---------------------------------|--|-----------------|--------------------------|---------------------------|-------------|--------------|--|--|--|--|
| • | | | Action | Criteria | Party | | | | | |
| Hazards and Hazardous Materials | | | | | | | | | | |
| | MM HAZ-1: Develop and Implement | Terrestrial and | | Implementing | Applicant; | Before and | | | | |
| Hazardous Materials | Spill Contingency and Hazardous | marine Project | | MM will reduce | Applicant's | during | | | | |
| | Materials Management and Plans. | areas | days prior to | potential for | Contractor | construction | | | | |
| | Prior to construction, the Applicant shall | | construction of | release of | | | | | | |
| | develop and implement Spill | | the offshore | hazardous | | | | | | |
| | Contingency and Hazardous Materials | | and onshore | materials into | | | | | | |
| | Management Plans (Plans) for onshore | | Project | the | | | | | | |
| | and offshore operations. They shall include, but not be limited to, procedures | | components | environment | | | | | | |
| | to be implemented, specific designation | | | | | | | | | |
| | of the on-site person who will have | | | | | | | | | |
| | responsibility for implementing the plans, | | | | | | | | | |
| | on-site spill response | | | | | | | | | |
| | materials/tools/equipment, and spill | | | | | | | | | |
| | notification protocol and procedures. | | | | | | | | | |
| | These Plans shall be submitted to CSLC | | | | | | | | | |
| | for review and approval 30 days before | | | | | | | | | |
| | construction begins. | | | | | | | | | |
| | A.Terrestrial Work: Measures for | | | | | | | | | |
| | terrestrial operations shall include, but | | | | | | | | | |
| | not be limited to, identification of | | | | | | | | | |
| | appropriate fueling and maintenance | | | | | | | | | |
| | areas for equipment, a daily | | | | | | | | | |
| | equipment inspection schedule, and | | | | | | | | | |
| | spill response procedures including | | | | | | | | | |
| | maintaining spill response supplies | | | | | | | | | |
| | onsite. | | | | | | | | | |
| | The terrestrial Plan will identify the | | | | | | | | | |
| | actions and notifications to occur if | | | | | | | | | |
| | evidence of soil contamination is | | | | | | | | | |
| | encountered during onshore | | | | | | | | | |
| | excavation. The Applicant shall notify | | | | | | | | | |
| | the County of San Luis Obispo County Environmental Health Services | | | | | | | | | |
| | | | | | | | | | | |
| | Division within 24 hours of discovery | | | | | | | | | |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|------------------|--|----------|------------------------------------|---------------------------|----------------------|--------|
| Potential Impact | of contaminated materials encountered during Project construction activities. Work in the area suspected of contamination shall stop until the notified agencies, together with the Applicant, have determined the next steps. The Plans will identify, at a minimum, implementing the following BMPs related to using hazardous substances: • Follow manufacturer's recommendations on use, storage, and disposal of chemical products used in construction • Avoid overtopping construction equipment fuel gas tanks • During routine maintenance of construction equipment, properly contain and remove grease and oils • Conduct all fueling of equipment at | Location | Reporting | | | Timing |
| | least 100 feet from wetlands and other waterbodies Properly dispose of discarded containers of fuels and other chemicals Maintain a complete list of the agencies to be notified (with their telephone number), including but not limited to, the CSLC's 24-hour emergency notification number (562) 590-5201 and the California Governor's Office of Emergency Services (Cal OES) contact number (800) 852-7550. | | | | | |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|--------------------------|--|---------------------------------|------------------------------------|---------------------------|----------------------|----------------|
| | B.Offshore Work: For offshore activities | | | | | |
| | involving work vessels, the primary | | | | | |
| | work vessel (dive support vessel) will | | | | | |
| | be required to carry on board a | | | | | |
| | minimum 400 feet of sorbent boom, 5 | | | | | |
| | bales of sorbent pads at least 18-inch | | | | | |
| | by 18-inch square, and a small | | | | | |
| | powered vessel for rapid deployment | | | | | |
| | to contain and clean up any small spill | | | | | |
| | or sheen on the water surface. The | | | | | |
| | Plans shall provide for the immediate | | | | | |
| | call out of additional spill containment | | | | | |
| | and clean-up resources in the event of | | | | | |
| | an incident that exceeds the rapid | | | | | |
| | clean-up capability of the on-site work | | | | | |
| | force. | | , | | | |
| | Implement MM BIO-1: Provide Environm | | | | , , , | |
| | Implement MM BIO-3: Delineate Work Lin | | | | | , , |
| | Implement MM BIO-5: Implement Best Ma | | | | | es (see above) |
| | Implement MM BIO-6: Prepare and Imple Hydrolog | ment an Inadve y and Water (| | ntingency Plan | (see above) | |
| Violation of Water | Implement MM BIO-3: Delineate Work Lin | | | gical Resources | (see above) | |
| Quality Standards | Implement MM BIO-5: Implement Best Ma | | | | | ies (see |
| | above) | - | | | J | ` |
| | Implement MM BIO-6: Prepare and Imple | ment an Inadve | ertent Return Co | ontingency Plan | (see above) | |
| | Implement MM HAZ-1: Develop and Imple | | | | | nt Plans (see |
| | above) | | | | | |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|--------------------|--|-----------------------------|------------------------------------|---|---|---------------------|
| | | Noise | | | | |
| Construction Noise | MM NOI-1 Construction Noise Control Plan. The Applicant shall ensure that its contractor develop a set of site-specific noise attenuation measures to ensure compliance with applicable City noise limits for the duration of the construction period. Before starting construction activities, the Applicant shall ensure that its contractor submits a Construction Noise Control Plan to the City for review and approval. Noise attenuation measures shall be identified in the Plan and implemented to meet a goal of keeping noise levels below the residential and commercial limits specified in the City's municipal code. Noise measures may include, but are not limited to, the following: • Require that all construction equipment powered by gasoline or diesel engines have sound control devices that are at least as effective as those originally provided by the manufacturer and that all equipment be operated and maintained to minimize noise generation. • Prohibit gasoline or diesel engines from having unmuffled exhaust systems. • Ensure that equipment and trucks for Project construction use the best available noise control techniques (e.g., improved mufflers, redesigned equipment, intake silencers, ducts, engine enclosures, acoustically | Terrestrial Project area | Contract specifications | Implementing MM will reduce construction noise impacts on sensitive receptors | Applicant; Applicant's contractor | During construction |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|------------------|---|----------|------------------------------------|---------------------------|----------------------|--------|
| | attenuating shields or shrouds) | | | | | |
| | wherever feasible. Acoustically | | | | | |
| | attenuating shields would be | | | | | |
| | appropriate for activities at the cable | | | | | |
| | landing site, where construction will be | | | | | |
| | stationary for a few weeks. According | | | | | |
| | to the Federal Highway Administration, | | | | | |
| | the use of shields or barriers around | | | | | |
| | noise sources can reduce noise by 5 to | | | | | |
| | 10 dBA, depending on the type of | | | | | |
| | barrier used. | | | | | |
| | Use "quiet" gasoline powered or cleatrically payored compressors as | | | | | |
| | electrically powered compressors as | | | | | |
| | well as electric rather than gasoline or | | | | | |
| | diesel powered forklifts for small lifting, where feasible. | | | | | |
| | Locate stationary noise sources, such | | | | | |
| | as temporary generators, concrete | | | | | |
| | saws, and crushing/processing | | | | | |
| | equipment, as far from nearby | | | | | |
| | receptors as possible. Muffle and | | | | | |
| | enclose noise sources within temporary | | | | | |
| | enclosures and shield with barriers | | | | | |
| | which could reduce construction noise | | | | | |
| | by as much as 5 dB. Or implement | | | | | |
| | other measures, to the extent feasible. | | | | | |
| | Undertake the noisiest activities during | | | | | |
| | times of least disturbance to | | | | | |
| | surrounding residents and occupants, | | | | | |
| | such as in the late morning, the middle | | | | | |
| | of the day, or early afternoon. | | | | | |
| | In response to noise complaints | | | | | |
| | received from people in the Project | | | | | |
| | area, monitor the effectiveness of | | | | | |
| | noise attenuation measures by taking | | | | | |
| | noise measurements and adjusting | | | | | |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|------------------------|---|-----------------------------|---|--|----------------------|---------------------|
| | the measures as necessary to reduce complaints. | | | | | |
| Construction Vibration | MM NOI 2: Construction Vibration Notification and Disturbance Coordinator. The Applicant shall provide advance written notification (via flyer) 15 days prior to the start of proposed construction activities to all residences and other sensitive uses within 80 feet of the construction site. Notification will include a brief overview of the Project and its purpose, proposed construction activities, schedule, and name and contact information of the Project manager or another designee responsible for ensuring that reasonable measures are implemented to address complaints received. The Applicant shall designate a representative to act as construction vibration disturbance coordinator responsible for resolving construction vibration concerns. They will be available during regular business hours to monitor and respond to concerns. If construction hours are extended, they also will be available during the extended hours. If a vibration complaint is received, they will be responsible for determining the cause of the complaint and ensuring that all reasonable measures are implemented to address the problem. | Terrestrial Project area | Provide advance written notification 15 days prior to start of activities to residences and other sensitive uses within 80 feet of construction | construction vibration impacts on sensitive receptors and provide notification | contractor | Before construction |
| | Implement MM BIO-10: Prepare and Impl | ement a Marine | e vviialite Monito | oring and Contil | ngency Plan (se | e apove) |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|-----------------------|---|---------------------|--|--|----------------------|---------------------|
| | | Recreation | | | | |
| Offshore Recreation | MM REC-1: Advanced Local Notice to Mariners. All offshore operations shall be described in a Local Notice to Mariners to be submitted to the U.S. Coast Guard (USCG) at least 15 days before offshore cable laying activities or repair activities. A copy of the published notice shall be immediately provided to the CSLC. The notice shall include: Type of operation (i.e., dredging, diving operations, construction). Specific location of operation or repair activities (including whether there is a possibility of exposed cable), including latitude and longitude and geographical position, if applicable Estimated schedule of activities (operation or repair), including start and completion dates (if these dates change, the USCG needs to be notified) Vessels involved in the operation VHF-FM radio frequencies monitored by vessels on the scene. Point of contact and 24-hour phone number Chart Number for the area of operation | Marine Project area | Local Notice to Mariners submitted to USCG 15 days before offshore cable laying activities Published notice submitted to CSLC immediately | Implementing MM will reduce project impacts on offshore recreation | Applicant and CSLC | Before construction |
| Marine Vessel Traffic | Implement MM REC-1: Advanced Local N | | ers (see above) | | | |
| | Implement APM-2: Marine Anchor Plan (| see below) | | | | |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|----------------------------------|---|---------------------|---|---------------------------|---|-----------------------------------|
| | Commercial Fig | shing and Mai | rine Anchors | | | |
| Disruption of Commercial Fishing | APM-1: Fishing Agreement. The Applicant will enact a fishing agreement, or will join an existing fishing agreement, that will serve to minimize potential impacts on the viability of the commercial fishing industry. This agreement would, in part, establish the following: • A cable/fishing liaison committee that would manage the interactions between the fishers and the cable companies • Policies for how the fishers will work around the cables and what to do if they think their fishing gear is hung up on a cable or similar issue • Methods of gear replacement and costs claims in the unlikely event that fishing gear is entangled in cable owned by the Applicant • Design and installation procedures to minimize impacts on fishing activities, such as: ° Burying cable where possible ° Allowing fishing representatives to review marine survey data and participate in cable alignment selection • Communication and notification procedures • Contributions to fishing improvement funds | Marine Project area | Provide Agreement to the CSLC prior to construction | | Applicant; Applicant's contractor | During construction and operation |

Table 4-1. Mitigation Monitoring Program

| Potential Impact | Mitigation Measure (MM) | Location | Monitoring/ Reporting Action | Effectiveness Criteria | Responsible Party | Timing |
|------------------|--|-----------------------------------|---|---|---|--------------------------------|
| Marine Anchoring | APM-2: Marine Anchor Plan. At least 30 days before starting construction, the Applicant will submit a Marine Anchor Plan to CSLC staff for review with the following: Map of the proposed acceptable anchor locations and exclusion zones or offshore temporary anchoring or mooring for work vessels. Narrative description of the anchor setting and retrieval procedures to be employed that will result in minimal impacts on the ocean bottom. Please note that anchor dragging along ocean bottom is not allowed. Coordinates of all dropped anchor points during construction shall be recorded and included on the post construction seafloor survey map. | Marine anchoring areas only | Provide Plan to the CSLC 30 days before starting construction | Implementing this APM will ensure safety for anchoring operations | Applicant; Applicant's contractor | Before and during construction |

Terms:

APM = Applicant proposed measure

Applicant = RTI Infrastructure, Inc.

AUV = autonomous underwater vehicle BACT = best available control technology

BMP = best management practice

BOEM = Bureau of Ocean Energy Management

BSA = biological study area

CARB = California Air Resources Board CCC = California Coastal Commission

CDFW = California Department of Fish and Wildlife

CFR = Code of Federal Regulations

CLP = cable landing parcel

CO₂e = CO₂ equivalent

CSLC = California State Lands Commission ESHA = environmentally sensitive habitat area

GHG = greenhouse gas

HDD = horizontal directional drilling

nm = nautical miles

NMFS = National Marine Fisheries Service

SLOAPCD = San Luis Obispo Air Pollution Control District

USACE = U.S. Army Corps of Engineers

USCG = U.S. Coast Guard

USFWS = U.S. Fish and Wildlife Service