CALIFORNIA COASTAL COMMISSION

South Coast District Office 301 E Ocean Blvd., Suite 300 Long Beach, CA 90802-4302 (562) 590-5071



W8b

5-22-0993 (Miltimore) MAY 10, 2023

EXHIBITS

Table of Contents:

Exhibit 1 – Vicinity Map and Project Site


Exhibit 2 – Project Plans

Exhibit 3 - CoSMoS Flood Map Analyses

Exhibit 4 – Mobile Home Removal Plan







ORANGE COUNTY ASSESSOR'S MAP

R/W=RIGHT OF WAY HP=HIGH POINT DWY=DRIVEWAY S/W=SIDEWALK PP=POWER POLE FL=FLOW LINE FH=FIRE HYDRANT BG=GRADE BREAK INV=INVERT ♥ =CENTERLINE PL=PROPERTY LINE **FS=FINISH SURFACE** FG=FINISH GRADE NG=NATURAL GROUND EDR=EDGE OF DIRT ROAD EOP=EDGE OF PAVEMENT TD=TOP OF AC DYKE

LEGEND:

W=WATER

EX=EXISTING

WV=WATER VALVE —O—O— =FENCE LINE

COVER SHEET CITY OF SEAL BEACH

OWNER: DIANE MITIMORE 1 COTTONWOOD LANE **SEAL BEACH SHORES** SEAL BEACH CA 90740 C/O MIKE TAYLOR, PMH 951 845-2671

CONTRACTOR: SAV-ON HOMES 1415 EAST 6TH. STREET BEAUMONT, CA 92223 951 845-2671 savonmike@gmail.com

MFGR./SUPPLIER:

savonmike@gmail.com PROPERTY DESCRIPTION:

The site is one of the 125 mobile home sites within Seal Beach Shores Mobile Home Park located between the first public road and the sea (San Gabriel River). The Park is bounded by the San Gabriel River to the north, with a revetment levee and the San Gabriel River Bike Trail between the Park and the River.

PROJECT DESCRIPTION:

Remove an existing mobile home and install a new 648 sq. ft. mobile home with entry stairs and handicap ramp.

USE & OCCUPANCY: CONTENTS: INTENDED USE SFR SHEET NO.

TYPE OF CONSTRUCTION:

MANUFACTURED HOME

TOTAL AREA:

TOTAL AREA

648 SQUARE FEET

COVER SHEET 2 **ELEVATIONS**

FLOOR PLAN

4 PARCEL MAP

VENTING FLOOD DETAIL

SITE PLAN

NOTES:

-THIS HOME WAS ENGINEERED, CONSTRUCTED AND INSPECTED IN CONFORMANCE WITH THE FEDERAL MANUFACTURED HOME CONSTRUCTION AND SAFETY STANDARDS (MHCSS)
OF THE US DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT (24CFR PART 3280, COMMONLY REFERRED TO AS THE "HUD" CODE) IN EFFECT ON THE DATE OF MANUFACTURE. -THIS HOME AND ITS INSTALLATION ALSO COMPLIES WITH THE REQUIREMENTS FOR 2019 CBC AND 2019 CALIFORNIA ADMINISTRATION CODE TITLE 25. AND STATE OF CALIFORNIA HEALTH AND SAFETY CODE 18551

-THIS HOME IS WILDERNESS-URBAN INTERFACE (WUI) COMPLIANT PER CALIFORNIA CODE OF REGULATIONS CHAPTER 3 AND TITLE 24 CALIFORNIA CODE OF REGULATIONS PART 2, MATERIALS AND CONSTRUCTION METHODS FOR WILDEIRE EXPOSURE

-THIS HOME IS NOT REQUIRED OR EQUIPPED WITH SOLAR POWER, ELECTRICAL ENERGY GENERATION OR STORAGE EQUIPMENT.

NOTE: UNLESS SPECIFIED ALL DRAWINGS ARE NOT TO SCALE

BUILDING AND SAFETY APPROVED

REVIEWED FOR SUBSTANTIAL COMPLIANCE ONLY SUBJECT TO FURTHER REVIEW AND CORRECTIONS. VIOLATION OF APPLICABLE CODES. LAWS OR ORDINANCES IS STRICTLY PROHIBITED DESPITE CONTENTS OF THESE PLANS. ALL REVISIONS OR DEVIATIONS FROM THESE PLANS REQUIRE PRIOR BUILDING OFFICIAL APPROVAL.

> 2/15/2023, 8:23:09 PM SEALB-B2022-1508

Sav-On Manufactured Homes

-o---o- =DAYLIGHT LINE -EDR- =EDGE OF DIRT ROAD

1415 E. 6TH. Street Beaumont, California 92223 (951) 845-2671 LICENSE NO. 295359



COVER SHEET
DIANE MITIMORE RESIDENCE


MILLIMONE RESIDE
1 COTTONWOOD LANE
SEAL BEACH SHORES
SEAL BEACH CA. 90740

	DRAWN BY	REV	DATE	DESCRIPTION
		N/C	7/26/21	NEW DRAWING, NO REVS.
ĺ	DATE			


Exhibit 2

Page 1 of 7









Manufactured Home ELEVATIONS

SCALE:NONE

BUILDING AND SAFETY APPROVED

REVIEWED FOR SUBSTANTIAL COMPLIANCE ONLY. SUBJECT TO FUTHER REVIEW AND CORRECTIONS. VIOLATION OF APPLICABLE CODES, LAWS OR ORDINANCES IS STRICTLY PROHIBITED DESPITE CONTENTS OF THESE PLANS. ALL REVISIONS OR DEVIATIONS FROM THESE PLANS REQUIRE PRIOR BUILDING OFFICIAL APPROVAL.

> 2/15/2023, 8:23:09 PM SEALB-B2022-1508

Sav-On Manufactured Homes

1415 E. 6TH. StreetBeaumont, California 92223 (951) 845-2671



COUNTY OF ORANGECITY OF SEAL BEACH


ELEVATIONS
DIANE MITIMORE RESIDENCE
1 COTTONWOOD LANE
SEAL BEACH, CA 90740
SEAL BEACH SHORES PARK

	REV	DATE	DESCRIPTION				
Ε	NC	5/18/22	NEW DRAWING, NO REVISIONS				

Exhibit 2

Page 2 of 7





Manufactured Home FLOOR PLAN

 $SCALE \frac{1}{4}' = 1'-0"$

BUILDING AND SAFETY APPROVED

REVIEWED FOR SUBSTANTIAL COMPLIANCE ONLY.
SUBJECT TO FURTHER REVIEW AND CORRECTIONS.
VIOLATION OF APPLICABLE CODES, LAWS OR
ORDINANCES IS STRICTLY PROHIBITED DESPITE
CONTENTS OF THESE PLANS, ALL REVISIONS OR
DEVIATIONS FROM THESE PLANS REQUIRE PRIOR
BUILDING OFFICIAL APPROVAL.

2/15/2023, 8:23:09 PM SEALB-B2022-1508

Sav-On Manufactured Homes

1415 E. 6TH. StreetBeaumont, California 92223 (951) 845-2671



COUNTY OF ORANGECITY OF SEAL BEACH


FLOOR PLAN
DIANE MITIMORE RESIDENCE
1 COTTONWOOD LANE
SEAL BEACH, CA 90740
SEAL BEACH SHORES PARK


	REV	DATE	DESCRIPTION
Έ	NC	5/18/22	NEW DRAWING, NO REVISIONS


Exhibit 2


Page 3 of 7















SoCal Professional Engineers, Inc.

Engineering, Planning, Surveying, Construction Management

March 8, 2023

California Coastal Commission

Re: Application No. 5-22-0993, 1 Cottonwood Lane, Seal Beach, CA

To whom it may concern,

The following is our proposed removal plan for the existing Manufactured Home at the above referenced site.

Day 1: The removal of personal items including but not limited to the following:

- Furniture, kitchen items, clothes, etc...
- Fixed heavy items such as stoves, heavy/large furniture need not be removed.

Day 2: Disconnect all utilities (Electrical, Sewage, Water, Gas, Cable, and Telephone)

Day 3: The preparation of the mobile for removal from site location. All skirting, stairs and handicap ramp will be disconnected from structure and removed. The components of these structures will be situated inside the mobile home. HCD permit will not be required.

Day 4: Separation of mobile home from site. Sections of mobile home disconnected by removing lag bolts at floor and truss locations. Remove steel piers and install axles, wheels/tires and towing hitch. If needed, installation of shipping plastic at open sides of mobile home to prevent water incursion. Attach mobile home to a transport vehicle and remove from mobile home park. HCD permit not required.

No staging area will be required as all work to be performed during preparation for transport will be performed on mobile home site. No engineering will be required for the deconstruction and removal of mobile home and accessory structures. Basic tools will be used for the removal of mobile home such as hammers, pry bars, cordless drill/impact wrenches, air compressors and pneumatic tools. Steel foundation piers and skirting will be loaded on a flatbed truck and removed from the site.

This above completes the removal plan.

KHALED FARAH, SCPE, INC Digitally signed by KHALED FARAH, SCPE, INC DN: cn=KHALED FARAH, SCPE, INC, o=Socal Professional Engineers, Inc., ou, email=info@rca-pe.com, c=US Date: 2023.03.08 14:32:47 -08:00'

Khaled Farah RCE-83128; Exp. 03.31.2025



Exhibit 4

Page 1 of 1

